BASELINE SUMMARY TABLE 17.5

Table 17.5 Summary of Baseline Daylight and Sunlight Results

Address	Total No. Windows that meet VSC criteria (>27%)		Total No. of Rooms that receive NSL in excess of 80%		Total no. of windows that meet APSH criteria	
	Pass	Total	Pass	Total	Pass	Total
3 NORTHUMBERLAND PARK	6	6	5	6	4	4
5 NORTHUMBERLAND PARK	4	4	4	4	4	4
7 NORTHUMBERLAND PARK	2	2	2	2	2	2
9 NORTHUMBERLAND PARK	2	2	2	2	2	2
11 NORTHUMBERLAND PARK	2	2	2	2	2	2
13 NORTHUMBERLAND PARK	4	4	4	4	4	4
15 NORTHUMBERLAND PARK	4	4	4	4	4	4
17 NORTHUMBERLAND PARK	4	4	4	4	4	4
19 NORTHUMBERLAND PARK	4	4	4	4	4	4
21 NORTHUMBERLAND PARK	2	2	2	2	2	2
23 NORTHUMBERLAND PARK	2	9	7	7	7	7
19 BENNETS CLOSE	2	3	2	3	3	3
9-13 BENNETS CLOSE	22	32	23	24	32	32
705 HIGH ROAD	10	12	9	9	0	0
ST FRANCAIS DE SALES RC PRIMARY SCHOOL	44	54	19	22	6	6
729 HIGH ROAD	18	26	11	12	11	11
4-18 BRERETON ROAD	20	40	27	40	0	0
LIBRARY-KATHLEEN FERRIER COURT	60	79	31	32	22	25
731 HIGH ROAD	4	4	4	4	0	0
733 HIGH ROAD	4	4	4	4	0	0
735 HIGH ROAD	5	5	4	5	0	0
737 HIGH ROAD	4	4	4	4	0	0
739 HIGH ROAD	4	4	4	4	0	0
741 HIGH ROAD	7	7	6	6	0	0
743 HIGH ROAD	4	4	4	4	0	0
745 HIGH ROAD	5	5	4	4	0	0
747 HIGH ROAD	4	4	4	4	0	0
749 HIGH ROAD	5	5	4	4	0	0
751 HIGH ROAD	4	4	4	4	0	0
753 HIGH ROAD	4	4	4	4	0	0
755 HIGH ROAD	4	4	4	4	0	0
757 HIGH ROAD	4	4	4	4	0	0
759 HIGH ROAD	11	13	6	6	0	0
BERGAN-BROOKLYN APPARTMENTS	38	66	35	36	28	28
769 HIGH ROAD	4	4	4	4	0	0
771 HIGH ROAD	4	4	4	4	0	0
771a HIGH ROAD	1	1	1	1	0	0
773 HIGH ROAD	4	4	5	5	0	0
775 HIGH ROAD	4	4	4	4	0	0

Address	Total No. Windows that meet VSC criteria (>27%)		Total No. of Rooms that receive NSL in excess of 80%		Total no. of windows that meet APSH criteria	
	Pass	Total	Pass	Total	Pass	Total
777-779-781 HIGH ROAD	8	8	8	8	0	0
783 HIGH ROAD	5	7	5	7	1	3
785 HIGH ROAD	4	4	4	4	0	0
787 HIGH ROAD	4	4	4	4	0	0
789 HIGH ROAD	4	4	4	4	0	0
791 HIGH ROAD	12	12	6	6	0	0
793-795 HIGH ROAD (BANK)	24	24	13	14	24	24
797 HIGH ROAD	4	4	4	4	4	4
799 HIGH ROAD	4	4	4	4	4	4
801 HIGH ROAD	4	4	4	4	4	4
803 HIGH ROAD	8	8	4	4	8	8
805 HIGH ROAD	4	4	0	2	4	4
809 HIGH ROAD	7	7	4	4	7	7
813 HIGH ROAD	4	4	2	2	4	4
815 HIGH ROAD	4	4	2	2	4	4
817 HIGH ROAD	2	2	2	2	2	2
819 HIGH ROAD	8	8	4	4	9	9
821 HIGH ROAD	4	4	2	2	4	4
823 HIGH ROAD	6	6	3	3	6	6
825 HIGH ROAD	2	2	1	1	2	2
827 HIGH ROAD	2	2	1	1	0	0
820 HIGH ROAD	2	2	2	2	0	0
814 HIGH ROAD	9	9	6	6	8	10
808 HIGH ROAD	11	11	9	9	0	0
806b HIGH ROAD	7	7	4	4	7	7
806 HIGH ROAD	5	8	8	8	0	0
804 HIGH ROAD	8	12	8	9	2	2
794 HIGH ROAD	7	19	9	11	0	1
790 HIGH ROAD	11	12	11	12	0	0
7 WHITE HART LANE	1	1	1	1	0	0
9-39 WHITE HART LANE	1	4	4	4	0	0
8 WILLIAM STREET	5	9	9	9	0	0
1 MOSELLE STREET	3	3	3	3	0	0
ERMINE HOUSE	11	12	6	6	3	3
29 NORTHUMBERLAND PARK	5	7	5	6	4	4
31 NORTHUMBERLAND PARK	4	7	3	5	3	3
33 NORTHUMBERLAND PARK	2	5	3	4	3	3
35 NORTHUMBERLAND PARK	2	4	2	4	3	3
37 NORTHUMBERLAND PARK	2	7	3	5	3	3
39 NORTHUMBERLAND PARK	2	12	3	4	3	3
41 NORTHUMBERLAND PARK	3	6	4	4	3	3

Address	Total No. Windows that meet VSC criteria (>27%)		Total No. of Rooms that receive NSL in excess of 80%		Total no. of windows that meet APSH criteria	
	Pass	Total	Pass	Total	Pass	Total
43 NORTHUMBERLAND PARK	3	6	4	4	3	3
45 NORTHUMBERLAND PARK	3	7	5	5	4	4
47 NORTHUMBERLAND PARK	3	7	3	4	3	3
49 NORTHUMBERLAND PARK	3	5	3	4	3	3
51 NORTHUMBERLAND PARK	3	4	3	4	3	3
53 NORTHUMBERLAND PARK	2	3	2	3	2	2
55 NORTHUMBERLAND PARK	2	2	2	2	2	2
57 NORTHUMBERLAND PARK	16	21	8	8	16	16
BURLEIGH COURT	19	20	19	20	18	18
50 NORTHUMBERLAND PARK	9	13	4	9	6	7
52 NORTHUMBERLAND PARK	8	8	7	8	8	8
2 WORCESTER AVENUE	5	5	4	4	0	0
4 WORCESTER AVENUE	4	4	4	4	0	0
6 WORCESTER AVENUE	4	4	4	4	0	0
8 WORCESTER AVENUE	4	5	4	4	0	0
10 WORCESTER AVENUE	4	5	4	4	1	1
12 WORCESTER AVENUE	4	5	4	4	0	0
14 WORCESTER AVENUE	3	4	4	4	0	0
16 WORCESTER AVENUE	4	4	4	4	0	0
18 WORCESTER AVENUE	3	4	4	4	0	0
1 WORCESTER AVENUE	19	24	7	8	6	6
3 WORCESTER AVENUE	11	16	4	4	5	5
5 WORCESTER AVENUE	11	16	4	4	5	5
7 WORCESTER AVENUE	10	16	4	4	5	5
9 WORCESTER AVENUE	10	16	4	4	5	5
11 WORCESTER AVENUE	10	16	4	4	5	5
13 WORCESTER AVENUE	9	15	4	4	5	5
15 WORCESTER AVENUE	9	16	4	5	5	5
17 WORCESTER AVENUE	9	15	3	4	12	15
19 WORCESTER AVENUE	10	15	4	4	12	15
21 WORCESTER AVENUE	12	16	4	4	13	16
23 WORCESTER AVENUE	10	16	4	4	13	16
25 WORCESTER AVENUE	11	17	4	4	14	17
27 WORCESTER AVENUE	7	20	4	4	6	20
29 WORCESTER AVENUE	11	14	3	4	11	14
31 WORCESTER AVENUE	9	17	3	4	10	17
33 WORCESTER AVENUE	9	17	3	4	10	17
35 WORCESTER AVENUE	10	17	3	4	10	17
37 WORCESTER AVENUE	11	17	3	4	11	17
39 WORCESTER AVENUE	14	16	4	4	15	16
41 WORCESTER AVENUE	23	29	5	5	24	29

Address	Total No. Windows that meet VSC criteria (>27%)		Total No. of Rooms that receive NSL in excess of 80%		Total no. of windows that meet APSH criteria	
	Pass	Total	Pass	Total	Pass	Total
NORTHUMBERLAND PARK COMMUNITY SCHOOL	16	20	5	5	15	15
ST PAUL-S AND ALL HALLOWS INFANT SCHOOL	27	37	17	23	30	32
56 PARK LANE	6	6	4	4	0	0
54 PARK LANE	4	4	4	4	0	0
52 PARK LANE	4	4	4	4	0	0
50 PARK LANE	3	4	1	5	0	0
48 PARK LANE	0	4	0	4	0	0
44 PARK LANE	0	9	0	4	0	0
42 PARK LANE	0	8	0	4	0	0
40 PARK LANE	0	9	0	4	0	0
38 PARK LANE	0	9	0	4	0	0
36 PARK LANE	0	21	0	4	0	0
34 PARK LANE	0	8	0	4	0	0
32 PARK LANE	0	9	0	4	0	0
30 PARK LANE	0	10	0	3	0	0
28 PARK LANE	0	9	0	4	0	0
1 LANCASTER CLOSE	1	11	7	8	3	5
2 LANCASTER CLOSE	4	6	5	6	2	2
3 LANCASTER CLOSE	3	3	3	3	0	0
CONCORD HOUSE	23	103	38	70	0	0
2-2a PARK LANE	3	5	1	4	0	0
2 VICARAGE ROAD	2	2	2	2	0	0
28 BROMLEY ROAD	4	4	2	2	2	2
29 BROMLEY ROAD	4	5	2	2	0	0
38 BROMLEY ROAD	2	2	2	2	0	2
COOMBES HOUSE	44	50	28	33	1	1
TOTAL	**1056**	**1589**	**766**	**917**	**594**	**674**

**Note: With regards to the APSH assessment, those properties that have a total of 0 windows assessed are north facing and therefore not applicable to the assessment.*

DAYLIGHT SUMMARY TABLE 17.6

Table 17.6 Summary of Daylight results for Project

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
3 NORTHUMBERLAND PARK	6	6	0	0	0	0	6	6	0	0	0	0
5 NORTHUMBERLAND PARK	4	4	0	0	0	0	4	4	0	0	0	0
7 NORTHUMBERLAND PARK	2	2	0	0	0	0	2	2	0	0	0	0
9 NORTHUMBERLAND PARK	2	2	0	0	0	0	2	2	0	0	0	0
11 NORTHUMBERLAND PARK	2	2	0	0	0	0	2	2	0	0	0	0
13 NORTHUMBERLAND PARK	4	4	0	0	0	0	4	4	0	0	0	0
15 NORTHUMBERLAND PARK	4	4	0	0	0	0	4	4	0	0	0	0
17 NORTHUMBERLAND PARK	4	4	0	0	0	0	4	4	0	0	0	0
19 NORTHUMBERLAND PARK	4	4	0	0	0	0	4	4	0	0	0	0
21 NORTHUMBERLAND PARK	2	2	0	0	0	0	2	2	0	0	0	0
23 NORTHUMBERLAND PARK	9	9	0	0	0	0	7	7	0	0	0	0
19 BENNETS CLOSE	3	3	0	0	0	0	3	3	0	0	0	0
9-13 BENNETS CLOSE	32	32	0	0	0	0	24	24	0	0	0	0
705 HIGH ROAD	12	12	0	0	0	0	9	9	0	0	0	0
ST FRANCAIS DE SALES RC PRIMARY SCHOOL	54	37	17	0	0	17	22	14	5	2	1	8
729 HIGH ROAD	26	9	4	9	4	17	12	9	2	1	0	3
4-18 BRERETON ROAD	40	33	3	4	0	7	40	32	6	2	0	8
LIBRARY-KATHLEEN FERRIER COURT	79	20	7	8	44	59	32	15	2	9	5	16
731 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
733 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
735 HIGH ROAD	5	1	0	0	4	4	5	0	0	0	5	5
737 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
739 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
741 HIGH ROAD	7	1	0	0	6	6	6	0	0	0	6	6
743 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
745 HIGH ROAD	5	0	0	0	5	5	4	0	0	0	4	4
747 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
749 HIGH ROAD	5	0	0	0	5	5	4	0	0	0	4	4
751 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
753 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
755 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
757 HIGH ROAD	4	0	0	0	4	4	4	0	0	0	4	4
759 HIGH ROAD	13	2	0	2	9	11	6	0	0	4	2	6
BERGAN-BROOKLYN APPARTMENTS	66	37	5	12	12	29	36	29	4	2	1	7
769 HIGH ROAD	4	2	2	0	0	2	4	2	2	0	0	2
771 HIGH ROAD	4	2	2	0	0	2	4	1	3	0	0	3
771a HIGH ROAD	1	0	1	0	0	1	1	1	0	0	0	0
773 HIGH ROAD	4	4	0	0	0	0	5	5	0	0	0	0
775 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
777-779-781 HIGH ROAD	8	8	0	0	0	0	8	8	0	0	0	0
783 HIGH ROAD	7	7	0	0	0	0	7	7	0	0	0	0

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
785 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
787 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
789 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
791 HIGH ROAD	12	12	0	0	0	0	6	6	0	0	0	0
793-795 HIGH ROAD (BANK)	24	24	0	0	0	0	14	14	0	0	0	0
797 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
799 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
801 HIGH ROAD	4	4	0	0	0	0	4	4	0	0	0	0
803 HIGH ROAD	8	8	0	0	0	0	4	4	0	0	0	0
805 HIGH ROAD	4	4	0	0	0	0	2	2	0	0	0	0
809 HIGH ROAD	7	7	0	0	0	0	4	4	0	0	0	0
813 HIGH ROAD	4	4	0	0	0	0	2	2	0	0	0	0
815 HIGH ROAD	4	4	0	0	0	0	2	2	0	0	0	0
817 HIGH ROAD	2	2	0	0	0	0	2	2	0	0	0	0
819 HIGH ROAD	8	8	0	0	0	0	4	4	0	0	0	0
821 HIGH ROAD	4	4	0	0	0	0	2	2	0	0	0	0
823 HIGH ROAD	6	6	0	0	0	0	3	3	0	0	0	0
825 HIGH ROAD	2	2	0	0	0	0	1	1	0	0	0	0
827 HIGH ROAD	2	2	0	0	0	0	1	1	0	0	0	0
820 HIGH ROAD	2	2	0	0	0	0	2	2	0	0	0	0
814 HIGH ROAD	9	9	0	0	0	0	6	6	0	0	0	0
808 HIGH ROAD	11	11	0	0	0	0	9	9	0	0	0	0

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
806b HIGH ROAD	7	7	0	0	0	0	4	4	0	0	0	0
806 HIGH ROAD	8	8	0	0	0	0	8	8	0	0	0	0
804 HIGH ROAD	12	12	0	0	0	0	9	9	0	0	0	0
794 HIGH ROAD	19	12	6	1	0	7	11	11	0	0	0	0
790 HIGH ROAD	12	0	0	1	11	12	12	0	5	4	3	12
7 WHITE HART LANE	1	1	0	0	0	0	1	1	0	0	0	0
9-39 WHITE HART LANE	4	4	0	0	0	0	4	4	0	0	0	0
8 WILLIAM STREET	9	9	0	0	0	0	9	9	0	0	0	0
1 MOSELLE STREET	3	3	0	0	0	0	3	3	0	0	0	0
ERMINE HOUSE	12	12	0	0	0	0	6	6	0	0	0	0
29 NORTHUMBERLAND PARK	7	7	0	0	0	0	6	5	0	0	0	0
31 NORTHUMBERLAND PARK	7	7	0	0	0	0	5	5	0	0	0	0
33 NORTHUMBERLAND PARK	5	5	0	0	0	0	4	4	0	0	0	0
35 NORTHUMBERLAND PARK	4	4	0	0	0	0	4	4	0	0	0	0
37 NORTHUMBERLAND PARK	7	7	0	0	0	0	5	5	0	0	0	0
39 NORTHUMBERLAND PARK	12	12	0	0	0	0	4	4	0	0	0	0
41 NORTHUMBERLAND PARK	6	6	0	0	0	0	4	4	0	0	0	0
43 NORTHUMBERLAND PARK	6	6	0	0	0	0	4	4	0	0	0	0
45 NORTHUMBERLAND PARK	7	6	0	0	1	1	5	5	0	0	0	0
47 NORTHUMBERLAND PARK	7	7	0	0	0	0	4	4	0	0	0	0
49 NORTHUMBERLAND PARK	5	3	0	0	2	2	4	4	0	0	0	0
51 NORTHUMBERLAND PARK	4	3	0	0	1	1	4	4	0	0	0	0

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
53 NORTHUMBERLAND PARK	3	3	0	0	0	0	3	3	0	0	0	0
55 NORTHUMBERLAND PARK	2	2	0	0	0	0	2	2	0	0	0	0
57 NORTHUMBERLAND PARK	21	21	0	0	0	0	8	8	0	0	0	0
BURLEIGH COURT	20	20	0	0	0	0	20	20	0	0	0	0
50 NORTHUMBERLAND PARK	13	13	0	0	0	0	9	9	0	0	0	0
52 NORTHUMBERLAND PARK	8	8	0	0	0	0	8	8	0	0	0	0
2 WORCESTER AVENUE	5	5	0	0	0	0	4	4	0	0	0	0
4 WORCESTER AVENUE	4	4	0	0	0	0	4	4	0	0	0	0
6 WORCESTER AVENUE	4	4	0	0	0	0	4	4	0	0	0	0
8 WORCESTER AVENUE	5	5	0	0	0	0	4	4	0	0	0	0
10 WORCESTER AVENUE	5	4	1	0	0	1	4	4	0	0	0	0
12 WORCESTER AVENUE	5	5	0	0	0	0	4	4	0	0	0	0
14 WORCESTER AVENUE	4	4	0	0	0	0	4	4	0	0	0	0
16 WORCESTER AVENUE	4	4	0	0	0	0	4	4	0	0	0	0
18 WORCESTER AVENUE	4	4	0	0	0	0	4	4	0	0	0	0
1 WORCESTER AVENUE	24	24	0	0	0	0	8	8	0	0	0	0
3 WORCESTER AVENUE	16	16	0	0	0	0	4	4	0	0	0	0
5 WORCESTER AVENUE	16	16	0	0	0	0	4	4	0	0	0	0
7 WORCESTER AVENUE	16	16	0	0	0	0	4	4	0	0	0	0
9 WORCESTER AVENUE	16	16	0	0	0	0	4	4	0	0	0	0
11 WORCESTER AVENUE	16	16	0	0	0	0	4	4	0	0	0	0
13 WORCESTER AVENUE	15	15	0	0	0	0	4	4	0	0	0	0

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
15 WORCESTER AVENUE	16	16	0	0	0	0	5	5	0	0	0	0
17 WORCESTER AVENUE	15	14	1	0	0	1	4	4	0	0	0	0
19 WORCESTER AVENUE	15	14	1	0	0	1	4	4	0	0	0	0
21 WORCESTER AVENUE	16	12	4	0	0	4	4	4	0	0	0	0
23 WORCESTER AVENUE	16	8	5	3	0	8	4	4	0	0	0	0
25 WORCESTER AVENUE	17	3	8	3	3	14	4	3	1	0	0	1
27 WORCESTER AVENUE	20	3	4	10	3	17	4	0	1	1	2	4
29 WORCESTER AVENUE	14	1	0	2	11	13	4	0	0	0	4	4
31 WORCESTER AVENUE	17	1	0	0	16	16	4	0	0	0	4	4
33 WORCESTER AVENUE	17	2	0	1	14	15	4	0	0	0	4	4
35 WORCESTER AVENUE	17	1	0	0	16	16	4	0	0	0	4	4
37 WORCESTER AVENUE	17	1	0	0	16	16	4	0	0	0	4	4
39 WORCESTER AVENUE	16	0	0	0	16	16	4	0	0	0	4	4
41 WORCESTER AVENUE	29	2	0	0	27	27	5	0	0	0	5	5
NORTHUMBERLAND PARK COMMUNITY SCHOOL	20	17	3	0	0	3	5	3	0	2	0	2
ST PAUL-S AND ALL HALLOWS INFANT SCHOOL	37	16	1	8	12	21	23	19	0	4	0	4
56 PARK LANE	6	4	2	0	0	2	4	4	0	0	0	0
54 PARK LANE	4	0	4	0	0	4	4	3	1	0	0	1
52 PARK LANE	4	1	3	0	0	3	4	4	0	0	0	0
50 PARK LANE	4	1	3	0	0	3	5	5	0	0	0	0
48 PARK LANE	4	0	1	3	0	4	4	4	0	0	0	0

Address	VSC						NSL					
	Total No. of Windows	No. Windows that meet BRE criteria	Below BRE Guidelines				Total No. of Rooms	No. Rooms that meet the 0.8 times former value criteria	Below BRE Guidelines			
			20-30% Reduction	30-40% Reduction	>40% Reduction	Total			20-30% Reduction	30-40% Reduction	>40% Reduction	Total
44 PARK LANE	9	0	0	0	9	9	4	4	0	0	0	0
42 PARK LANE	8	0	0	0	8	8	4	4	0	0	0	0
40 PARK LANE	9	0	0	0	9	9	4	4	0	0	0	0
38 PARK LANE	9	0	0	0	9	9	4	4	0	0	0	0
36 PARK LANE	21	4	1	8	8	17	4	4	0	0	0	0
34 PARK LANE	8	1	0	3	4	7	4	4	0	0	0	0
32 PARK LANE	9	1	0	0	8	8	4	4	0	0	0	0
30 PARK LANE	10	0	1	0	9	10	3	3	0	0	0	0
28 PARK LANE	9	0	0	0	9	9	4	2	0	0	2	2
1 LANCASTER CLOSE	11	8	2	1	0	3	8	8	0	0	0	0
2 LANCASTER CLOSE	6	5	1	0	0	1	6	6	0	0	0	0
3 LANCASTER CLOSE	3	3	0	0	0	0	3	3	0	0	0	0
CONCORD HOUSE	103	7	0	0	96	96	70	21	7	3	38	48
2-2a PARK LANE	5	2	2	1	0	3	4	3	0	1	0	1
2 VICARAGE ROAD	2	0	2	0	0	2	2	1	0	1	0	1
28 BROMLEY ROAD	4	2	0	2	0	2	2	2	0	0	0	0
29 BROMLEY ROAD	5	2	0	3	0	3	2	2	0	0	0	0
38 BROMLEY ROAD	2	0	2	0	0	2	2	2	0	0	0	0
COOMBES HOUSE	50	46	4	0	0	4	33	32	1	0	0	1
TOTAL	**1589**	**954**	**103**	**85**	**447**	**635**	**917**	**696**	**40**	**36**	**142**	**218**

SUNLIGHT SUMMARY TABLE 17.7

Table 17.7 Summary of Sunlight results for Project

Address	Total No. Windows	Meet BRE Guidelines Total & Winter	Window which do not meet the BRE criteria					
			Below threshold for Winter APSH			Below threshold for Annual APSH		
			20-30% Reduction	30-40% Reduction	>40% Reduction	20-30% Reduction	30-40% Reduction	>40% Reduction
3 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
5 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
7 NORTHUMBERLAND PARK	2	2	0	0	0	0	0	0
9 NORTHUMBERLAND PARK	2	2	0	0	0	0	0	0
11 NORTHUMBERLAND PARK	2	2	0	0	0	0	0	0
13 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
15 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
17 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
19 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
21 NORTHUMBERLAND PARK	2	2	0	0	0	0	0	0
23 NORTHUMBERLAND PARK	7	7	0	0	0	0	0	0
19 BENNETS CLOSE	3	3	0	0	0	0	0	0
9-13 BENNETS CLOSE	32	32	0	0	0	0	0	0
ST FRANCAIS DE SALES RC PRIMARY SCHOOL	6	6	0	0	0	0	0	0
729 HIGH ROAD	11	10	0	0	0	0	0	1
LIBRARY-KATHLEEN FERRIER COURT	25	20	0	0	1	1	0	4
BERGAN-BROOKLYN APPARTMENTS	28	28	0	0	0	0	0	0
783 HIGH ROAD	3	3	0	0	0	0	0	0
793-795 HIGH ROAD (BANK)	24	24	0	0	0	0	0	0
797 HIGH ROAD	4	4	0	0	0	0	0	0
799 HIGH ROAD	4	4	0	0	0	0	0	0
801 HIGH ROAD	4	4	0	0	0	0	0	0
803 HIGH ROAD	8	8	0	0	0	0	0	0
805 HIGH ROAD	4	4	0	0	0	0	0	0

Address	Total No. Windows	Meet BRE Guidelines Total & Winter	Window which do not meet the BRE criteria					
			Below threshold for Winter APSH			Below threshold for Annual APSH		
			20-30% Reduction	30-40% Reduction	>40% Reduction	20-30% Reduction	30-40% Reduction	>40% Reduction
809 HIGH ROAD	7	7	0	0	0	0	0	0
813 HIGH ROAD	4	4	0	0	0	0	0	0
815 HIGH ROAD	4	4	0	0	0	0	0	0
817 HIGH ROAD	2	2	0	0	0	0	0	0
819 HIGH ROAD	9	9	0	0	0	0	0	0
821 HIGH ROAD	4	4	0	0	0	0	0	0
823 HIGH ROAD	6	6	0	0	0	0	0	0
825 HIGH ROAD	2	2	0	0	0	0	0	0
814 HIGH ROAD	10	10	0	0	0	0	0	0
806b HIGH ROAD	7	7	0	0	0	0	0	0
804 HIGH ROAD	2	2	0	0	0	0	0	0
794 HIGH ROAD	1	0	0	0	1	0	1	0
ERMINE HOUSE	3	3	0	0	0	0	0	0
29 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
31 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
33 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
35 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
37 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
39 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
41 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
43 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
45 NORTHUMBERLAND PARK	4	4	0	0	0	0	0	0
47 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
49 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0
51 NORTHUMBERLAND PARK	3	3	0	0	0	0	0	0

Address	Total No. Windows	Meet BRE Guidelines Total & Winter	Window which do not meet the BRE criteria					
			Below threshold for Winter APSH			Below threshold for Annual APSH		
			20-30% Reduction	30-40% Reduction	>40% Reduction	20-30% Reduction	30-40% Reduction	>40% Reduction
53 NORTHUMBERLAND PARK	2	2	0	0	0	0	0	0
55 NORTHUMBERLAND PARK	2	2	0	0	0	0	0	0
57 NORTHUMBERLAND PARK	16	16	0	0	0	0	0	0
BURLEIGH COURT	18	18	0	0	0	0	0	0
50 NORTHUMBERLAND PARK	7	7	0	0	0	0	0	0
52 NORTHUMBERLAND PARK	8	8	0	0	0	0	0	0
10 WORCESTER AVENUE	1	0	0	0	1	0	0	0
1 WORCESTER AVENUE	6	6	0	0	0	0	0	0
3 WORCESTER AVENUE	5	5	0	0	0	0	0	0
5 WORCESTER AVENUE	5	5	0	0	0	0	0	0
7 WORCESTER AVENUE	5	5	0	0	0	0	0	0
9 WORCESTER AVENUE	5	5	0	0	0	0	0	0
11 WORCESTER AVENUE	5	4	0	0	1	0	0	0
13 WORCESTER AVENUE	5	5	0	0	0	0	0	0
15 WORCESTER AVENUE	5	4	0	0	1	0	0	0
17 WORCESTER AVENUE	15	11	0	0	4	0	0	0
19 WORCESTER AVENUE	15	10	0	0	5	0	0	0
21 WORCESTER AVENUE	16	7	0	0	9	3	1	0
23 WORCESTER AVENUE	16	4	0	0	12	1	1	6
25 WORCESTER AVENUE	17	1	0	0	15	0	3	13
27 WORCESTER AVENUE	20	0	0	0	13	0	0	20
29 WORCESTER AVENUE	14	0	0	0	14	0	0	14
31 WORCESTER AVENUE	17	1	0	0	14	0	0	16
33 WORCESTER AVENUE	17	3	0	0	14	0	0	15
35 WORCESTER AVENUE	17	2	0	0	15	0	0	15

Address	Total No. Windows	Meet BRE Guidelines Total & Winter	Window which do not meet the BRE criteria					
			Below threshold for Winter APSH			Below threshold for Annual APSH		
			20-30% Reduction	30-40% Reduction	>40% Reduction	20-30% Reduction	30-40% Reduction	>40% Reduction
37 WORCESTER AVENUE	17	3	0	0	14	0	0	15
39 WORCESTER AVENUE	16	0	0	0	16	0	0	16
41 WORCESTER AVENUE	29	2	0	0	24	0	0	27
NORTHUMBERLAND PARK COMMUNITY SCHOOL	15	13	0	1	1	0	0	0
ST PAUL-S AND ALL HALLOWS INFANT SCHOOL	32	21	0	0	1	1	5	5
1 LANCASTER CLOSE	5	5	0	0	0	0	0	0
2 LANCASTER CLOSE	2	2	0	0	0	0	0	0
28 BROMLEY ROAD	2	2	0	0	0	0	0	0
38 BROMLEY ROAD	2	2	0	0	0	0	0	0
COOMBES HOUSE	1	1	0	0	0	0	0	0
TOTAL	**674**	**469**	**0**	**1**	**176**	**6**	**11**	**167**

Vertical Sky Component (VSC)

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
3 NORTHUMBERLAND PARK						
R1/21	**W1/21**	UNKNOWN	34	33	1	2.9
R2/21	**W2/21**	UNKNOWN	34	33	1	2.9
R3/21	**W3/21**	UNKNOWN	33.5	33.5	0	0.0
R1/22	**W1/22**	UNKNOWN	35.5	34	1.5	4.2
R2/22	**W2/22**	UNKNOWN	35.5	34	1.5	4.2
R3/22	**W3/22**	UNKNOWN	36	36	0	0.0
5 NORTHUMBERLAND PARK						
R1/31	**W1/31**	UNKNOWN	34	33	1	2.9
R2/31	**W2/31**	UNKNOWN	33.5	33	0.5	1.5
R1/32	**W1/32**	UNKNOWN	35	34	1	2.9
R2/32	**W2/32**	UNKNOWN	35	34	1	2.9
7 NORTHUMBERLAND PARK						
R1/41	**W1/41**	UNKNOWN	32.5	32	0.5	1.5
R1/42	**W1/42**	UNKNOWN	34.5	33.5	1	2.9
9 NORTHUMBERLAND PARK						
R2/41	**W2/41**	UNKNOWN	32.5	32	0.5	1.5
R2/42	**W2/42**	UNKNOWN	34	33.5	0.5	1.5
11 NORTHUMBERLAND PARK						
R3/41	**W3/41**	UNKNOWN	31.5	31	0.5	1.6
R3/42	**W3/42**	UNKNOWN	33.5	33	0.5	1.5
13 NORTHUMBERLAND PARK						
R1/51	**W1/51**	UNKNOWN	30	30	0	0.0
R2/51	**W2/51**	UNKNOWN	29.5	29.5	0	0.0
R1/52	**W1/52**	UNKNOWN	33	33	0	0.0
R2/52	**W2/52**	UNKNOWN	33	33	0	0.0
15 NORTHUMBERLAND PARK						
R3/51	**W3/51**	UNKNOWN	30.5	30.5	0	0.0

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R4/51	W4/51	UNKNOWN	30.5	30.5	0	0.0
R3/52	W3/52	UNKNOWN	33	32.5	0.5	1.5
R4/52	W4/52	UNKNOWN	32.5	32.5	0	0.0
17 NORTHUMBERLAND PARK						
R5/51	W5/51	UNKNOWN	30.5	30.5	0	0.0
R6/51	W6/51	UNKNOWN	30	30	0	0.0
R5/52	W5/52	UNKNOWN	32.5	32.5	0	0.0
R6/52	W6/52	UNKNOWN	32.5	32	0.5	1.5
19 NORTHUMBERLAND PARK						
R7/51	W7/51	UNKNOWN	29.5	29.5	0	0.0
R8/51	W8/51	UNKNOWN	29.5	29.5	0	0.0
R7/52	W7/52	UNKNOWN	32	32	0	0.0
R8/52	W8/52	UNKNOWN	32	32	0	0.0
21 NORTHUMBERLAND PARK						
R9/51	W9/51	UNKNOWN	29.5	29.5	0	0.0
R9/52	W9/52	UNKNOWN	32	32	0	0.0
23 NORTHUMBERLAND PARK						
R1/60	W1/60	UNKNOWN	21	21	0	0.0
R2/60	W2/60	UNKNOWN	9	9	0	0.0
R2/60	W3/60	UNKNOWN	17.5	17.5	0	0.0
R2/60	W4/60	UNKNOWN	32.5	32.5	0	0.0
R1/61	W1/61	UNKNOWN	24	24	0	0.0
R2/61	W2/61	UNKNOWN	24	24	0	0.0
R1/65	W1/65	UNKNOWN	20	20	0	0.0
R1/70	W1/70	UNKNOWN	28	28	0	0.0
R1/71	W1/71	UNKNOWN	18	18	0	0.0
19 BENNETS CLOSE						
R1/850	W1/850	UNKNOWN	26.5	26.5	0	0.0
R1/851	W1/851	UNKNOWN	32.5	32.5	0	0.0
R1/852	W1/852	UNKNOWN	36.5	36	0.5	1.4
9-13 BENNETS CLOSE						

Vertical Sky Component						
Room	Window	Room Use	Existing	Proposed	Loss	%
R1/860	W1/860	UNKNOWN	29	29	0	0.0
R2/860	W8/860	UNKNOWN	30	30	0	0.0
R3/860	W2/860	UNKNOWN	24	24	0	0.0
R3/860	W3/860	UNKNOWN	22.5	22.5	0	0.0
R4/860	W4/860	UNKNOWN	23	23	0	0.0
R5/860	W5/860	UNKNOWN	23	23	0	0.0
R6/860	W6/860	UNKNOWN	23	23	0	0.0
R6/860	W7/860	UNKNOWN	24.5	24.5	0	0.0
R1/861	W1/861	UNKNOWN	32.5	32	0.5	1.5
R2/861	W8/861	UNKNOWN	32.5	32.5	0	0.0
R3/861	W2/861	UNKNOWN	27	27	0	0.0
R3/861	W3/861	UNKNOWN	25.5	25.5	0	0.0
R4/861	W4/861	UNKNOWN	25.5	25.5	0	0.0
R5/861	W5/861	UNKNOWN	25.5	25.5	0	0.0
R6/861	W6/861	UNKNOWN	25.5	25.5	0	0.0
R6/861	W7/861	UNKNOWN	27	27	0	0.0
R1/862	W1/862	UNKNOWN	35	35	0	0.0
R2/862	W8/862	UNKNOWN	35	35	0	0.0
R3/862	W2/862	UNKNOWN	29	29	0	0.0
R3/862	W3/862	UNKNOWN	27.5	27.5	0	0.0
R4/862	W4/862	UNKNOWN	27.5	27.5	0	0.0
R5/862	W5/862	UNKNOWN	28	27.5	0.5	1.8
R6/862	W6/862	UNKNOWN	27.5	27.5	0	0.0
R6/862	W7/862	UNKNOWN	29.5	29.5	0	0.0
R1/863	W1/863	UNKNOWN	36.5	36	0.5	1.4
R2/863	W8/863	UNKNOWN	36.5	36	0.5	1.4
R3/863	W2/863	UNKNOWN	31	30.5	0.5	1.6
R3/863	W3/863	UNKNOWN	29	29	0	0.0
R4/863	W4/863	UNKNOWN	29.5	29	0.5	1.7
R5/863	W5/863	UNKNOWN	29.5	29	0.5	1.7
R6/863	W6/863	UNKNOWN	29	29	0	0.0
R6/863	W7/863	UNKNOWN	31	30.5	0.5	1.6
705 HIGH ROAD						
R1/420	W1/420	UNKNOWN	15.5	15	0.5	3.2
R1/421	W1/421	UNKNOWN	26.5	25.5	1	3.8

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R1/429	W1/429	UNKNOWN	32.5	28.5	4	12.3
R1/430	W1/430	UNKNOWN	33.5	28.5	5	14.9
R1/430	W3/430	UNKNOWN	35	30	5	14.3
R1/430	W4/430	UNKNOWN	34.5	30	4.5	13.0
R2/430	W2/430	UNKNOWN	35.5	30.5	5	14.1
R1/431	W1/431	UNKNOWN	36.5	31.5	5	13.7
R2/431	W2/431	UNKNOWN	37	32	5	13.5
R1/435	W1/435	UNKNOWN	36	30.5	5.5	15.3
R1/435	W2/435	UNKNOWN	36	30.5	5.5	15.3
R1/436	W1/436	UNKNOWN	36.5	31.5	5	13.7
ST FRANCAIS DE SALES RC PRIMARY SCHOOL						
R1/450	W1/450	UNKNOWN	38	37.5	0.5	1.3
R1/450	W2/450	UNKNOWN	38	37.5	0.5	1.3
R1/450	W3/450	UNKNOWN	35.5	27	8.5	23.9
R1/450	W4/450	UNKNOWN	35.5	27	8.5	23.9
R1/450	W5/450	UNKNOWN	36	27	9	25.0
R1/450	W6/450	UNKNOWN	35.5	27	8.5	23.9
R2/450	W7/450	UNKNOWN	35.5	27	8.5	23.9
R2/450	W8/450	UNKNOWN	35.5	27	8.5	23.9
R3/450	W9/450	UNKNOWN	34.5	26	8.5	24.6
R3/450	W10/450	UNKNOWN	34.5	26	8.5	24.6
R3/450	W11/450	UNKNOWN	34.5	26.5	8	23.2
R3/450	W12/450	UNKNOWN	35	26.5	8.5	24.3
R3/450	W13/450	UNKNOWN	35	26.5	8.5	24.3
R4/450	W14/450	UNKNOWN	35	26.5	8.5	24.3
R4/450	W15/450	UNKNOWN	35	26.5	8.5	24.3
R4/450	W16/450	UNKNOWN	34.5	26.5	8	23.2
R4/450	W17/450	UNKNOWN	34	26	8	23.5
R4/450	W18/450	UNKNOWN	34.5	26.5	8	23.2
R5/450	W19/450	UNKNOWN	34	26	8	23.5
R6/450	W20/450	UNKNOWN	33	26	7	21.2
R6/450	W21/450	UNKNOWN	19	15	4	21.1
R6/450	W22/450	UNKNOWN	22	16.5	5.5	25.0
R6/450	W23/450	UNKNOWN	25.5	19	6.5	25.5
R6/450	W24/450	UNKNOWN	31	30.5	0.5	1.6
R6/450	W25/450	UNKNOWN	31.5	31	0.5	1.6
R7/450	W28/450	UNKNOWN	21.5	20	1.5	7.0
R8/450	W29/450	UNKNOWN	26	21	5	19.2
R9/450	W26/450	UNKNOWN	17.5	16	1.5	8.6
R10/450	W27/450	UNKNOWN	19	17	2	10.5
R1/451	W1/451	UNKNOWN	38.5	38	0.5	1.3
R1/451	W2/451	UNKNOWN	38.5	38	0.5	1.3
R1/451	W3/451	UNKNOWN	36	27.5	8.5	23.6
R1/451	W4/451	UNKNOWN	36	27	9	25.0

Vertical Sky Component						
Room	Window	Room Use	Existing	Proposed	Loss	%
R2/451	W5/451	UNKNOWN	36	27	9	25.0
R2/451	W6/451	UNKNOWN	36	27	9	25.0
R3/451	W7/451	UNKNOWN	35.5	27	8.5	23.9
R4/451	W8/451	UNKNOWN	35.5	27	8.5	23.9
R4/451	W9/451	UNKNOWN	35.5	27	8.5	23.9
R4/451	W10/451	UNKNOWN	35.5	26.5	9	25.4
R5/451	W11/451	UNKNOWN	35.5	27	8.5	23.9
R5/451	W12/451	UNKNOWN	35.5	27	8.5	23.9
R6/451	W13/451	UNKNOWN	35	27	8	22.9
R6/451	W14/451	UNKNOWN	33.5	32.5	1	3.0
R6/451	W15/451	UNKNOWN	34	33	1	2.9
R6/451	W16/451	UNKNOWN	34	33.5	0.5	1.5
R6/451	W17/451	UNKNOWN	34	33.5	0.5	1.5
R7/451	W26/451	UNKNOWN	30	25.5	4.5	15.0
R8/451	W27/451	UNKNOWN	28.5	25	3.5	12.3
R1/455	W1/455	UNKNOWN	33	31.5	1.5	4.5
R1/455	W2/455	UNKNOWN	29	29	0	0.0
R1/455	W3/455	UNKNOWN	30.5	22	8.5	27.9
R1/1020	W3/1020	UNKNOWN	23	21.5	1.5	6.5
R2/1020	W2/1020	UNKNOWN	20.5	18.5	2	9.8
R3/1020	W1/1020	UNKNOWN	24.5	20.5	4	16.3
729 HIGH ROAD						
R1/460	W4/460	UNKNOWN	36	33	3	8.3
R1/460	W5/460	UNKNOWN	33.5	25	8.5	25.4
R1/460	W6/460	UNKNOWN	33	20.5	12.5	37.9
R1/460	W7/460	UNKNOWN	22.5	15	7.5	33.3
R2/460	W11/460	UNKNOWN	26	17.5	8.5	32.7
R2/460	W12/460	UNKNOWN	31.5	19.5	12	38.1
R2/460	W13/460	UNKNOWN	20.5	14.5	6	29.3
R3/460	W8/460	UNKNOWN	20	8	12	60.0
R3/460	W9/460	UNKNOWN	20.5	8.5	12	58.5
R3/460	W10/460	UNKNOWN	4.5	0	4.5	100.0
R4/460	W3/460	UNKNOWN	36	33	3	8.3
R5/460	W1/460	UNKNOWN	35	32	3	8.6
R5/460	W2/460	UNKNOWN	35.5	32.5	3	8.5
R1/461	W4/461	UNKNOWN	36	33	3	8.3
R1/461	W5/461	UNKNOWN	33.5	24.5	9	26.9
R1/461	W6/461	UNKNOWN	34	21	13	38.2
R1/461	W7/461	UNKNOWN	26	18	8	30.8
R2/461	W9/461	UNKNOWN	28	19.5	8.5	30.4
R2/461	W10/461	UNKNOWN	33	20.5	12.5	37.9
R2/461	W11/461	UNKNOWN	23.5	16.5	7	29.8
R3/461	W8/461	UNKNOWN	30	17	13	43.3

Vertical Sky Component						
Room	**Window**	**Room Use**	Existing	Proposed	Loss	**%**
R4/461	**W3/461**	UNKNOWN	36	33	3	8.3
R5/461	**W1/461**	UNKNOWN	36	33	3	8.3
R5/461	**W2/461**	UNKNOWN	36	33	3	8.3
R1/462	**W1/462**	UNKNOWN	39	35.5	3.5	9.0
R2/462	**W2/462**	Bedroom	35.5	22.5	13	36.6
4-18 BRERETON ROAD						
R1/940	**W1/940**	UNKNOWN	23.5	19.5	4	17.0
R2/940	**W2/940**	UNKNOWN	23	18.5	4.5	19.6
R3/940	**W3/940**	UNKNOWN	22	18	4	18.2
R4/940	**W4/940**	UNKNOWN	21.5	17.5	4	18.6
R5/940	**W5/940**	UNKNOWN	20.5	16.5	4	19.5
R6/940	**W6/940**	UNKNOWN	20	16	4	20.0
R7/940	**W7/940**	UNKNOWN	19	15.5	3.5	18.4
R8/940	**W8/940**	UNKNOWN	18.5	15.5	3	16.2
R9/940	**W9/940**	UNKNOWN	18.5	16	2.5	13.5
R10/940	**W10/940**	UNKNOWN	18	15.5	2.5	13.9
R11/940	**W11/940**	UNKNOWN	16.5	14.5	2	12.1
R12/940	**W12/940**	UNKNOWN	15.5	13	2.5	16.1
R1/941	**W1/941**	UNKNOWN	16.5	12.5	4	24.2
R2/941	**W2/941**	UNKNOWN	13	8.5	4.5	34.6
R3/941	**W3/941**	UNKNOWN	12.5	8	4.5	36.0
R4/941	**W4/941**	UNKNOWN	11	7	4	36.4
R5/941	**W5/941**	UNKNOWN	10.5	7	3.5	33.3
R6/941	**W6/941**	UNKNOWN	10.5	7.5	3	28.6
R7/941	**W7/941**	UNKNOWN	10.5	8	2.5	23.8
R8/941	**W8/941**	UNKNOWN	6.5	5.5	1	15.4
R1/942	**W1/942**	UNKNOWN	30.5	26	4.5	14.8
R2/942	**W2/942**	UNKNOWN	30.5	25.5	5	16.4
R3/942	**W3/942**	UNKNOWN	30	25	5	16.7
R4/942	**W4/942**	UNKNOWN	29.5	24.5	5	16.9
R5/942	**W5/942**	UNKNOWN	28.5	24	4.5	15.8

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R6/942	W6/942	UNKNOWN	28	23.5	4.5	16.1
R7/942	W7/942	UNKNOWN	27.5	23.5	4	14.5
R8/942	W8/942	UNKNOWN	27.5	24	3.5	12.7
R9/942	W9/942	UNKNOWN	28	24.5	3.5	12.5
R10/942	W10/942	UNKNOWN	28.5	25.5	3	10.5
R11/942	W11/942	UNKNOWN	29	25.5	3.5	12.1
R12/942	W12/942	UNKNOWN	27.5	24.5	3	10.9
R1/943	W1/943	UNKNOWN	34	29	5	14.7
R2/943	W2/943	UNKNOWN	33.5	28.5	5	14.9
R3/943	W3/943	UNKNOWN	33	28	5	15.2
R4/943	W4/943	UNKNOWN	32	27.5	4.5	14.1
R5/943	W5/943	UNKNOWN	31.5	27.5	4	12.7
R6/943	W6/943	UNKNOWN	32	28.5	3.5	10.9
R7/943	W7/943	UNKNOWN	33	29	4	12.1
R8/943	W8/943	UNKNOWN	33.5	29.5	4	11.9
LIBRARY-KATHLEEN FERRIER COURT						
R1/480	W13/480	Unknown	25.5	20	5.5	21.6
R1/480	W14/480	Unknown	25.5	20	5.5	21.6
R1/480	W15/480	Unknown	27.5	22	5.5	20.0
R1/480	W16/480	Unknown	28.5	23	5.5	19.3
R1/480	W18/480	Unknown	27.5	22	5.5	20.0
R1/480	W19/480	Unknown	29	15	14	48.3
R1/480	W20/480	Unknown	29.5	15	14.5	49.2
R1/480	W21/480	Unknown	30.5	15.5	15	49.2
R1/480	W22/480	Unknown	25.5	21.5	4	15.7
R1/480	W23/480	Unknown	25	21	4	16.0
R1/480	W24/480	Unknown	25	20.5	4.5	18.0
R1/480	W25/480	Unknown	26	21.5	4.5	17.3
R1/480	W26/480	Unknown	33	16.5	16.5	50.0
R1/480	W27/480	Unknown	33	16.5	16.5	50.0
R2/480	W1/480	Unknown	10	7.5	2.5	25.0
R2/480	W10/480	Unknown	15.5	2.5	13	83.9
R2/480	W11/480	Unknown	18.5	15	3.5	18.9
R2/480	W12/480	Unknown	19	14.5	4.5	23.7
R2/480	W17/480	Unknown	16	2	14	87.5
R2/480	W2/480	Unknown	10	7.5	2.5	25.0
R2/480	W3/480	Unknown	10.5	8	2.5	23.8
R2/480	W4/480	Unknown	14.5	10.5	4	27.6
R2/480	W5/480	Unknown	17.5	10	7.5	42.9
R2/480	W6/480	Unknown	18	8.5	9.5	52.8
R2/480	W7/480	Unknown	18.5	6	12.5	67.6
R2/480	W8/480	Unknown	16.5	3.5	13	78.8
R2/480	W9/480	Unknown	16	3	13	81.3
R1/481	W3/481	LIVINGROOM	33.5	29.5	4	11.9
R1/481	W4/481	LIVINGROOM	34	19	15	44.1

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R1/481	W5/481	LIVINGROOM	34.5	19.5	15	43.5
R1/481	W6/481	LIVINGROOM	34	19	15	44.1
R2/481	W7/481	LIVINGROOM	34	19	15	44.1
R2/481	W8/481	LIVINGROOM	34.5	19	15.5	44.9
R2/481	W9/481	LIVINGROOM	34	19	15	44.1
R3/481	W10/481	LIVINGROOM	34	18.5	15.5	45.6
R3/481	W11/481	LIVINGROOM	34.5	19	15.5	44.9
R3/481	W12/481	LIVINGROOM	34	18.5	15.5	45.6
R4/481	W13/481	LIVINGROOM	34	18.5	15.5	45.6
R4/481	W14/481	LIVINGROOM	34.5	18.5	16	46.4
R4/481	W15/481	LIVINGROOM	34	18.5	15.5	45.6
R5/481	W1/481	UNKNOWN	33.5	29	4.5	13.4
R5/481	W2/481	UNKNOWN	33.5	29	4.5	13.4
R1/482	W1/482	BEDROOM	35	31	4	11.4
R2/482	W2/482	BEDROOM	35.5	31	4.5	12.7
R3/482	W3/482	BEDROOM	35.5	31	4.5	12.7
R3/482	W4/482	BEDROOM	29	13.5	15.5	53.4
R4/482	W5/482	BEDROOM	29	13.5	15.5	53.4
R5/482	W6/482	BEDROOM	29	13.5	15.5	53.4
R6/482	W7/482	BEDROOM	29	13.5	15.5	53.4
R7/482	W8/482	BEDROOM	29	13.5	15.5	53.4
R8/482	W9/482	BEDROOM	29	13.5	15.5	53.4
R9/482	W10/482	BEDROOM	29	13.5	15.5	53.4
R10/482	W11/482	BEDROOM	29	13	16	55.2
R1/483	W3/483	LIVINGROOM	37	32.5	4.5	12.2
R1/483	W4/483	LIVINGROOM	36	21.5	14.5	40.3
R1/483	W5/483	LIVINGROOM	36.5	21.5	15	41.1
R1/483	W6/483	LIVINGROOM	36	21	15	41.7
R2/483	W7/483	LIVINGROOM	36.5	21	15.5	42.5
R2/483	W8/483	LIVINGROOM	37	21.5	15.5	41.9
R2/483	W9/483	LIVINGROOM	36.5	21	15.5	42.5
R3/483	W10/483	LIVINGROOM	36.5	21	15.5	42.5
R3/483	W11/483	LIVINGROOM	37	21.5	15.5	41.9
R3/483	W12/483	LIVINGROOM	36.5	21	15.5	42.5
R4/483	W13/483	LIVINGROOM	36.5	21	15.5	42.5
R4/483	W14/483	LIVINGROOM	37	21.5	15.5	41.9
R4/483	W15/483	LIVINGROOM	36.5	21	15.5	42.5
R5/483	W1/483	UNKNOWN	37	32.5	4.5	12.2
R5/483	W2/483	UNKNOWN	37	32.5	4.5	12.2
R1/484	W1/484	BEDROOM	38	34	4	10.5
R2/484	W2/484	BEDROOM	38	34	4	10.5

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R3/484	W3/484	BEDROOM	38	33.5	4.5	11.8
R3/484	W4/484	BEDROOM	38	23.5	14.5	38.2
R4/484	W5/484	BEDROOM	38	23.5	14.5	38.2
R5/484	W6/484	BEDROOM	38	23.5	14.5	38.2
R6/484	W7/484	BEDROOM	38	23.5	14.5	38.2
R7/484	W8/484	BEDROOM	38	23.5	14.5	38.2
R8/484	W9/484	BEDROOM	38	23.5	14.5	38.2
R9/484	W10/484	BEDROOM	38	23.5	14.5	38.2
R10/484	W11/484	BEDROOM	38	23.5	14.5	38.2
731 HIGH ROAD						
R1/491	W1/491	UNKNOWN	34.5	18	16.5	47.8
R2/491	W2/491	UNKNOWN	34.5	18	16.5	47.8
R1/492	W1/492	UNKNOWN	36	19	17	47.2
R2/492	W2/492	UNKNOWN	36	19	17	47.2
733 HIGH ROAD						
R3/491	W3/491	UNKNOWN	34.5	18	16.5	47.8
R4/491	W4/491	UNKNOWN	34.5	17.5	17	49.3
R3/492	W3/492	UNKNOWN	36	19	17	47.2
R4/492	W4/492	UNKNOWN	36	19	17	47.2
735 HIGH ROAD						
R5/491	W5/491	UNKNOWN	34	17.5	16.5	48.5
R6/491	W6/491	UNKNOWN	34	17.5	16.5	48.5
R5/492	W5/492	UNKNOWN	35.5	19	16.5	46.5
R6/492	W6/492	UNKNOWN	35.5	19	16.5	46.5
R1/951	W1/951	UNKNOWN	27.5	22.5	5	18.2
737 HIGH ROAD						
R7/491	W7/491	UNKNOWN	34	17.5	16.5	48.5
R8/491	W8/491	UNKNOWN	34	17.5	16.5	48.5
R7/492	W7/492	UNKNOWN	35.5	19	16.5	46.5
R8/492	W8/492	UNKNOWN	35.5	19	16.5	46.5

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
739 HIGH ROAD						
R9/491	**W9/491**	UNKNOWN	34	17.5	16.5	48.5
R10/491	**W10/491**	UNKNOWN	34.5	17.5	17	49.3
R9/492	**W9/492**	UNKNOWN	35.5	19	16.5	46.5
R10/492	**W10/492**	UNKNOWN	36	19	17	47.2
741 HIGH ROAD						
R7/490	**W26/490**	UNKNOWN	29	26.5	2.5	8.6
R11/491	**W11/491**	UNKNOWN	34.5	17.5	17	49.3
R12/491	**W12/491**	UNKNOWN	34.5	17.5	17	49.3
R11/492	**W11/492**	UNKNOWN	36	19	17	47.2
R12/492	**W12/492**	UNKNOWN	36	19	17	47.2
R1/495	**W1/495**	UNKNOWN	34	17.5	16.5	48.5
R1/496	**W1/496**	UNKNOWN	36	18.5	17.5	48.6
743 HIGH ROAD						
R1/501	**W1/501**	UNKNOWN	35	16	19	54.3
R2/501	**W2/501**	UNKNOWN	35	16.5	18.5	52.9
R1/502	**W1/502**	UNKNOWN	36	17	19	52.8
R2/502	**W2/502**	UNKNOWN	36.5	17.5	19	52.1
745 HIGH ROAD						
R3/501	**W3/501**	Bedroom	34.5	16	18.5	53.6
R3/501	**W4/501**	Bedroom	35	16	19	54.3
R4/501	**W5/501**	UNKNOWN	35.5	16.5	19	53.5
R3/502	**W3/502**	UNKNOWN	36.5	17.5	19	52.1
R4/502	**W4/502**	UNKNOWN	36.5	17.5	19	52.1
747 HIGH ROAD						
R5/501	**W6/501**	UNKNOWN	35.5	17	18.5	52.1
R6/501	**W7/501**	UNKNOWN	36	17	19	52.8
R5/502	**W5/502**	UNKNOWN	36.5	18	18.5	50.7
R6/502	**W6/502**	UNKNOWN	37	18	19	51.4
749 HIGH ROAD						

Vertical Sky Component						
Room	Window	Room Use	Existing	Proposed	Loss	%
R7/501	W8/501	UNKNOWN	35.5	17	18.5	52.1
R7/501	W9/501	UNKNOWN	36	17.5	18.5	51.4
R8/501	W10/501	UNKNOWN	36	17.5	18.5	51.4
R7/502	W7/502	UNKNOWN	37	18.5	18.5	50.0
R8/502	W8/502	UNKNOWN	37	18.5	18.5	50.0
751 HIGH ROAD						
R9/501	W11/501	UNKNOWN	36.5	18	18.5	50.7
R10/501	W12/501	UNKNOWN	36.5	18	18.5	50.7
R9/502	W9/502	UNKNOWN	37	19	18	48.6
R10/502	W10/502	UNKNOWN	37	19	18	48.6
753 HIGH ROAD						
R11/501	W13/501	UNKNOWN	36.5	18.5	18	49.3
R12/501	W14/501	UNKNOWN	36.5	18.5	18	49.3
R11/502	W11/502	UNKNOWN	37	19.5	17.5	47.3
R12/502	W12/502	UNKNOWN	37	19.5	17.5	47.3
755 HIGH ROAD						
R13/501	W15/501	UNKNOWN	36.5	19	17.5	47.9
R14/501	W16/501	UNKNOWN	36.5	19	17.5	47.9
R13/502	W13/502	UNKNOWN	37	20	17	45.9
R14/502	W14/502	UNKNOWN	37	20.5	16.5	44.6
757 HIGH ROAD						
R15/501	W17/501	UNKNOWN	36.5	19.5	17	46.6
R16/501	W18/501	UNKNOWN	36.5	20	16.5	45.2
R15/502	W15/502	UNKNOWN	37	20.5	16.5	44.6
R16/502	W16/502	UNKNOWN	37	21	16	43.2
759 HIGH ROAD						
R10/500	W45/500	UNKNOWN	24.5	23.5	1	4.1
R10/500	W46/500	UNKNOWN	22.5	21.5	1	4.4
R17/501	W19/501	UNKNOWN	36.5	20.5	16	43.8
R17/501	W20/501	UNKNOWN	36.5	20.5	16	43.8

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R18/501	W21/501	UNKNOWN	36.5	21	15.5	42.5
R18/501	W22/501	UNKNOWN	37	21.5	15.5	41.9
R18/501	W23/501	UNKNOWN	36.5	21	15.5	42.5
R19/501	W24/501	UNKNOWN	36.5	21.5	15	41.1
R17/503	W1/503	UNKNOWN	37.5	22	15.5	41.3
R17/503	W2/503	UNKNOWN	37.5	22.5	15	40.0
R18/503	W3/503	UNKNOWN	37.5	22.5	15	40.0
R18/503	W4/503	UNKNOWN	37.5	23	14.5	38.7
R19/503	W5/503	UNKNOWN	37.5	23	14.5	38.7
BERGAN-BROOKLYN APPARTMENTS						
R1/510	W21/510	UNKNOWN	22.5	12	10.5	46.7
R2/510	W19/510	UNKNOWN	22.5	13	9.5	42.2
R2/510	W20/510	UNKNOWN	23	12.5	10.5	45.7
R3/510	W15/510	UNKNOWN	28.5	18	10.5	36.8
R3/510	W16/510	UNKNOWN	26.5	16	10.5	39.6
R3/510	W17/510	UNKNOWN	9.5	2.5	7	73.7
R3/510	W18/510	UNKNOWN	19.5	8	11.5	59.0
R4/510	W13/510	UNKNOWN	27.5	15	12.5	45.5
R4/510	W14/510	UNKNOWN	24	12	12	50.0
R5/510	W10/510	UNKNOWN	28.5	24	4.5	15.8
R5/510	W11/510	UNKNOWN	28	22.5	5.5	19.6
R5/510	W12/510	UNKNOWN	31.5	20	11.5	36.5
R6/510	W9/510	UNKNOWN	19	18.5	0.5	2.6
R7/510	W7/510	UNKNOWN	20.5	17.5	3	14.6
R7/510	W8/510	UNKNOWN	21.5	18	3.5	16.3
R8/510	W3/510	UNKNOWN	15	13.5	1.5	10.0
R8/510	W4/510	UNKNOWN	5.5	5	0.5	9.1
R8/510	W5/510	UNKNOWN	20.5	20	0.5	2.4
R8/510	W6/510	UNKNOWN	22.5	22.5	0	0.0
R9/510	W1/510	UNKNOWN	22.5	20.5	2	8.9
R9/510	W2/510	UNKNOWN	20	19.5	0.5	2.5
R1/511	W13/511	UNKNOWN	24.5	14.5	10	40.8
R2/511	W11/511	UNKNOWN	27	16	11	40.7
R2/511	W12/511	UNKNOWN	25	14.5	10.5	42.0
R4/511	W9/511	UNKNOWN	28	16	12	42.9
R4/511	W10/511	UNKNOWN	28	16	12	42.9
R5/511	W6/511	UNKNOWN	31	27	4	12.9
R5/511	W7/511	UNKNOWN	31	25.5	5.5	17.7
R5/511	W8/511	UNKNOWN	35.5	24	11.5	32.4
R6/511	W5/511	UNKNOWN	21.5	21	0.5	2.3
R7/511	W3/511	UNKNOWN	24	20.5	3.5	14.6
R7/511	W4/511	UNKNOWN	24	20	4	16.7

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R9/511	W1/511	UNKNOWN	24.5	21	3.5	14.3
R9/511	W2/511	UNKNOWN	24.5	21	3.5	14.3
R1/512	W13/512	UNKNOWN	26	16.5	9.5	36.5
R2/512	W11/512	UNKNOWN	36	26	10	27.8
R2/512	W12/512	UNKNOWN	35	25	10	28.6
R4/512	W9/512	UNKNOWN	36.5	25	11.5	31.5
R4/512	W10/512	UNKNOWN	36.5	25.5	11	30.1
R5/512	W6/512	UNKNOWN	34	30	4	11.8
R5/512	W7/512	UNKNOWN	34	29	5	14.7
R5/512	W8/512	UNKNOWN	36.5	25.5	11	30.1
R6/512	W5/512	UNKNOWN	24	22.5	1.5	6.3
R7/512	W3/512	UNKNOWN	34	29.5	4.5	13.2
R7/512	W4/512	UNKNOWN	34	29.5	4.5	13.2
R9/512	W1/512	UNKNOWN	34	29.5	4.5	13.2
R9/512	W2/512	UNKNOWN	34.5	29.5	5	14.5
R1/513	W13/513	UNKNOWN	36.5	27.5	9	24.7
R2/513	W11/513	UNKNOWN	36	26.5	9.5	26.4
R2/513	W12/513	UNKNOWN	36	26.5	9.5	26.4
R4/513	W9/513	UNKNOWN	36	25	11	30.6
R4/513	W10/513	UNKNOWN	35.5	25	10.5	29.6
R5/513	W6/513	UNKNOWN	36.5	31.5	5	13.7
R5/513	W7/513	UNKNOWN	37	31.5	5.5	14.9
R5/513	W8/513	UNKNOWN	37	27	10	27.0
R6/513	W5/513	UNKNOWN	26	24	2	7.7
R7/513	W3/513	UNKNOWN	35	29.5	5.5	15.7
R7/513	W4/513	UNKNOWN	35	29.5	5.5	15.7
R9/513	W1/513	UNKNOWN	34	29.5	4.5	13.2
R9/513	W2/513	UNKNOWN	34.5	29.5	5	14.5
R1/521	W2/521	UNKNOWN	31.5	21	10.5	33.3
R2/521	W1/521	UNKNOWN	25	23.5	1.5	6.0
R1/522	W2/522	UNKNOWN	32	22	10	31.3
R2/522	W1/522	UNKNOWN	26.5	24	2.5	9.4
R1/523	W2/523	UNKNOWN	33	23	10	30.3
R2/523	W1/523	UNKNOWN	28.5	25	3.5	12.3
769 HIGH ROAD						
R1/531	W1/531	UNKNOWN	35.5	26	9.5	26.8
R2/531	W2/531	UNKNOWN	35.5	26	9.5	26.8

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R1/532	W1/532	UNKNOWN	36.5	27	9.5	26.0
R2/532	W2/532	UNKNOWN	36.5	27.5	9	24.7
771 HIGH ROAD						
R3/531	W3/531	UNKNOWN	35	26	9	25.7
R4/531	W4/531	UNKNOWN	35	26	9	25.7
R3/532	W3/532	UNKNOWN	36.5	27.5	9	24.7
R4/532	W4/532	UNKNOWN	36	28	8	22.2
771a HIGH ROAD						
R5/531	W5/531	UNKNOWN	29	21.5	7.5	25.9
773 HIGH ROAD						
R1/541	W1/541	UNKNOWN	34.5	27	7.5	21.7
R2/541	W2/541	UNKNOWN	34	27.5	6.5	19.1
R1/542	W1/542	UNKNOWN	35.5	28.5	7	19.7
R2/542	W2/542	UNKNOWN	35.5	28.5	7	19.7
775 HIGH ROAD						
R3/541	W3/541	UNKNOWN	34	28	6	17.6
R4/541	W4/541	UNKNOWN	34	28.5	5.5	16.2
R3/542	W3/542	UNKNOWN	35.5	29.5	6	16.9
R4/542	W4/542	UNKNOWN	35.5	30	5.5	15.5
777-779-781 HIGH ROAD						
R1/551	W1/551	UNKNOWN	33.5	28.5	5	14.9
R2/551	W2/551	UNKNOWN	33.5	29	4.5	13.4
R3/551	W3/551	UNKNOWN	33.5	29	4.5	13.4
R4/551	W4/551	UNKNOWN	33.5	29.5	4	11.9
R1/552	W1/552	UNKNOWN	35	30	5	14.3
R2/552	W2/552	UNKNOWN	35	30	5	14.3
R3/552	W3/552	UNKNOWN	35	30.5	4.5	12.9
R4/552	W4/552	UNKNOWN	35	30.5	4.5	12.9
783 HIGH ROAD						

Vertical Sky Component						
Room	**Window**	**Room Use**	Existing	Proposed	Loss	**%**
R7/561	**W1/561**	UNKNOWN	34	29.5	4.5	13.2
R8/561	**W2/561**	UNKNOWN	34	30	4	11.8
R7/562	**W1/562**	UNKNOWN	35.5	31	4.5	12.7
R8/562	**W2/562**	UNKNOWN	35.5	31	4.5	12.7
R1/563	**W1/563**	UNKNOWN	2.5	2.5	0	0.0
R1/564	**W1/564**	UNKNOWN	4.5	4.5	0	0.0
R1/565	**W1/565**	UNKNOWN	37.5	32.5	5	13.3
785 HIGH ROAD						
R1/561	**W3/561**	UNKNOWN	34	30	4	11.8
R2/561	**W4/561**	UNKNOWN	34	30	4	11.8
R1/562	**W3/562**	UNKNOWN	35.5	31	4.5	12.7
R2/562	**W4/562**	UNKNOWN	35.5	31.5	4	11.3
787 HIGH ROAD						
R3/561	**W5/561**	UNKNOWN	34	30.5	3.5	10.3
R4/561	**W6/561**	UNKNOWN	34	30.5	3.5	10.3
R3/562	**W5/562**	UNKNOWN	35.5	31.5	4	11.3
R4/562	**W6/562**	UNKNOWN	35.5	31.5	4	11.3
789 HIGH ROAD						
R5/561	**W7/561**	UNKNOWN	34	30.5	3.5	10.3
R6/561	**W8/561**	UNKNOWN	34	31	3	8.8
R5/562	**W7/562**	UNKNOWN	35	31.5	3.5	10.0
R6/562	**W8/562**	UNKNOWN	35	31	4	11.4
791 HIGH ROAD						
R9/561	**W9/561**	UNKNOWN	34	31	3	8.8
R10/561	**W10/561**	UNKNOWN	33.5	30.5	3	9.0
R10/561	**W11/561**	UNKNOWN	33	32.5	0.5	1.5
R10/561	**W12/561**	UNKNOWN	32.5	32.5	0	0.0
R11/561	**W13/561**	UNKNOWN	33	33	0	0.0
R11/561	**W14/561**	UNKNOWN	33.5	33.5	0	0.0
R9/562	**W9/562**	UNKNOWN	34.5	31	3.5	10.1
R10/562	**W10/562**	UNKNOWN	34.5	31.5	3	8.7

Vertical Sky Component						
Room	Window	Room Use	Existing	Proposed	Loss	%
R10/562	W11/562	UNKNOWN	34.5	34	0.5	1.4
R10/562	W12/562	UNKNOWN	35	35	0	0.0
R11/562	W13/562	UNKNOWN	34.5	34.5	0	0.0
R11/562	W14/562	UNKNOWN	35	35	0	0.0
793-795 HIGH ROAD (BANK)						
R1/571	W3/571	UNKNOWN	34	31	3	8.8
R2/571	W7/571	UNKNOWN	34.5	32.5	2	5.8
R3/571	W8/571	UNKNOWN	34.5	32.5	2	5.8
R3/571	W9/571	UNKNOWN	34.5	32.5	2	5.8
R4/571	W4/571	UNKNOWN	34.5	31	3.5	10.1
R4/571	W5/571	UNKNOWN	34.5	31	3.5	10.1
R4/571	W6/571	UNKNOWN	35	32.5	2.5	7.1
R5/571	W1/571	UNKNOWN	34	31.5	2.5	7.4
R5/571	W2/571	UNKNOWN	33.5	31.5	2	6.0
R1/572	W3/572	UNKNOWN	36	32.5	3.5	9.7
R2/572	W7/572	UNKNOWN	36	33	3	8.3
R3/572	W8/572	UNKNOWN	36	33	3	8.3
R3/572	W9/572	UNKNOWN	36	33.5	2.5	6.9
R4/572	W4/572	UNKNOWN	36	33	3	8.3
R4/572	W5/572	UNKNOWN	36	32	4	11.1
R4/572	W6/572	UNKNOWN	36	33	3	8.3
R5/572	W1/572	UNKNOWN	35.5	33	2.5	7.0
R5/572	W2/572	UNKNOWN	35.5	32.5	3	8.5
R1/573	W1/573	UNKNOWN	38	35	3	7.9
R2/573	W2/573	UNKNOWN	38.5	35	3.5	9.1
R3/573	W3/573	UNKNOWN	38	35	3	7.9
R3/573	W4/573	UNKNOWN	38	34	4	10.5
R3/573	W5/573	UNKNOWN	37.5	35	2.5	6.7
R4/573	W6/573	UNKNOWN	37.5	35	2.5	6.7
797 HIGH ROAD						
R1/581	W1/581	UNKNOWN	34	32	2	5.9
R2/581	W2/581	UNKNOWN	34	32	2	5.9
R1/582	W1/582	UNKNOWN	36	33.5	2.5	6.9
R2/582	W2/582	UNKNOWN	36	33.5	2.5	6.9
799 HIGH ROAD						
R1/591	W1/591	UNKNOWN	34	32	2	5.9

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R2/591	W2/591	UNKNOWN	33.5	32	1.5	4.5
R1/592	W1/592	UNKNOWN	35.5	33.5	2	5.6
R2/592	W2/592	UNKNOWN	35.5	33.5	2	5.6
801 HIGH ROAD						
R1/601	W1/601	UNKNOWN	34	32.5	1.5	4.4
R2/601	W2/601	UNKNOWN	34	32	2	5.9
R1/602	W1/602	UNKNOWN	35.5	33.5	2	5.6
R2/602	W2/602	UNKNOWN	35	33.5	1.5	4.3
803 HIGH ROAD						
R3/601	W3/601	UNKNOWN	34	32.5	1.5	4.4
R3/601	W4/601	UNKNOWN	34.5	33	1.5	4.3
R4/601	W5/601	UNKNOWN	34.5	33	1.5	4.3
R4/601	W6/601	UNKNOWN	34.5	33	1.5	4.3
R3/602	W3/602	UNKNOWN	35	33.5	1.5	4.3
R3/602	W4/602	UNKNOWN	35.5	34	1.5	4.2
R4/602	W5/602	UNKNOWN	35.5	34	1.5	4.2
R4/602	W6/602	UNKNOWN	35.5	34	1.5	4.2
805 HIGH ROAD						
R5/601	W7/601	UNKNOWN	34.5	33	1.5	4.3
R5/601	W8/601	UNKNOWN	34.5	33.5	1	2.9
R5/602	W7/602	UNKNOWN	36	34.5	1.5	4.2
R5/602	W8/602	UNKNOWN	36	35	1	2.8
809 HIGH ROAD						
R1/621	W1/621	UNKNOWN	35	34	1	2.9
R1/621	W2/621	UNKNOWN	35	34.5	0.5	1.4
R1/621	W3/621	UNKNOWN	35	34.5	0.5	1.4
R2/621	W4/621	UNKNOWN	35.5	34.5	1	2.8
R2/621	W5/621	UNKNOWN	35.5	34.5	1	2.8
R1/622	W1/622	Bedroom	36	34.5	1.5	4.2
R2/622	W2/622	Bedroom	36	35	1	2.8
813 HIGH ROAD						
R1/631	W1/631	UNKNOWN	35	34.5	0.5	1.4
R1/631	W2/631	UNKNOWN	35	34.5	0.5	1.4
R1/632	W1/632	UNKNOWN	37	36	1	2.7

Vertical Sky Component						
Room	**Window**	**Room Use**	Existing	Proposed	Loss	**%**
R1/632	**W2/632**	UNKNOWN	37	36	1	2.7
815 HIGH ROAD						
R2/631	**W3/631**	UNKNOWN	35.5	35	0.5	1.4
R2/631	**W4/631**	UNKNOWN	35.5	35	0.5	1.4
R2/632	**W3/632**	UNKNOWN	37	36	1	2.7
R2/632	**W4/632**	UNKNOWN	37	36	1	2.7
817 HIGH ROAD						
R3/631	**W5/631**	UNKNOWN	35.5	35	0.5	1.4
R3/632	**W5/632**	UNKNOWN	37	36	1	2.7
819 HIGH ROAD						
R1/641	**W1/641**	UNKNOWN	36.5	35.5	1	2.7
R1/641	**W2/641**	UNKNOWN	36.5	35.5	1	2.7
R2/641	**W3/641**	Bedroom	36.5	35.5	1	2.7
R2/641	**W4/641**	Bedroom	36	35.5	0.5	1.4
R1/642	**W1/642**	UNKNOWN	37.5	36.5	1	2.7
R1/642	**W2/642**	UNKNOWN	37.5	36.5	1	2.7
R2/642	**W3/642**	Bedroom	37.5	36.5	1	2.7
R2/642	**W4/642**	Bedroom	37.5	36.5	1	2.7
821 HIGH ROAD						
R3/641	**W5/641**	UNKNOWN	35.5	35	0.5	1.4
R3/641	**W6/641**	UNKNOWN	30.5	30	0.5	1.6
R3/642	**W5/642**	UNKNOWN	37.5	36.5	1	2.7
R3/642	**W6/642**	UNKNOWN	37.5	36.5	1	2.7
823 HIGH ROAD						
R4/641	**W7/641**	UNKNOWN	35.5	35	0.5	1.4
R4/641	**W8/641**	UNKNOWN	35.5	35	0.5	1.4
R5/641	**W9/641**	UNKNOWN	35.5	35	0.5	1.4
R5/641	**W10/641**	UNKNOWN	35.5	35	0.5	1.4
R6/641	**W11/641**	UNKNOWN	35.5	35	0.5	1.4
R6/641	**W12/641**	UNKNOWN	35.5	35	0.5	1.4
825 HIGH ROAD						
R1/651	**W1/651**	UNKNOWN	36	35.5	0.5	1.4
R1/651	**W2/651**	UNKNOWN	36	35.5	0.5	1.4
827 HIGH ROAD						
R2/651	**W3/651**	UNKNOWN	33.5	33.5	0	0.0

Vertical Sky Component						
Room	Window	Room Use	Existing	Proposed	Loss	%
R2/651	W4/651	UNKNOWN	36	35.5	0.5	1.4
820 HIGH ROAD						
R4/11	W4/11	UNKNOWN	35	35	0	0.0
R4/12	W4/12	UNKNOWN	37	36.5	0.5	1.4
814 HIGH ROAD						
R1/821	W1/821	UNKNOWN	34.5	34	0.5	1.4
R1/821	W2/821	UNKNOWN	34	33.5	0.5	1.5
R2/821	W3/821	UNKNOWN	34.5	34	0.5	1.4
R2/821	W4/821	UNKNOWN	35	34.5	0.5	1.4
R1/831	W3/831	UNKNOWN	33	32.5	0.5	1.5
R1/831	W4/831	UNKNOWN	34.5	34.5	0	0.0
R2/831	W2/831	UNKNOWN	30.5	29.5	1	3.3
R3/831	W1/831	UNKNOWN	29.5	28.5	1	3.4
R4/831	W5/831	UNKNOWN	35	35	0	0.0
808 HIGH ROAD						
R1/791	W1/791	UNKNOWN	33.5	33	0.5	1.5
R1/792	W1/792	Unknown	34	33	1	2.9
R1/795	W1/795	UNKNOWN	34	33.5	0.5	1.5
R1/796	W1/796	UNKNOWN	36	35	1	2.8
R1/797	W1/797	UNKNOWN	36.5	35	1.5	4.1
R2/797	W2/797	UNKNOWN	36.5	35.5	1	2.7
R1/800	W1/800	UNKNOWN	31	31	0	0.0
R1/801	W1/801	UNKNOWN	34.5	33.5	1	2.9
R1/801	W2/801	UNKNOWN	34.5	33.5	1	2.9
R1/801	W3/801	UNKNOWN	35.5	34.5	1	2.8
R1/802	W1/802	UNKNOWN	36.5	35.5	1	2.7
806b HIGH ROAD						
R1/770	W1/770	UNKNOWN	27	25	2	7.4
R1/771	W5/771	UNKNOWN	31	29	2	6.5
R1/771	W6/771	UNKNOWN	31.5	29.5	2	6.3
R2/771	W3/771	UNKNOWN	29	28.5	0.5	1.7
R2/771	W4/771	UNKNOWN	30	28.5	1.5	5.0
R3/771	W1/771	UNKNOWN	30.5	28.5	2	6.6

Vertical Sky Component

Room	Window	Room Use	Existing	Proposed	Loss	%
R3/771	W2/771	UNKNOWN	30	29	1	3.3
806 HIGH ROAD						
R3/781	W3/781	UNKNOWN	31.5	30.5	1	3.2
R4/781	W4/781	UNKNOWN	29.5	28.5	1	3.4
R5/781	W5/781	UNKNOWN	23.5	23	0.5	2.1
R6/781	W6/781	UNKNOWN	25.5	24.5	1	3.9
R3/782	W4/782	UNKNOWN	34.5	33	1.5	4.3
R4/782	W5/782	UNKNOWN	33	31.5	1.5	4.5
R6/782	W6/782	UNKNOWN	30	28.5	1.5	5.0
R1/788	W1/788	UNKNOWN	20.5	19.5	1	4.9
804 HIGH ROAD						
R1/761	W1/761	UNKNOWN	27.5	24	3.5	12.7
R1/761	W2/761	UNKNOWN	28.5	25	3.5	12.3
R1/761	W3/761	UNKNOWN	26.5	26	0.5	1.9
R2/761	W4/761	UNKNOWN	27	26.5	0.5	1.9
R1/781	W1/781	UNKNOWN	28.5	28.5	0	0.0
R2/781	W2/781	UNKNOWN	30.5	30	0.5	1.6
R1/782	W1/782	UNKNOWN	32.5	32.5	0	0.0
R1/782	W2/782	UNKNOWN	33	32.5	0.5	1.5
R2/782	W3/782	UNKNOWN	34	33	1	2.9
R1/785	W1/785	UNKNOWN	23.5	23.5	0	0.0
R1/786	W1/786	UNKNOWN	26	26	0	0.0
R1/787	W1/787	UNKNOWN	26	26	0	0.0
794 HIGH ROAD						
R1/674	W1/674	UNKNOWN	16	16	0	0.0
R1/674	W2/674	UNKNOWN	12	12	0	0.0
R1/675	W1/675	UNKNOWN	22.5	21.5	1	4.4
R1/675	W2/675	UNKNOWN	19	19	0	0.0
R1/676	W10/676	UNKNOWN	21.5	21	0.5	2.3
R1/680	W1/680	UNKNOWN	19.5	16	3.5	17.9
R1/681	W1/681	UNKNOWN	28.5	22.5	6	21.1
R1/682	W1/682	UNKNOWN	36.5	26.5	10	27.4
R1/689	W2/689	UNKNOWN	22	17.5	4.5	20.5
R1/689	W3/689	UNKNOWN	8.5	7.5	1	11.8

Vertical Sky Component						
Room	**Window**	**Room Use**	Existing	Proposed	Loss	**%**
R1/690	**W1/690**	UNKNOWN	18.5	13	5.5	29.7
R1/690	**W2/690**	UNKNOWN	30.5	23.5	7	23.0
R1/690	**W3/690**	UNKNOWN	26	24.5	1.5	5.8
R3/690	**W5/690**	UNKNOWN	16	15.5	0.5	3.1
R3/690	**W6/690**	UNKNOWN	16.5	16	0.5	3.0
R1/691	**W1/691**	UNKNOWN	27.5	17	10.5	38.2
R1/691	**W2/691**	UNKNOWN	34	25	9	26.5
R1/691	**W3/691**	UNKNOWN	28.5	27	1.5	5.3
R1/692	**W1/692**	UNKNOWN	36	27.5	8.5	23.6
790 HIGH ROAD						
R1/660	**W1/660**	UNKNOWN	34	17	17	50.0
R2/660	**W2/660**	UNKNOWN	33.5	17.5	16	47.8
R3/660	**W3/660**	UNKNOWN	31.5	16	15.5	49.2
R4/660	**W4/660**	UNKNOWN	25.5	11	14.5	56.9
R1/661	**W1/661**	UNKNOWN	36	19.5	16.5	45.8
R2/661	**W2/661**	UNKNOWN	36	20	16	44.4
R3/661	**W3/661**	UNKNOWN	35	20	15	42.9
R4/661	**W4/661**	UNKNOWN	29.5	16	13.5	45.8
R1/662	**W1/662**	UNKNOWN	37	21	16	43.2
R2/662	**W2/662**	UNKNOWN	37	21.5	15.5	41.9
R3/662	**W3/662**	UNKNOWN	37	22	15	40.5
R4/662	**W4/662**	UNKNOWN	36	22.5	13.5	37.5
7 WHITE HART LANE						
R1/981	**W1/981**	UNKNOWN	32	31.5	0.5	1.6
9-39 WHITE HART LANE						
R1/990	**W1/990**	UNKNOWN	15	14	1	6.7
R1/991	**W1/991**	UNKNOWN	17	15	2	11.8
R1/992	**W1/992**	UNKNOWN	19	16	3	15.8
R1/993	**W1/993**	UNKNOWN	27	24	3	11.1
8 WILLIAM STREET						
R2/970	**W2/970**	UNKNOWN	21.5	21	0.5	2.3
R3/970	**W3/970**	UNKNOWN	25.5	25	0.5	2.0
R4/970	**W4/970**	UNKNOWN	25	24.5	0.5	2.0

Vertical Sky Component						
Room	Window	Room Use	Existing	Proposed	Loss	%
R2/971	W2/971	UNKNOWN	24.5	24.5	0	0.0
R3/971	W3/971	UNKNOWN	30.5	29.5	1	3.3
R4/971	W4/971	UNKNOWN	31	29.5	1.5	4.8
R2/972	W2/972	UNKNOWN	32.5	30.5	2	6.2
R3/972	W3/972	UNKNOWN	36	33	3	8.3
R4/972	W4/972	UNKNOWN	36.5	33.5	3	8.2
1 MOSELLE STREET						
R1/970	W1/970	UNKNOWN	30	28	2	6.7
R1/971	W1/971	UNKNOWN	33	30.5	2.5	7.6
R1/972	W1/972	UNKNOWN	36	32.5	3.5	9.7
ERMINE HOUSE						
R1/960	W1/960	UNKNOWN	33.5	27.5	6	17.9
R1/960	W3/960	UNKNOWN	30.5	28	2.5	8.2
R2/960	W2/960	UNKNOWN	26.5	22	4.5	17.0
R2/960	W4/960	UNKNOWN	32	31.5	0.5	1.6
R1/961	W1/961	UNKNOWN	35.5	28.5	7	19.7
R1/961	W3/961	UNKNOWN	31.5	29	2.5	7.9
R2/961	W2/961	UNKNOWN	28	23.5	4.5	16.1
R2/961	W4/961	UNKNOWN	33.5	33.5	0	0.0
R1/962	W1/962	UNKNOWN	37	29.5	7.5	20.3
R1/962	W3/962	UNKNOWN	32.5	29.5	3	9.2
R2/962	W2/962	UNKNOWN	29.5	25	4.5	15.3
R2/962	W4/962	UNKNOWN	35	35	0	0.0

DAYLIGHT DISTRIBUTION (NSL)

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
3 NORTHUMBERLAND PARK								
R1/21	UNKNOWN	134.39	129.04	127.55	1.49	1.15	96.02	94.91
R2/21	UNKNOWN	127.68	122.39	122.39	0.00	0.00	95.86	95.86
R3/21	UNKNOWN	93.56	51.24	51.24	0.00	0.00	54.77	54.77
R1/22	UNKNOWN	134.39	129.04	128.96	0.08	0.07	96.02	95.96
R2/22	UNKNOWN	127.68	122.27	122.27	0.00	0.00	95.77	95.77
R3/22	UNKNOWN	93.56	85.41	85.41	0.00	0.00	91.29	91.29
5 NORTHUMBERLAND PARK								
R1/31	UNKNOWN	100.61	99.09	98.81	0.28	0.29	98.48	98.20
R2/31	UNKNOWN	111.20	108.98	108.98	0.00	0.00	98.00	98.00
R1/32	UNKNOWN	100.61	99.09	99.09	0.00	0.00	98.48	98.48
R2/32	UNKNOWN	111.20	108.98	108.98	0.00	0.00	98.00	98.00
7 NORTHUMBERLAND PARK								
R1/41	UNKNOWN	217.85	205.45	200.62	4.84	2.35	94.31	92.09
R1/42	UNKNOWN	217.85	208.74	205.43	3.31	1.59	95.82	94.30
9 NORTHUMBERLAND PARK								
R2/41	UNKNOWN	217.24	198.76	195.36	3.40	1.71	91.49	89.93
R2/42	UNKNOWN	217.24	204.04	202.82	1.22	0.60	93.92	93.36
11 NORTHUMBERLAND PARK								
R3/41	UNKNOWN	217.83	193.73	191.14	2.58	1.33	88.93	87.75
R3/42	UNKNOWN	217.83	200.25	199.29	0.96	0.48	91.93	91.49
13 NORTHUMBERLAND PARK								
R1/51	UNKNOWN	118.85	107.26	106.69	0.57	0.53	90.25	89.77
R2/51	UNKNOWN	108.63	107.09	106.68	0.41	0.39	98.58	98.20
R1/52	UNKNOWN	118.85	111.76	111.42	0.33	0.30	94.03	93.75
R2/52	UNKNOWN	108.63	107.26	107.25	0.02	0.02	98.74	98.72
15 NORTHUMBERLAND PARK								
R3/51	UNKNOWN	106.96	96.04	95.62	0.41	0.43	89.79	89.40
R4/51	UNKNOWN	108.20	102.33	102.02	0.31	0.30	94.58	94.29
R3/52	UNKNOWN	106.96	100.69	100.50	0.18	0.18	94.13	93.96
R4/52	UNKNOWN	108.20	104.74	104.62	0.12	0.12	96.81	96.69
17 NORTHUMBERLAND PARK								
R5/51	UNKNOWN	102.05	88.17	87.79	0.38	0.43	86.40	86.03
R6/51	UNKNOWN	104.49	93.24	92.90	0.33	0.36	89.23	88.91
R5/52	UNKNOWN	102.05	92.98	92.61	0.37	0.39	91.11	90.75
R6/52	UNKNOWN	104.49	97.19	96.90	0.29	0.30	93.01	92.73
19 NORTHUMBERLAND PARK								
R7/51	UNKNOWN	106.96	85.64	85.48	0.16	0.19	80.07	79.91
R8/51	UNKNOWN	90.58	74.61	74.49	0.11	0.15	82.37	82.24
R7/52	UNKNOWN	106.96	93.31	93.05	0.25	0.27	87.24	87.00
R8/52	UNKNOWN	90.58	79.69	79.45	0.24	0.30	87.98	87.72
21 NORTHUMBERLAND PARK								
R9/51	UNKNOWN	193.07	166.55	166.55	0.00	0.00	86.27	86.27
R9/52	UNKNOWN	193.07	172.59	172.48	0.11	0.06	89.39	89.34
23 NORTHUMBERLAND PARK								
R1/60	UNKNOWN	203.34	168.20	168.20	0.00	0.00	82.72	82.72
R2/60	UNKNOWN	82.35	76.35	76.35	0.00	0.00	92.71	92.71
R1/61	UNKNOWN	203.34	184.39	184.39	0.00	0.00	90.68	90.68
R2/61	UNKNOWN	100.98	89.83	89.83	0.00	0.00	88.96	88.96
R1/65	UNKNOWN	74.17	60.29	60.29	0.00	0.00	81.29	81.29
R1/70	UNKNOWN	202.03	190.76	190.76	0.00	0.00	94.42	94.42
R1/71	UNKNOWN	115.82	97.65	97.65	0.00	0.00	84.31	84.31
29 NORTHUMBERLAND PARK								

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R1/80	UNKNOWN	157.70	139.85	139.85	0.00	0.00	88.68	88.68
R2/80	UNKNOWN	44.57	0.00	0.00	0.00	#DIV/0!	0.00	0.00
R3/80	UNKNOWN	35.27	33.40	33.40	0.00	0.00	94.71	94.71
R1/81	UNKNOWN	157.70	156.57	156.57	0.00	0.00	99.28	99.28
R2/81	UNKNOWN	44.57	43.09	43.09	0.00	0.00	96.67	96.67
R1/82	UNKNOWN	157.70	147.53	147.53	0.00	0.00	93.55	93.55
31 NORTHUMBERLAND PARK								
R4/80	UNKNOWN	166.11	160.30	160.30	0.00	0.00	96.50	96.50
R5/80	UNKNOWN	60.16	50.87	50.87	0.00	0.00	84.55	84.55
R6/80	UNKNOWN	43.93	31.63	31.63	0.00	0.00	72.00	72.00
R4/81	UNKNOWN	166.11	158.92	158.92	0.00	0.00	95.68	95.68
R4/82	UNKNOWN	166.11	118.46	118.46	0.00	0.00	71.32	71.32
33 NORTHUMBERLAND PARK								
R1/90	UNKNOWN	71.92	64.93	64.93	0.00	0.00	90.28	90.28
R2/90	UNKNOWN	166.22	160.87	160.87	0.00	0.00	96.78	96.78
R1/91	UNKNOWN	71.92	54.59	54.59	0.00	0.00	75.90	75.90
R2/91	UNKNOWN	166.22	157.01	157.01	0.00	0.00	94.46	94.46
35 NORTHUMBERLAND PARK								
R3/90	UNKNOWN	168.71	162.99	162.99	0.00	0.00	96.61	96.61
R4/90	UNKNOWN	73.47	0.02	0.02	0.00	0.00	0.03	0.03
R3/91	UNKNOWN	168.71	159.77	159.77	0.00	0.00	94.70	94.70
R4/91	UNKNOWN	75.10	59.20	58.40	0.81	1.36	78.84	77.76
37 NORTHUMBERLAND PARK								
R1/100	UNKNOWN	168.77	162.85	162.85	0.00	0.00	96.49	96.49
R2/100	UNKNOWN	35.62	14.67	14.68	-0.01	-0.03	41.18	41.20
R3/100	UNKNOWN	33.45	15.71	15.71	0.00	0.00	46.98	46.98
R1/101	UNKNOWN	168.77	161.99	161.99	0.00	0.00	95.98	95.98
R2/101	UNKNOWN	72.79	71.75	71.75	0.00	0.00	98.57	98.57
39 NORTHUMBERLAND PARK								
R4/100	UNKNOWN	60.95	43.17	43.17	0.00	0.00	70.83	70.83
R5/100	UNKNOWN	168.57	162.70	162.70	0.00	0.00	96.52	96.52
R4/101	UNKNOWN	60.95	60.41	60.41	0.00	0.00	99.12	99.12
R5/101	UNKNOWN	168.57	160.22	160.21	0.02	0.01	95.05	95.04
41 NORTHUMBERLAND PARK								
R1/110	UNKNOWN	75.46	63.15	63.15	0.00	0.00	83.69	83.69
R2/110	UNKNOWN	132.16	128.01	128.01	0.00	0.00	96.86	96.86
R1/111	UNKNOWN	81.13	80.13	80.13	0.00	0.00	98.77	98.77
R2/111	UNKNOWN	132.16	128.55	128.55	0.00	0.00	97.27	97.27
43 NORTHUMBERLAND PARK								
R3/110	UNKNOWN	130.06	126.08	126.08	0.00	0.00	96.95	96.95
R4/110	UNKNOWN	82.03	70.62	70.62	0.00	0.00	86.08	86.08
R3/111	UNKNOWN	130.06	126.59	126.59	0.00	0.00	97.34	97.34
R4/111	UNKNOWN	82.03	81.14	81.14	0.00	0.00	98.92	98.92
45 NORTHUMBERLAND PARK								
R1/120	UNKNOWN	52.13	47.54	47.54	0.00	0.00	91.20	91.20
R2/120	UNKNOWN	78.88	68.75	68.75	0.00	0.00	87.16	87.16
R3/120	UNKNOWN	129.26	125.93	125.93	0.00	0.00	97.43	97.43
R1/121	UNKNOWN	80.34	79.47	79.47	0.00	0.00	98.91	98.91
R3/121	UNKNOWN	129.26	125.90	125.90	0.00	0.00	97.40	97.40
47 NORTHUMBERLAND PARK								
R4/120	UNKNOWN	131.81	128.20	128.20	0.00	0.00	97.26	97.26
R5/120	UNKNOWN	82.29	48.62	48.62	0.00	0.00	59.08	59.08
R2/121	UNKNOWN	81.29	80.43	80.43	0.00	0.00	98.95	98.95
R4/121	UNKNOWN	131.81	128.36	128.36	0.00	0.00	97.38	97.38
49 NORTHUMBERLAND PARK								
R1/130	UNKNOWN	86.53	40.78	40.78	0.00	0.00	47.13	47.13
R2/130	UNKNOWN	129.07	125.86	125.86	0.00	0.00	97.51	97.51

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	% Loss	% Prev	% New
R1/131	UNKNOWN	79.69	78.98	78.98	0.00	0.00	99.11	99.11
R2/131	UNKNOWN	129.07	125.72	125.72	0.00	0.00	97.40	97.40
51 NORTHUMBERLAND PARK								
R3/130	UNKNOWN	128.36	125.06	125.06	0.00	0.00	97.43	97.43
R4/130	UNKNOWN	82.57	16.06	16.06	0.00	0.00	19.45	19.45
R3/131	UNKNOWN	128.36	125.03	125.03	0.00	0.00	97.41	97.41
R4/131	UNKNOWN	77.89	77.27	77.27	0.00	0.00	99.20	99.20
53 NORTHUMBERLAND PARK								
R1/150	UNKNOWN	239.18	235.61	235.61	0.00	0.00	98.51	98.51
R1/151	UNKNOWN	239.18	231.89	231.89	0.00	0.00	96.95	96.95
R3/151	UNKNOWN	109.69	68.27	68.27	0.00	0.00	62.24	62.24
55 NORTHUMBERLAND PARK								
R2/150	UNKNOWN	240.27	236.71	236.71	0.00	0.00	98.52	98.52
R2/151	UNKNOWN	240.27	232.73	232.73	0.00	0.00	96.86	96.86
57 NORTHUMBERLAND PARK								
R1/160	UNKNOWN	174.73	174.20	174.20	0.00	0.00	99.70	99.70
R2/160	UNKNOWN	193.50	192.46	192.46	0.00	0.00	99.46	99.46
R3/160	UNKNOWN	88.66	87.03	87.03	0.00	0.00	98.16	98.16
R4/160	UNKNOWN	179.23	165.04	165.04	0.00	0.00	92.09	92.09
R1/161	UNKNOWN	149.17	145.53	145.53	0.00	0.00	97.56	97.56
R2/161	UNKNOWN	111.89	109.51	109.51	0.00	0.00	97.87	97.87
R3/161	UNKNOWN	139.62	136.58	136.58	0.00	0.00	97.82	97.82
R4/161	UNKNOWN	179.23	159.59	157.38	2.20	1.38	89.04	87.81
BURLEIGH COURT								
R1/170	UNKNOWN	139.85	138.68	138.68	0.00	0.00	99.16	99.16
R2/170	UNKNOWN	144.67	143.11	143.11	0.00	0.00	98.92	98.92
R3/170	UNKNOWN	112.10	111.91	111.91	0.00	0.00	99.83	99.83
R4/170	UNKNOWN	117.36	117.17	117.17	0.00	0.00	99.84	99.84
R5/170	UNKNOWN	82.38	81.00	81.00	0.00	0.00	98.32	98.32
R6/170	UNKNOWN	113.70	113.45	113.45	0.00	0.00	99.78	99.78
R1/171	UNKNOWN	139.85	138.68	138.68	0.00	0.00	99.16	99.16
R2/171	UNKNOWN	144.67	143.11	143.11	0.00	0.00	98.92	98.92
R3/171	UNKNOWN	112.10	111.91	111.91	0.00	0.00	99.83	99.83
R4/171	UNKNOWN	117.36	117.17	117.17	0.00	0.00	99.84	99.84
R5/171	UNKNOWN	82.38	80.72	80.72	0.00	0.00	97.99	97.99
R6/171	UNKNOWN	113.70	113.45	113.45	0.00	0.00	99.78	99.78
R1/172	UNKNOWN	139.85	138.66	138.66	0.00	0.00	99.15	99.15
R2/172	UNKNOWN	144.67	143.07	143.07	0.00	0.00	98.89	98.89
R3/172	UNKNOWN	112.10	111.91	111.91	0.00	0.00	99.83	99.83
R4/172	UNKNOWN	117.36	117.17	117.17	0.00	0.00	99.84	99.84
R5/172	UNKNOWN	82.38	80.41	80.41	0.00	0.00	97.60	97.60
R6/172	UNKNOWN	113.70	113.45	113.45	0.00	0.00	99.77	99.77
R1/175	UNKNOWN	94.13	43.57	43.57	0.00	0.00	46.29	46.29
R1/176	UNKNOWN	94.13	85.20	85.20	0.00	0.00	90.51	90.51
19 BENNETS CLOSE								
R1/850	UNKNOWN	126.48	73.84	73.84	0.00	0.00	58.38	58.38
R1/851	UNKNOWN	126.48	122.84	122.84	0.00	0.00	97.12	97.12
R1/852	UNKNOWN	126.48	122.84	122.84	0.00	0.00	97.12	97.12
9-13 BENNETS CLOSE								
R1/860	UNKNOWN	97.50	77.87	77.87	0.00	0.00	79.87	79.87
R2/860	UNKNOWN	100.25	86.99	86.99	0.00	0.00	86.78	86.78
R3/860	UNKNOWN	129.40	126.64	126.64	0.00	0.00	97.87	97.87
R4/860	UNKNOWN	65.26	64.78	64.78	0.00	0.00	99.26	99.26
R5/860	UNKNOWN	67.52	66.81	66.81	0.00	0.00	98.95	98.95
R6/860	UNKNOWN	117.03	115.77	115.77	0.00	0.00	98.93	98.93
R1/861	UNKNOWN	97.50	95.25	95.25	0.00	0.00	97.70	97.70
R2/861	UNKNOWN	100.25	98.02	98.02	0.00	0.00	97.78	97.78
R3/861	UNKNOWN	129.40	126.64	126.64	0.00	0.00	97.87	97.87
R4/861	UNKNOWN	65.26	64.78	64.78	0.00	0.00	99.26	99.26
R5/861	UNKNOWN	67.52	66.81	66.81	0.00	0.00	98.95	98.95
R6/861	UNKNOWN	117.03	115.77	115.77	0.00	0.00	98.93	98.93
R1/862	UNKNOWN	97.50	95.25	95.25	0.00	0.00	97.70	97.70
R2/862	UNKNOWN	100.25	98.02	98.02	0.00	0.00	97.78	97.78

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	% Loss	% Prev	% New
R3/862	UNKNOWN	129.40	126.64	126.64	0.00	0.00	97.87	97.87
R4/862	UNKNOWN	65.26	64.78	64.78	0.00	0.00	99.26	99.26
R5/862	UNKNOWN	67.52	66.81	66.81	0.00	0.00	98.95	98.95
R6/862	UNKNOWN	117.03	115.77	115.77	0.00	0.00	98.93	98.93
R1/863	UNKNOWN	97.50	95.25	95.25	0.00	0.00	97.70	97.70
R2/863	UNKNOWN	100.25	98.02	98.02	0.00	0.00	97.78	97.78
R3/863	UNKNOWN	129.40	126.64	126.64	0.00	0.00	97.87	97.87
R4/863	UNKNOWN	65.26	64.78	64.78	0.00	0.00	99.26	99.26
R5/863	UNKNOWN	67.52	66.81	66.81	0.00	0.00	98.95	98.95
R6/863	UNKNOWN	117.03	115.77	115.77	0.00	0.00	98.93	98.93
50 NORTHUMBERLAND PARK								
R1/180	UNKNOWN	133.63	90.10	85.30	4.80	5.33	67.43	63.83
R2/180	UNKNOWN	88.18	15.51	31.99	-16.48	-106.27	17.59	36.27
R3/180	UNKNOWN	150.31	20.39	38.65	-18.25	-89.51	13.57	25.71
R1/181	UNKNOWN	131.40	119.53	119.53	0.00	0.00	90.97	90.97
R2/181	UNKNOWN	70.82	69.04	69.04	0.00	0.00	97.49	97.49
R1/182	UNKNOWN	219.57	217.89	217.53	0.36	0.17	99.24	99.07
R1/183	UNKNOWN	140.32	116.45	116.45	0.00	0.00	82.99	82.99
R2/183	UNKNOWN	116.75	84.99	84.99	0.00	0.00	72.80	72.80
R1/185	UNKNOWN	44.25	32.58	32.58	0.00	0.00	73.61	73.61
52 NORTHUMBERLAND PARK								
R3/181	UNKNOWN	118.77	117.19	111.00	6.19	5.28	98.67	93.45
R2/182	UNKNOWN	151.61	147.14	147.04	0.10	0.07	97.05	96.98
R3/183	Bedroom	139.29	129.16	129.16	0.00	0.00	92.73	92.73
R4/183	UNKNOWN	104.54	80.24	80.24	0.00	0.00	76.76	76.76
R1/190	UNKNOWN	109.40	105.58	87.81	17.76	16.83	96.51	80.27
R1/191	UNKNOWN	109.40	105.58	90.31	15.27	14.46	96.51	82.55
R1/192	UNKNOWN	106.81	102.74	96.43	6.31	6.14	96.18	90.28
R1/193	UNKNOWN	106.81	95.26	90.41	4.85	5.09	89.19	84.65
2 WORCESTER AVENUE								
R15/210	UNKNOWN	124.03	118.11	117.86	0.25	0.21	95.22	95.02
R16/210	KITCHEN	48.04	47.40	47.40	0.00	0.00	98.67	98.67
R17/211	UNKNOWN	30.90	27.43	27.43	0.00	0.00	88.78	88.78
R18/211	BEDROOM	114.17	112.44	112.43	0.01	0.01	98.48	98.47
4 WORCESTER AVENUE								
R13/210	UNKNOWN	124.03	119.80	119.79	0.01	0.01	96.58	96.58
R14/210	KITCHEN	49.75	48.61	48.61	0.00	0.00	97.71	97.71
R15/211	UNKNOWN	29.63	29.56	29.56	0.00	0.00	99.75	99.75
R16/211	BEDROOM	114.17	112.43	112.39	0.04	0.03	98.47	98.44
6 WORCESTER AVENUE								
R17/210	UNKNOWN	90.20	87.88	87.88	0.00	0.00	97.44	97.44
R18/210	KITCHEN	96.45	94.01	94.01	0.00	0.00	97.47	97.47
R13/211	UNKNOWN	30.90	30.74	30.74	0.00	0.00	99.48	99.48
R14/211	BEDROOM	114.17	112.80	112.80	0.00	0.00	98.79	98.79
8 WORCESTER AVENUE								
R11/210	UNKNOWN	124.03	119.98	119.87	0.11	0.09	96.74	96.65
R12/210	KITCHEN	49.75	49.40	49.40	0.00	0.00	99.30	99.30
R11/211	UNKNOWN	29.63	29.38	29.38	0.00	0.00	99.17	99.17
R12/211	BEDROOM	114.17	112.44	112.35	0.09	0.08	98.48	98.40
10 WORCESTER AVENUE								
R1/210	KITCHEN	84.25	71.57	62.06	9.51	13.29	84.95	73.66
R9/210	UNKNOWN	124.03	119.62	119.08	0.54	0.46	96.44	96.00
R9/211	UNKNOWN	30.90	30.80	30.80	0.00	0.00	99.68	99.67
R10/211	BEDROOM	114.17	112.77	112.77	0.00	0.00	98.77	98.77
12 WORCESTER AVENUE								
R8/210	KITCHEN	49.75	49.58	49.58	0.00	0.00	99.67	99.67
R10/210	UNKNOWN	124.03	119.69	119.38	0.31	0.26	96.50	96.25
R7/211	UNKNOWN	28.49	28.41	28.41	0.00	0.00	99.72	99.72
R8/211	BEDROOM	114.17	112.48	112.28	0.20	0.18	98.52	98.34

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
14 WORCESTER AVENUE								
R4/210	KITCHEN	49.75	48.68	48.68	0.00	0.00	97.87	97.87
R5/210	UNKNOWN	124.03	119.93	118.93	1.00	0.84	96.69	95.88
R5/211	UNKNOWN	30.90	30.78	30.78	0.00	0.00	99.61	99.61
R6/211	BEDROOM	114.17	112.77	112.76	0.01	0.01	98.77	98.77
16 WORCESTER AVENUE								
R6/210	UNKNOWN	124.03	121.09	120.41	0.68	0.56	97.62	97.08
R7/210	KITCHEN	49.75	47.55	47.55	0.00	0.00	95.59	95.59
R3/211	UNKNOWN	29.63	29.06	29.06	0.00	0.00	98.08	98.08
R4/211	BEDROOM	114.17	112.62	112.20	0.42	0.37	98.64	98.27
18 WORCESTER AVENUE								
R2/210	KITCHEN	49.75	48.60	48.60	0.00	0.00	97.70	97.70
R3/210	UNKNOWN	124.03	116.56	115.50	1.06	0.91	93.97	93.12
R1/211	UNKNOWN	30.90	30.71	30.71	0.00	0.00	99.40	99.40
R2/211	BEDROOM	114.17	111.43	111.31	0.12	0.11	97.60	97.49
1 WORCESTER AVENUE								
R1/220	UNKNOWN	111.35	110.38	110.38	0.00	0.00	99.13	99.13
R2/220	UNKNOWN	100.71	100.26	100.26	0.00	0.00	99.55	99.55
R3/220	UNKNOWN	61.10	58.76	58.76	0.00	0.00	96.18	96.18
R16/220	LIVINGROOM	168.47	168.46	168.46	0.00	0.00	100.00	100.00
R17/220	UNKNOWN	69.63	69.55	69.55	0.00	0.00	99.88	99.88
R15/221	BEDROOM	151.25	151.20	151.19	0.01	0.01	99.97	99.96
R16/221	BEDROOM	55.48	55.18	55.18	0.00	0.00	99.46	99.46
R17/221	UNKNOWN	55.34	36.48	36.48	0.00	0.00	65.93	65.93
3 WORCESTER AVENUE								
R18/220	LIVINGROOM	175.67	175.32	175.32	0.00	0.00	99.80	99.80
R19/220	BEDROOM	62.52	62.17	62.17	0.00	0.00	99.44	99.44
R13/221	BEDROOM	152.26	152.22	152.22	0.00	0.00	99.98	99.97
R14/221	BEDROOM	55.48	55.26	55.26	0.00	0.00	99.61	99.61
5 WORCESTER AVENUE								
R12/220	LIVINGROOM	168.47	167.94	167.94	0.00	0.00	99.69	99.69
R13/220	UNKNOWN	69.63	69.39	69.39	0.00	0.00	99.65	99.65
R11/221	BEDROOM	151.25	151.00	150.99	0.01	0.01	99.83	99.83
R12/221	BEDROOM	55.48	55.30	55.29	0.00	0.01	99.67	99.67
7 WORCESTER AVENUE								
R14/220	LIVINGROOM	175.67	174.79	174.79	0.00	0.00	99.50	99.50
R15/220	UNKNOWN	62.52	55.75	55.75	0.00	0.00	89.18	89.18
R9/221	BEDROOM	152.26	152.03	152.02	0.00	0.00	99.85	99.84
R10/221	BEDROOM	55.48	55.31	55.31	0.00	0.00	99.70	99.70
9 WORCESTER AVENUE								
R8/220	LIVINGROOM	168.47	167.94	167.94	0.00	0.00	99.69	99.68
R11/220	BEDROOM	69.63	61.80	61.80	0.00	0.00	88.76	88.76
R7/221	BEDROOM	151.25	151.17	151.15	0.02	0.02	99.94	99.93
R8/221	BEDROOM	55.48	55.21	55.21	0.00	0.00	99.52	99.52
11 WORCESTER AVENUE								
R9/220	LIVINGROOM	175.67	174.65	174.62	0.03	0.02	99.42	99.40
R10/220	UNKNOWN	62.52	54.18	54.18	0.00	0.00	86.67	86.67
R5/221	BEDROOM	152.26	152.19	152.19	0.00	0.00	99.95	99.95
R6/221	BEDROOM	55.48	55.31	55.31	0.00	0.00	99.70	99.70
13 WORCESTER AVENUE								
R4/220	LIVINGROOM	168.47	168.17	168.17	0.00	0.00	99.82	99.82
R5/220	UNKNOWN	69.63	61.02	61.02	0.00	0.00	87.63	87.63
R3/221	BEDROOM	151.25	151.10	151.08	0.03	0.02	99.90	99.88
R4/221	BEDROOM	55.48	55.27	55.26	0.01	0.02	99.63	99.61
15 WORCESTER AVENUE								
R6/220	LIVINGROOM	175.67	174.99	174.95	0.04	0.02	99.61	99.59

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R7/220	UNKNOWN	62.52	52.13	52.13	0.00	0.00	83.39	83.39
R1/221	BEDROOM	152.26	152.15	152.15	0.01	0.00	99.93	99.92
R2/221	BEDROOM	55.48	54.70	54.70	0.00	0.00	98.60	98.60
R18/221	UNKNOWN	47.04	2.39	2.39	0.00	0.00	5.09	5.09
17 WORCESTER AVENUE								
R9/230	LIVINGROOM	168.47	168.46	168.46	0.00	0.00	99.99	99.99
R10/230	UNKNOWN	69.63	43.52	43.52	0.00	0.00	62.49	62.49
R11/231	BEDROOM	151.25	151.20	151.15	0.05	0.03	99.96	99.93
R12/231	BEDROOM	55.48	51.57	51.57	0.00	0.00	92.95	92.95
19 WORCESTER AVENUE								
R11/230	LIVINGROOM	175.67	175.21	175.20	0.01	0.01	99.74	99.73
R12/230	UNKNOWN	62.52	55.71	55.71	0.00	0.00	89.12	89.12
R1/231	UNKNOWN	152.30	152.15	151.96	0.19	0.12	99.90	99.78
R2/231	UNKNOWN	55.48	55.32	55.31	0.00	0.00	99.71	99.71
21 WORCESTER AVENUE								
R7/230	LIVINGROOM	168.47	168.20	168.19	0.00	0.00	99.84	99.84
R8/230	UNKNOWN	69.63	61.68	61.68	0.00	0.00	88.58	88.58
R1/231	UNKNOWN	55.48	55.28	55.24	0.04	0.07	99.64	99.58
R2/231	UNKNOWN	151.25	150.99	150.98	0.01	0.01	99.83	99.82
23 WORCESTER AVENUE								
R5/230	LIVINGROOM	175.67	174.81	174.63	0.17	0.10	99.51	99.41
R6/230	UNKNOWN	62.52	62.26	57.51	4.75	7.64	99.59	91.99
R5/231	BEDROOM	152.26	152.02	148.38	3.64	2.39	99.84	97.45
R6/231	BEDROOM	55.48	55.40	51.06	4.33	7.82	99.85	92.04
25 WORCESTER AVENUE								
R1/230	LIVINGROOM	168.47	168.47	145.60	22.87	13.58	100.00	86.42
R2/230	UNKNOWN	69.63	69.37	48.98	20.38	29.38	99.62	70.34
R3/231	BEDROOM	151.25	150.99	131.86	19.13	12.67	99.82	87.18
R4/231	BEDROOM	55.48	55.29	46.58	8.71	15.75	99.67	83.97
27 WORCESTER AVENUE								
R3/230	LIVINGROOM	175.67	175.23	131.52	43.71	24.94	99.75	74.87
R4/230	UNKNOWN	62.52	56.47	16.44	40.04	70.89	90.33	26.29
R1/231	BEDROOM	152.26	151.95	102.87	49.08	32.30	99.79	67.56
R2/231	BEDROOM	55.48	53.84	29.14	24.70	45.89	97.05	52.52
29 WORCESTER AVENUE								
R1/380	UNKNOWN	70.30	35.31	8.34	26.96	76.37	50.22	11.87
R2/380	LIVINGROOM	168.47	168.36	77.94	90.41	53.70	99.93	46.27
R1/381	BEDROOM	55.48	55.24	28.17	27.07	49.00	99.57	50.78
R2/381	BEDROOM	151.25	151.01	71.34	79.67	52.76	99.84	47.17
31 WORCESTER AVENUE								
R3/380	LIVINGROOM	175.77	175.32	72.78	102.55	58.49	99.75	41.41
R4/380	UNKNOWN	62.23	43.74	4.05	39.69	90.74	70.29	6.51
R1/381	UNKNOWN	151.54	151.36	55.54	95.82	63.31	99.88	36.65
R2/381	UNKNOWN	55.48	55.34	18.54	36.80	66.50	99.76	33.42
33 WORCESTER AVENUE								
R5/380	UNKNOWN	59.75	39.78	0.58	39.19	98.54	66.57	0.97
R6/380	LIVINGROOM	178.98	178.55	64.32	114.24	63.98	99.76	35.94
R1/381	UNKNOWN	55.48	55.37	17.87	37.50	67.73	99.82	32.21
R2/381	UNKNOWN	151.25	151.18	52.22	98.96	65.46	99.95	34.52
35 WORCESTER AVENUE								
R7/380	LIVINGROOM	176.92	176.55	62.13	114.41	64.81	99.79	35.12
R8/380	UNKNOWN	59.85	40.93	1.21	39.72	97.04	68.38	2.02
R1/381	UNKNOWN	151.25	151.18	44.71	106.47	70.43	99.95	29.56
R2/381	UNKNOWN	55.48	55.47	17.11	38.36	69.15	99.98	30.84
37 WORCESTER AVENUE								

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R9/380	UNKNOWN	59.66	42.60	1.25	41.35	97.06	71.40	2.10
R10/380	LIVINGROOM	179.53	179.08	65.69	113.40	63.32	99.75	36.59
R1/381	UNKNOWN	55.48	55.43	17.21	38.22	68.96	99.91	31.01
R2/381	UNKNOWN	151.25	151.25	49.22	102.02	67.45	100.00	32.55
39 WORCESTER AVENUE								
R11/380	LIVINGROOM	171.28	170.98	70.86	100.13	58.56	99.83	41.37
R12/380	UNKNOWN	59.85	58.57	19.00	39.57	67.56	97.85	31.74
R1/381	UNKNOWN	151.25	151.25	48.41	102.84	67.99	100.00	32.01
R2/381	UNKNOWN	55.48	55.40	23.75	31.65	57.13	99.86	42.81
41 WORCESTER AVENUE								
R13/380	UNKNOWN	59.66	51.35	5.75	45.60	88.80	86.07	9.64
R14/380	LIVINGROOM	179.63	179.41	96.08	83.33	46.45	99.88	53.49
R15/380	UNKNOWN	142.94	127.90	38.27	89.62	70.07	89.48	26.78
R1/381	UNKNOWN	55.48	55.40	24.18	31.22	56.35	99.87	43.59
R2/381	UNKNOWN	151.25	151.09	68.54	82.55	54.64	99.90	45.32
NORTHUMBERLAND PARK COMMUNITY SCHOOL								
R1/245	UNKNOWN	983.53	983.51	628.91	354.60	36.05	100.00	63.94
R2/245	UNKNOWN	996.61	996.61	996.61	0.00	0.00	100.00	100.00
R1/246	UNKNOWN	717.32	717.32	717.32	0.00	0.00	100.00	100.00
R2/246	UNKNOWN	678.30	678.30	678.28	0.03	0.00	100.00	100.00
R3/246	UNKNOWN	116.79	116.43	76.59	39.84	34.22	99.69	65.58
ST PAUL-S AND ALL HALLOWS INFANT SCHOOL								
R1/250	UNKNOWN	355.38	233.05	264.06	-31.00	-13.30	65.58	74.30
R2/250	UNKNOWN	357.46	234.06	262.78	-28.72	-12.27	65.48	73.51
R4/250	UNKNOWN	328.52	328.52	281.57	46.95	14.29	100.00	85.71
R5/250	UNKNOWN	322.18	322.18	313.30	8.88	2.76	100.00	97.24
R1/260	UNKNOWN	283.69	283.69	283.69	0.00	0.00	100.00	100.00
R2/260	UNKNOWN	378.93	377.44	376.94	0.50	0.13	99.61	99.47
R1/270	UNKNOWN	282.36	206.88	202.22	4.66	2.25	73.27	71.62
R2/270	UNKNOWN	275.34	188.46	208.09	-19.63	-10.42	68.45	75.58
R3/270	UNKNOWN	211.97	152.30	160.46	-8.16	-5.36	71.85	75.70
R4/270	UNKNOWN	361.32	361.32	361.31	0.00	0.00	100.00	100.00
R1/280	UNKNOWN	133.31	132.24	131.16	1.08	0.82	99.20	98.39
R2/280	UNKNOWN	106.62	97.30	88.23	9.07	9.33	91.26	82.75
R3/280	UNKNOWN	122.90	118.12	117.98	0.14	0.12	96.11	95.99
R4/280	UNKNOWN	121.82	116.76	114.29	2.47	2.11	95.85	93.82
R1/281	UNKNOWN	129.43	65.29	86.60	-21.32	-32.65	50.44	66.91
R2/281	UNKNOWN	127.78	125.67	122.16	3.51	2.80	98.35	95.60
R3/281	UNKNOWN	129.77	125.49	122.62	2.87	2.28	96.70	94.49
R1/290	UNKNOWN	157.66	156.77	157.29	-0.53	-0.34	99.44	99.77
R2/290	UNKNOWN	193.21	190.65	190.67	-0.03	-0.01	98.67	98.69
R1/1000	UNKNOWN	254.23	252.55	160.77	91.78	36.34	99.34	63.24
R2/1000	UNKNOWN	261.98	260.80	167.39	93.41	35.82	99.55	63.90
R1/1001	UNKNOWN	254.23	252.60	169.21	83.38	33.01	99.36	66.56
R2/1001	UNKNOWN	261.98	260.80	177.32	83.48	32.01	99.55	67.69
56 PARK LANE								
R1/301	UNKNOWN	109.80	107.99	107.20	0.79	0.73	98.36	97.63
R2/301	UNKNOWN	109.35	106.63	87.99	18.64	17.48	97.51	80.47
R1/302	UNKNOWN	109.80	109.20	107.22	1.98	1.81	99.45	97.66
R2/302	UNKNOWN	109.35	106.64	89.00	17.64	16.54	97.52	81.39
54 PARK LANE								
R3/301	UNKNOWN	108.29	100.84	80.70	20.14	19.97	93.12	74.53
R4/301	UNKNOWN	105.06	102.71	91.06	11.65	11.34	97.76	86.67
R3/302	UNKNOWN	108.29	105.65	82.81	22.83	21.61	97.56	76.47
R4/302	UNKNOWN	105.06	102.71	91.34	11.37	11.07	97.76	86.94
52 PARK LANE								
R5/301	UNKNOWN	97.55	81.33	68.91	12.43	15.28	83.38	70.64
R6/301	UNKNOWN	107.30	94.10	87.47	6.64	7.05	87.70	81.51
R5/302	UNKNOWN	97.55	83.95	67.24	16.71	19.91	86.06	68.93
R6/302	UNKNOWN	107.30	94.71	85.16	9.55	10.09	88.26	79.36

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
50 PARK LANE								
R4/300	UNKNOWN	339.89	333.40	336.02	-2.62	-0.79	98.09	98.86
R7/301	UNKNOWN	103.30	67.70	63.91	3.79	5.60	65.54	61.87
R8/301	UNKNOWN	99.56	71.28	74.84	-3.56	-4.99	71.60	75.17
R7/302	UNKNOWN	103.30	71.70	63.79	7.91	11.03	69.42	61.76
R8/302	UNKNOWN	99.56	73.92	74.33	-0.40	-0.54	74.25	74.66
48 PARK LANE								
R9/301	UNKNOWN	107.47	50.57	51.34	-0.77	-1.53	47.06	47.78
R10/301	UNKNOWN	108.15	57.50	60.18	-2.68	-4.65	53.17	55.64
R9/302	UNKNOWN	107.47	55.85	50.72	5.13	9.18	51.97	47.20
R10/302	UNKNOWN	108.15	61.85	59.57	2.28	3.68	57.19	55.09
44 PARK LANE								
R1/320	UNKNOWN	162.65	73.01	132.46	-59.45	-81.43	44.89	81.44
R2/320	HALLWAY?	37.76	20.04	37.33	-17.29	-86.31	53.07	98.87
R1/321	UNKNOWN	142.06	76.13	122.18	-46.04	-60.48	53.59	86.01
R2/321	HALLWAY?	53.17	29.50	45.89	-16.39	-55.54	55.49	86.31
42 PARK LANE								
R3/320	HALLWAY?	54.98	14.51	45.50	-30.99	-213.53	26.39	82.75
R4/320	UNKNOWN	168.15	70.91	132.48	-61.57	-86.83	42.17	78.78
R3/321	HALLWAY?	127.26	65.82	107.38	-41.56	-63.15	51.72	84.38
R4/321	UNKNOWN	81.80	42.04	51.43	-9.38	-22.32	51.39	62.87
40 PARK LANE								
R5/320	UNKNOWN	133.54	50.05	110.44	-60.39	-120.65	37.48	82.70
R6/320	HALLWAY?	55.44	26.69	37.22	-10.53	-39.45	48.15	67.14
R5/321	UNKNOWN	133.54	70.06	119.24	-49.18	-70.21	52.46	89.29
R6/321	HALLWAY?	55.44	29.10	36.51	-7.41	-25.46	52.49	65.85
38 PARK LANE								
R7/320	HALLWAY?	54.14	19.45	15.96	3.49	17.93	35.92	29.48
R8/320	UNKNOWN	149.93	52.26	78.75	-26.49	-50.69	34.85	52.52
R7/321	HALLWAY?	54.14	28.83	23.38	5.45	18.91	53.25	43.18
R8/321	UNKNOWN	149.93	75.00	89.82	-14.82	-19.77	50.02	59.91
36 PARK LANE								
R1/340	UNKNOWN	139.89	24.32	99.16	-74.85	-307.81	17.38	70.88
R2/340	HALLWAY?	91.08	44.54	83.20	-38.66	-86.80	48.91	91.35
R1/341	UNKNOWN	139.89	63.34	117.78	-54.44	-85.94	45.28	84.19
R2/341	HALLWAY?	63.92	28.55	54.18	-25.64	-89.81	44.66	84.77
34 PARK LANE								
R3/340	HALLWAY?	54.81	13.14	34.87	-21.72	-165.32	23.97	63.61
R4/340	UNKNOWN	150.00	43.67	114.93	-71.26	-163.16	29.12	76.62
R3/341	HALLWAY?	54.81	25.45	45.53	-20.08	-78.89	46.43	83.06
R4/341	UNKNOWN	150.00	66.23	125.30	-59.07	-89.18	44.15	83.53
32 PARK LANE								
R5/340	UNKNOWN	140.56	40.41	104.53	-64.13	-158.71	28.75	74.37
R6/340	HALLWAY?	54.14	20.52	37.65	-17.14	-83.54	37.89	69.54
R5/341	UNKNOWN	140.56	60.02	108.59	-48.56	-80.90	42.70	77.25
R6/341	HALLWAY?	54.14	23.50	42.20	-18.70	-79.58	43.40	77.94
30 PARK LANE								
R7/340	HALLWAY?	50.09	16.39	36.24	-19.84	-121.04	32.73	72.33
R8/340	UNKNOWN	162.37	53.85	110.68	-56.82	-105.51	33.17	68.17
R7/341	HALLWAY?	199.56	87.76	162.97	-75.21	-85.70	43.98	81.67
28 PARK LANE								
R9/340	UNKNOWN	136.20	37.97	85.46	-47.48	-125.05	27.88	62.75
R10/340	HALLWAY?	62.65	23.01	13.45	9.56	41.55	36.72	21.47
R8/341	UNKNOWN	136.20	56.47	91.27	-34.80	-61.62	41.46	67.01

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R9/341	UNKNOWN	62.65	24.70	13.43	11.27	45.62	39.43	21.44
1 LANCASTER CLOSE								
R1/350	Unknown	115.78	110.38	96.04	14.34	12.99	95.34	82.95
R2/350	Unknown	90.63	65.85	60.54	5.31	8.07	72.65	66.79
R3/350	Unknown	89.31	75.99	72.10	3.89	5.12	85.09	80.73
R4/350	Unknown	115.36	108.77	107.07	1.70	1.57	94.29	92.81
R1/351	Unknown	115.78	114.26	112.41	1.85	1.62	98.68	97.08
R2/351	Unknown	90.63	88.23	86.18	2.05	2.33	97.35	95.08
R3/351	Unknown	89.31	77.55	65.94	11.61	14.97	86.83	73.84
R4/351	Unknown	115.36	107.18	106.01	1.17	1.09	92.91	91.89
2 LANCASTER CLOSE								
R1/350	Unknown	98.80	92.23	90.05	2.18	2.36	93.35	91.14
R2/350	Unknown	90.78	62.49	59.19	3.30	5.28	68.84	65.20
R3/350	Unknown	122.08	113.54	112.34	1.20	1.06	93.00	92.02
R1/351	Unknown	89.59	87.33	83.16	4.16	4.77	97.48	92.83
R2/351	Unknown	124.94	122.29	119.14	3.15	2.57	97.87	95.35
R3/351	Unknown	122.08	113.19	111.26	1.93	1.70	92.72	91.14
3 LANCASTER CLOSE								
R1/350	Unknown	139.07	135.45	134.17	1.28	0.95	97.40	96.48
R1/351	Unknown	107.56	107.04	106.24	0.80	0.74	99.51	98.77
R2/351	Unknown	85.56	84.17	82.27	1.91	2.27	98.38	96.15
CONCORD HOUSE								
R1/390	UNKNOWN	87.32	0.00	3.40	-3.40	#DIV/0!	0.00	3.89
R2/390	KITCHEN	81.47	17.20	7.34	9.86	57.35	21.11	9.01
R3/390	UNKNOWN	58.23	4.69	6.10	-1.41	-30.10	8.06	10.48
R4/390	UNKNOWN	55.54	6.94	6.44	0.50	7.20	12.50	11.60
R5/390	KITCHEN	75.97	28.38	15.77	12.61	44.42	37.35	20.76
R6/390	KITCHEN	81.26	58.57	19.85	38.72	66.11	72.08	24.43
R7/390	KITCHEN	75.73	54.34	20.75	33.59	61.82	71.76	27.40
R8/390	UNKNOWN	55.44	43.71	8.39	35.31	80.79	78.84	15.14
R9/390	UNKNOWN	58.04	54.04	8.48	45.56	84.31	93.10	14.61
R10/390	KITCHEN	81.19	58.16	13.32	44.84	77.10	71.64	16.40
R11/390	KITCHEN	75.72	53.23	14.62	38.61	72.53	70.30	19.31
R12/390	UNKNOWN	55.38	27.25	1.77	25.47	93.49	49.20	3.20
R13/390	UNKNOWN	57.97	46.84	2.66	44.17	94.31	80.80	4.59
R14/390	KITCHEN	81.18	48.24	3.02	45.22	93.74	59.42	3.72
R15/390	UNKNOWN	55.53	49.50	10.74	38.76	78.30	89.15	19.35
R16/390	UNKNOWN	58.44	55.26	8.71	46.55	84.25	94.56	14.90
R17/390	KITCHEN	81.59	58.30	26.26	32.03	54.95	71.45	32.19
R18/390	KITCHEN	75.79	59.12	23.32	35.81	60.57	78.01	30.76
R19/390	UNKNOWN	55.33	48.39	9.58	38.81	80.20	87.45	17.31
R20/390	UNKNOWN	57.91	54.35	8.44	45.91	84.48	93.85	14.57
R21/390	UNKNOWN	58.25	54.97	12.03	42.93	78.11	94.36	20.66
R22/390	KITCHEN	81.55	58.33	35.67	22.66	38.84	71.53	43.74
R23/390	KITCHEN	76.07	59.74	25.72	34.02	56.94	78.53	33.81
R24/390	UNKNOWN	132.51	129.05	93.43	35.62	27.60	97.39	70.51
R1/391	UNKNOWN	93.65	64.71	54.33	10.38	16.04	69.10	58.01
R2/391	BEDROOM	146.32	105.10	98.06	7.04	6.70	71.83	67.01
R3/391	BEDROOM	140.24	119.29	87.53	31.76	26.62	85.06	62.42
R4/391	BEDROOM	141.02	114.97	92.47	22.50	19.57	81.53	65.57
R5/391	BEDROOM	140.23	130.25	106.80	23.45	18.01	92.88	76.15
R6/391	BEDROOM	139.87	123.70	86.09	37.61	30.41	88.44	61.55
R7/391	BEDROOM	141.95	140.80	114.67	26.13	18.56	99.19	80.78
R8/391	BEDROOM	140.83	136.39	109.52	26.88	19.70	96.85	77.76
R9/391	BEDROOM	141.09	139.98	119.03	20.95	14.97	99.21	84.37
R10/391	BEDROOM	141.63	140.51	116.47	24.03	17.10	99.21	82.24
R11/391	BEDROOM	143.07	141.97	129.18	12.79	9.01	99.23	90.29
R12/391	BEDROOM	143.27	142.25	125.96	16.29	11.45	99.29	87.92
R1/392	UNKNOWN	87.32	63.82	50.30	13.52	21.19	73.09	57.60
R2/392	KITCHEN	83.06	32.50	19.65	12.85	39.53	39.12	23.66
R3/392	UNKNOWN	58.23	27.10	7.70	19.41	71.60	46.55	13.22
R4/392	UNKNOWN	56.21	14.32	0.00	14.32	100.00	25.48	0.00
R5/392	KITCHEN	78.33	45.86	16.97	28.90	63.01	58.55	21.66
R6/392	KITCHEN	83.06	70.07	28.70	41.37	59.04	84.35	34.55
R7/392	KITCHEN	78.22	65.73	30.39	35.34	53.77	84.03	38.85
R8/392	UNKNOWN	55.44	38.19	11.54	26.66	69.79	68.90	20.81
R9/392	UNKNOWN	58.04	44.83	5.62	39.20	87.45	77.23	9.69
R10/392	KITCHEN	83.01	69.77	23.27	46.49	66.64	84.05	28.04
R11/392	KITCHEN	78.19	65.57	21.66	43.91	66.97	83.86	27.70

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R12/392	UNKNOWN	56.05	27.62	6.28	21.34	77.26	49.27	11.20
R13/392	UNKNOWN	57.97	43.20	7.49	35.71	82.67	74.52	12.91
R14/392	KITCHEN	83.06	62.79	12.82	49.97	79.58	75.59	15.44
R15/392	UNKNOWN	56.28	43.89	1.92	41.97	95.62	77.97	3.41
R16/392	UNKNOWN	58.44	45.10	22.10	23.00	51.00	77.17	37.82
R17/392	KITCHEN	83.06	69.90	38.31	31.59	45.20	84.15	46.12
R18/392	KITCHEN	78.22	65.74	29.97	35.76	54.40	84.04	38.32
R19/392	UNKNOWN	56.09	42.95	0.40	42.55	99.06	76.58	0.72
R20/392	UNKNOWN	57.91	44.01	3.81	40.20	91.34	76.00	6.58
R21/392	UNKNOWN	58.25	46.92	37.32	9.60	20.46	80.55	64.07
R22/392	KITCHEN	83.06	70.20	54.78	15.42	21.97	84.52	65.95
R23/392	KITCHEN	78.22	65.68	36.49	29.18	44.43	83.96	46.66
R2/393	BEDROOM	142.81	123.17	116.88	6.30	5.11	86.25	81.84
R3/393	BEDROOM	140.24	130.94	99.64	31.30	23.90	93.37	71.05
R4/393	BEDROOM	141.02	128.81	105.75	23.06	17.90	91.34	74.99
R5/393	BEDROOM	140.23	137.51	125.14	12.37	9.00	98.06	89.24
R6/393	BEDROOM	139.87	134.60	95.51	39.09	29.04	96.23	68.28
R7/393	BEDROOM	145.52	144.33	134.26	10.08	6.98	99.19	92.26
R8/393	BEDROOM	140.83	138.85	126.00	12.85	9.26	98.59	89.47
R9/393	BEDROOM	142.29	141.18	132.92	8.26	5.85	99.22	93.41
R10/393	BEDROOM	141.63	140.51	131.01	9.49	6.76	99.21	92.51
R11/393	BEDROOM	138.64	137.59	135.40	2.19	1.59	99.24	97.66
R12/393	BEDROOM	143.23	142.26	136.52	5.74	4.04	99.33	95.32
2-2a PARK LANE								
R2/401	UNKNOWN	173.84	170.89	170.70	0.19	0.11	98.30	98.20
R2/402	UNKNOWN	108.92	86.01	75.69	10.32	12.00	78.96	69.49
R1/931	UNKNOWN	116.36	90.53	61.73	28.79	31.81	77.80	53.05
R2/931	UNKNOWN	98.37	67.05	55.64	11.41	17.01	68.15	56.56
2 VICARAGE ROAD								
R1/880	UNKNOWN	93.71	90.51	84.22	6.29	6.95	96.59	89.87
R1/881	UNKNOWN	93.71	86.33	58.49	27.84	32.25	92.13	62.42
28 BROMLEY ROAD								
R1/890	UNKNOWN	98.10	95.40	97.74	-2.35	-2.46	97.25	99.64
R1/891	UNKNOWN	98.10	95.79	97.76	-1.97	-2.06	97.64	99.65
29 BROMLEY ROAD								
R1/900	UNKNOWN	150.11	148.54	141.79	6.75	4.55	98.96	94.46
R1/901	UNKNOWN	150.11	149.52	135.48	14.04	9.39	99.61	90.26
38 BROMLEY ROAD								
R1/910	UNKNOWN	134.68	129.38	110.78	18.60	14.38	96.06	82.25
R1/911	UNKNOWN	134.68	129.39	111.66	17.73	13.70	96.07	82.91
COOMBES HOUSE								
R1/920	UNKNOWN	130.46	78.16	66.15	12.01	15.36	59.91	50.71
R2/920	UNKNOWN	181.90	174.66	170.97	3.70	2.12	96.02	93.99
R3/920	UNKNOWN	74.70	71.79	69.47	2.31	3.22	96.10	93.00
R4/920	UNKNOWN	141.16	137.99	127.42	10.57	7.66	97.75	90.27
R5/920	UNKNOWN	161.05	158.26	148.26	9.99	6.32	98.27	92.06
R6/920	UNKNOWN	153.39	153.13	137.98	15.15	9.89	99.83	89.96
R7/920	UNKNOWN	184.06	172.67	172.67	0.00	0.00	93.81	93.81
R8/920	UNKNOWN	68.62	66.50	66.50	0.00	0.00	96.91	96.91
R9/920	UNKNOWN	132.72	124.21	123.40	0.81	0.65	93.59	92.98
R10/920	UNKNOWN	158.45	142.61	125.59	17.02	11.94	90.00	79.26
R11/920	UNKNOWN	349.69	323.43	251.71	71.72	22.17	92.49	71.98
R1/921	UNKNOWN	130.46	80.94	70.74	10.20	12.60	62.04	54.23
R2/921	UNKNOWN	181.90	175.45	171.56	3.90	2.22	96.45	94.31
R3/921	UNKNOWN	74.70	71.79	69.54	2.25	3.13	96.10	93.09
R4/921	UNKNOWN	141.16	137.99	132.02	5.97	4.33	97.75	93.52
R5/921	UNKNOWN	131.17	128.70	128.70	0.00	0.00	98.11	98.11
R6/921	UNKNOWN	153.39	153.13	140.47	12.66	8.27	99.83	91.58
R7/921	UNKNOWN	224.37	205.15	205.15	0.00	0.00	91.44	91.43
R8/921	UNKNOWN	94.94	55.21	55.15	0.06	0.11	58.16	58.09
R2/922	UNKNOWN	181.90	175.52	171.84	3.67	2.09	96.49	94.47
R3/922	UNKNOWN	74.70	71.79	69.82	1.97	2.74	96.10	93.46
R4/922	UNKNOWN	141.16	137.99	134.70	3.29	2.39	97.75	95.42

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R5/922	UNKNOWN	131.17	128.70	128.70	0.00	0.00	98.11	98.11
R6/922	UNKNOWN	153.39	153.13	143.75	9.38	6.13	99.83	93.72
R7/922	UNKNOWN	224.37	207.50	207.50	0.00	0.00	92.48	92.48
R8/922	UNKNOWN	94.94	57.50	57.45	0.05	0.09	60.57	60.52
R2/923	UNKNOWN	181.90	175.55	172.23	3.32	1.89	96.51	94.68
R3/923	UNKNOWN	74.70	71.79	70.14	1.65	2.30	96.10	93.88
R4/923	UNKNOWN	141.16	137.99	135.71	2.28	1.66	97.75	96.14
R5/923	UNKNOWN	131.17	128.70	128.70	0.00	0.00	98.11	98.11
R6/923	UNKNOWN	153.39	153.13	147.70	5.43	3.55	99.83	96.29
R7/923	UNKNOWN	224.37	208.65	208.65	0.00	0.00	92.99	92.99
R8/923	UNKNOWN	94.94	65.61	65.57	0.04	0.07	69.11	69.07
705 HIGH ROAD								
R1/420	UNKNOWN	67.86	59.26	58.08	1.18	1.99	87.32	85.58
R1/421	UNKNOWN	67.86	65.98	65.91	0.07	0.11	97.23	97.12
R1/429	UNKNOWN	153.91	128.92	103.76	25.16	19.52	83.76	67.41
R1/430	UNKNOWN	84.22	74.62	73.87	0.75	1.00	88.60	87.71
R2/430	UNKNOWN	113.48	112.91	112.91	0.00	0.00	99.49	99.49
R1/431	UNKNOWN	90.03	84.00	76.01	7.98	9.51	93.30	84.43
R2/431	UNKNOWN	109.11	106.40	95.59	10.81	10.16	97.52	87.61
R1/435	UNKNOWN	135.57	129.98	129.90	0.08	0.06	95.88	95.82
R1/436	UNKNOWN	135.57	132.06	118.54	13.52	10.24	97.41	87.44
ST FRANCAIS DE SALES RC PRIMARY SCHOOL								
R1/450	UNKNOWN	278.37	275.51	275.50	0.01	0.00	98.97	98.97
R2/450	UNKNOWN	248.71	245.96	197.38	48.58	19.75	98.89	79.36
R3/450	UNKNOWN	239.83	234.77	181.61	53.16	22.64	97.89	75.73
R4/450	UNKNOWN	347.61	330.37	283.73	46.64	14.12	95.04	81.62
R5/450	UNKNOWN	241.84	235.35	175.50	59.85	25.43	97.32	72.57
R6/450	UNKNOWN	367.32	366.91	362.38	4.53	1.24	99.89	98.66
R7/450	UNKNOWN	192.26	192.13	160.34	31.80	16.55	99.94	83.40
R8/450	UNKNOWN	213.27	212.88	170.34	42.54	19.98	99.82	79.87
R9/450	UNKNOWN	261.75	203.11	179.94	23.17	11.41	77.60	68.75
R10/450	UNKNOWN	236.24	183.60	176.18	7.41	4.04	77.72	74.58
R1/451	UNKNOWN	278.37	277.53	277.53	0.00	0.00	99.70	99.70
R2/451	UNKNOWN	248.71	246.94	173.44	73.50	29.76	99.28	69.73
R3/451	UNKNOWN	239.83	229.06	107.81	121.24	52.93	95.51	44.95
R4/451	UNKNOWN	347.61	346.18	271.27	74.91	21.64	99.59	78.04
R5/451	UNKNOWN	241.84	239.16	230.80	8.36	3.50	98.89	95.43
R6/451	UNKNOWN	367.32	366.41	366.33	0.07	0.02	99.75	99.73
R7/451	UNKNOWN	261.75	260.81	221.33	39.48	15.14	99.64	84.56
R8/451	UNKNOWN	236.24	235.77	206.90	28.88	12.25	99.80	87.58
R1/455	UNKNOWN	219.55	216.97	215.87	1.10	0.51	98.83	98.32
R1/1020	UNKNOWN	295.78	251.40	171.73	79.67	31.69	85.00	58.06
R2/1020	UNKNOWN	344.42	251.04	162.86	88.18	35.13	72.89	47.28
R3/1020	UNKNOWN	362.82	314.43	247.86	66.58	21.17	86.66	68.31
729 HIGH ROAD								
R1/460	UNKNOWN	191.88	191.21	191.13	0.08	0.04	99.65	99.61
R2/460	UNKNOWN	216.31	211.59	191.24	20.35	9.62	97.82	88.41
R3/460	UNKNOWN	97.73	77.95	55.79	22.16	28.43	79.76	57.09
R4/460	UNKNOWN	94.77	92.16	92.13	0.03	0.03	97.24	97.22
R5/460	UNKNOWN	156.70	155.04	155.04	0.00	0.00	98.94	98.94
R1/461	UNKNOWN	191.88	191.18	189.63	1.55	0.81	99.63	98.83
R2/461	UNKNOWN	216.31	211.56	157.94	53.62	25.34	97.80	73.02
R3/461	UNKNOWN	97.73	95.80	81.74	14.05	14.67	98.02	83.64
R4/461	UNKNOWN	94.77	93.21	93.21	0.00	0.00	98.36	98.36
R5/461	UNKNOWN	156.70	155.52	155.52	0.00	0.00	99.25	99.25
R1/462	UNKNOWN	157.95	156.90	152.65	4.25	2.71	99.33	96.64
R2/462	Bedroom	157.59	143.47	97.95	45.51	31.72	91.04	62.16
4-18 BRERETON ROAD								
R1/940	UNKNOWN	59.30	52.19	40.27	11.92	22.84	88.00	67.91
R2/940	UNKNOWN	20.16	19.38	19.38	0.00	0.00	96.10	96.10
R3/940	UNKNOWN	100.01	90.93	67.36	23.57	25.92	90.92	67.35
R4/940	UNKNOWN	100.01	94.60	69.41	25.18	26.62	94.59	69.41
R5/940	UNKNOWN	20.38	10.52	10.41	0.12	1.11	51.63	51.06
R6/940	UNKNOWN	50.08	23.45	22.91	0.55	2.33	46.83	45.74
R7/940	UNKNOWN	51.75	21.69	21.11	0.58	2.68	41.91	40.79
R8/940	UNKNOWN	20.20	8.83	8.77	0.06	0.72	43.73	43.41
R9/940	UNKNOWN	100.01	72.53	55.98	16.55	22.82	72.52	55.97

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R10/940	UNKNOWN	100.01	72.04	58.18	13.87	19.25	72.04	58.17
R11/940	UNKNOWN	20.87	20.05	20.05	0.00	0.01	96.11	96.11
R12/940	UNKNOWN	52.28	39.26	35.31	3.95	10.06	75.10	67.54
R1/941	UNKNOWN	38.58	34.98	34.97	0.00	0.01	90.67	90.66
R2/941	UNKNOWN	103.61	92.67	89.11	3.56	3.85	89.44	86.01
R3/941	UNKNOWN	103.61	98.17	95.51	2.66	2.71	94.75	92.18
R4/941	UNKNOWN	38.58	25.53	25.46	0.07	0.26	66.17	66.00
R5/941	UNKNOWN	38.58	24.92	24.70	0.22	0.89	64.59	64.02
R6/941	UNKNOWN	103.61	93.83	82.78	11.05	11.78	90.57	79.90
R7/941	UNKNOWN	103.61	90.83	76.26	14.57	16.04	87.67	73.60
R8/941	UNKNOWN	38.58	33.48	32.52	0.96	2.87	86.79	84.29
R1/942	UNKNOWN	41.98	41.68	39.90	1.79	4.29	99.30	95.04
R2/942	UNKNOWN	21.24	19.96	19.94	0.03	0.13	94.00	93.87
R3/942	UNKNOWN	92.78	91.31	66.01	25.30	27.70	98.41	71.15
R4/942	UNKNOWN	92.78	89.90	66.72	23.17	25.78	96.89	71.91
R5/942	UNKNOWN	21.97	16.33	16.16	0.17	1.06	74.33	73.54
R6/942	UNKNOWN	40.80	26.08	25.26	0.82	3.13	63.93	61.92
R7/942	UNKNOWN	41.98	24.30	23.02	1.29	5.29	57.89	54.83
R8/942	UNKNOWN	21.24	13.77	13.49	0.28	2.05	64.84	63.52
R9/942	UNKNOWN	92.78	81.44	56.46	24.97	30.67	87.77	60.85
R10/942	UNKNOWN	92.78	88.31	57.54	30.77	34.84	95.18	62.01
R11/942	UNKNOWN	21.97	20.25	20.21	0.04	0.19	92.18	92.00
R12/942	UNKNOWN	40.80	40.49	37.12	3.37	8.33	99.25	90.98
R1/943	UNKNOWN	33.96	32.87	32.86	0.01	0.03	96.79	96.76
R2/943	UNKNOWN	118.14	112.44	105.93	6.51	5.79	95.18	89.67
R3/943	UNKNOWN	118.14	116.50	109.87	6.63	5.69	98.61	93.00
R4/943	UNKNOWN	29.51	28.50	28.50	0.00	0.01	96.59	96.58
R5/943	UNKNOWN	33.96	32.92	32.91	0.00	0.00	96.92	96.92
R6/943	UNKNOWN	118.14	113.75	101.10	12.66	11.13	96.29	85.58
R7/943	UNKNOWN	118.14	111.33	99.72	11.62	10.43	94.24	84.41
R8/943	UNKNOWN	29.51	28.50	28.50	0.00	0.01	96.57	96.57
LIBRARY-KATHLEEN FERRIER COURT								
R1/480	UNKNOWN	292.96	292.96	292.96	0.00	0.00	100.00	100.00
R2/480	UNKNOWN	3034.78	2937.79	2832.46	105.32	3.59	96.80	93.33
R1/481	LIVINGROOM	227.39	223.75	220.97	2.78	1.24	98.40	97.18
R2/481	LIVINGROOM	226.45	220.02	143.89	76.13	34.60	97.16	63.54
R3/481	LIVINGROOM	228.97	222.44	142.24	80.20	36.06	97.15	62.12
R4/481	LIVINGROOM	234.89	226.93	141.56	85.36	37.62	96.61	60.27
R5/481	UNKNOWN	295.00	268.90	257.82	11.08	4.12	91.15	87.40
R1/482	BEDROOM	108.89	105.91	105.59	0.32	0.30	97.26	96.97
R2/482	BEDROOM	69.29	68.34	68.34	0.00	0.00	98.62	98.62
R3/482	BEDROOM	127.58	126.07	119.48	6.59	5.23	98.82	93.65
R4/482	BEDROOM	71.69	68.57	50.46	18.11	26.41	95.64	70.38
R5/482	BEDROOM	67.63	64.75	42.79	21.96	33.92	95.74	63.27
R6/482	BEDROOM	120.25	116.56	51.22	65.34	56.06	96.93	42.59
R7/482	BEDROOM	117.55	113.92	46.87	67.05	58.86	96.91	39.87
R8/482	BEDROOM	70.57	67.55	45.22	22.33	33.05	95.72	64.09
R9/482	BEDROOM	71.56	68.39	41.92	26.47	38.71	95.57	58.57
R10/482	BEDROOM	120.62	116.66	46.09	70.56	60.49	96.71	38.21
R1/483	LIVINGROOM	227.39	225.78	224.95	0.83	0.37	99.29	98.93
R2/483	LIVINGROOM	228.65	221.23	148.86	72.37	32.71	96.75	65.10
R3/483	LIVINGROOM	228.97	222.07	149.20	72.86	32.81	96.98	65.16
R4/483	LIVINGROOM	234.89	226.62	146.66	79.96	35.28	96.48	62.44
R5/483	UNKNOWN	295.00	289.42	289.41	0.00	0.00	98.11	98.11
R1/484	BEDROOM	108.89	105.88	105.87	0.01	0.01	97.23	97.22
R2/484	BEDROOM	69.29	68.31	68.31	0.00	0.00	98.58	98.58
R3/484	BEDROOM	127.58	126.11	121.09	5.03	3.98	98.85	94.91
R4/484	BEDROOM	71.69	68.58	62.73	5.85	8.53	95.65	87.49
R5/484	BEDROOM	67.63	64.77	55.10	9.66	14.92	95.77	81.48
R6/484	BEDROOM	120.25	0.00	0.00	0.00	#DIV/0!	0.00	0.00
R7/484	BEDROOM	117.55	114.00	60.55	53.45	46.89	96.98	51.51
R8/484	BEDROOM	70.57	67.61	58.32	9.29	13.74	95.81	82.65
R9/484	BEDROOM	71.56	68.48	54.28	14.20	20.74	95.70	75.85
R10/484	BEDROOM	120.56	116.74	61.61	55.13	47.22	96.83	51.10
731 HIGH ROAD								
R1/491	UNKNOWN	102.34	101.09	30.69	70.40	69.64	98.78	29.99
R2/491	UNKNOWN	79.21	78.42	27.04	51.38	65.52	98.99	34.13
R1/492	UNKNOWN	102.34	100.17	31.24	68.94	68.82	97.89	30.52
R2/492	UNKNOWN	79.21	77.92	27.51	50.41	64.70	98.36	34.73
733 HIGH ROAD								
R3/491	UNKNOWN	75.12	74.20	25.76	48.44	65.29	98.77	34.29

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R4/491	UNKNOWN	85.38	84.01	28.97	55.04	65.51	98.39	33.93
R3/492	UNKNOWN	75.12	74.06	26.68	47.38	63.97	98.58	35.52
R4/492	UNKNOWN	85.38	83.90	29.82	54.08	64.46	98.26	34.92
735 HIGH ROAD								
R5/491	UNKNOWN	80.60	79.63	25.98	53.66	67.38	98.80	32.23
R6/491	UNKNOWN	85.60	84.11	28.12	55.99	66.57	98.26	32.85
R5/492	UNKNOWN	80.60	79.46	27.84	51.63	64.97	98.59	34.54
R6/492	UNKNOWN	85.60	84.03	29.62	54.41	64.75	98.17	34.60
R1/951	UNKNOWN	155.05	114.99	59.67	55.32	48.11	74.17	38.49
737 HIGH ROAD								
R7/491	UNKNOWN	85.30	84.15	26.49	57.65	68.52	98.64	31.06
R8/491	UNKNOWN	76.91	76.19	24.37	51.82	68.02	99.06	31.68
R7/492	UNKNOWN	85.30	83.99	28.64	55.35	65.90	98.46	33.57
R8/492	UNKNOWN	76.91	76.07	25.80	50.27	66.08	98.91	33.55
739 HIGH ROAD								
R9/491	UNKNOWN	80.52	79.59	24.94	54.65	68.67	98.85	30.97
R10/491	UNKNOWN	88.62	87.14	27.93	59.21	67.95	98.34	31.52
R9/492	UNKNOWN	80.52	79.49	26.44	53.05	66.73	98.73	32.84
R10/492	UNKNOWN	88.62	86.93	29.40	57.54	66.19	98.10	33.17
741 HIGH ROAD								
R11/491	UNKNOWN	81.95	80.85	25.11	55.74	68.95	98.65	30.63
R12/491	UNKNOWN	72.97	72.31	22.86	49.46	68.39	99.10	31.32
R11/492	UNKNOWN	81.95	80.72	26.58	54.14	67.07	98.50	32.43
R12/492	UNKNOWN	72.97	72.26	24.71	47.55	65.80	99.03	33.86
R1/495	UNKNOWN	52.13	48.19	14.42	33.77	70.08	92.44	27.66
R1/496	UNKNOWN	52.13	50.64	18.74	31.90	62.99	97.15	35.96
743 HIGH ROAD								
R1/501	UNKNOWN	122.31	120.65	23.90	96.75	80.19	98.65	19.54
R2/501	UNKNOWN	97.79	96.80	20.76	76.04	78.56	98.98	21.23
R1/502	UNKNOWN	122.31	120.66	28.83	91.83	76.11	98.65	23.57
R2/502	UNKNOWN	97.79	96.80	24.68	72.12	74.50	98.98	25.24
745 HIGH ROAD								
R3/501	Bedroom	99.94	97.28	18.85	78.43	80.63	97.34	18.86
R4/501	UNKNOWN	92.90	91.61	19.59	72.03	78.62	98.62	21.08
R3/502	UNKNOWN	99.94	98.57	24.29	74.27	75.36	98.63	24.31
R4/502	UNKNOWN	92.90	92.22	23.75	68.47	74.25	99.26	25.56
747 HIGH ROAD								
R5/501	UNKNOWN	95.42	94.33	20.39	73.94	78.38	98.86	21.37
R6/501	UNKNOWN	98.08	97.23	22.82	74.41	76.53	99.13	23.27
R5/502	UNKNOWN	95.42	94.33	23.48	70.85	75.11	98.86	24.61
R6/502	UNKNOWN	98.83	97.97	26.04	71.93	73.42	99.14	26.35
749 HIGH ROAD								
R7/501	UNKNOWN	98.33	94.35	14.21	80.14	84.94	95.95	14.45
R8/501	UNKNOWN	92.76	91.04	20.25	70.78	77.75	98.14	21.83
R7/502	UNKNOWN	98.33	97.00	24.50	72.50	74.74	98.65	24.92
R8/502	UNKNOWN	92.76	92.10	25.38	66.72	72.44	99.28	27.36
751 HIGH ROAD								
R9/501	UNKNOWN	100.94	99.75	23.03	76.71	76.91	98.81	22.82
R10/501	UNKNOWN	94.77	94.05	23.94	70.11	74.55	99.25	25.26
R9/502	UNKNOWN	100.94	99.75	26.61	73.13	73.32	98.81	26.37
R10/502	UNKNOWN	94.77	94.05	27.15	66.91	71.14	99.25	28.65
753 HIGH ROAD								
R11/501	UNKNOWN	102.55	101.09	23.95	77.14	76.31	98.58	23.36
R12/501	UNKNOWN	95.33	94.57	24.50	70.06	74.09	99.20	25.70
R11/502	UNKNOWN	102.55	101.22	27.87	73.35	72.47	98.70	27.17
R12/502	UNKNOWN	95.33	94.57	27.88	66.69	70.52	99.20	29.25

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
755 HIGH ROAD								
R13/501	UNKNOWN	97.80	96.25	22.82	73.43	76.29	98.41	23.33
R14/501	UNKNOWN	86.20	83.57	15.57	68.00	81.37	96.95	18.06
R13/502	UNKNOWN	97.80	96.25	26.41	69.84	72.56	98.41	27.01
R14/502	UNKNOWN	86.20	85.75	27.35	58.40	68.11	99.48	31.73
757 HIGH ROAD								
R15/501	UNKNOWN	93.22	92.29	24.51	67.78	73.44	99.00	26.29
R16/501	UNKNOWN	85.68	82.83	16.94	65.89	79.55	96.67	19.77
R15/502	UNKNOWN	93.22	92.29	28.12	64.16	69.53	99.00	30.17
R16/502	UNKNOWN	85.68	85.16	28.23	56.94	66.86	99.39	32.94
759 HIGH ROAD								
R17/501	UNKNOWN	156.17	154.87	95.59	59.28	38.27	99.17	61.21
R18/501	UNKNOWN	156.98	155.63	101.66	53.97	34.68	99.14	64.76
R19/501	UNKNOWN	101.33	99.76	39.94	59.82	59.96	98.46	39.42
R17/503	UNKNOWN	156.17	154.87	93.14	61.73	39.86	99.17	59.64
R18/503	UNKNOWN	156.98	155.65	99.01	56.64	36.39	99.15	63.07
R19/503	UNKNOWN	101.33	99.76	36.55	63.21	63.36	98.46	36.07
BERGAN-BROOKLYN APPARTMENTS								
R1/510	UNKNOWN	117.98	100.85	76.17	24.68	24.47	85.48	64.57
R2/510	UNKNOWN	199.78	199.20	183.99	15.21	7.64	99.71	92.09
R3/510	UNKNOWN	91.40	85.34	68.70	16.65	19.51	93.38	75.16
R4/510	UNKNOWN	212.24	211.76	185.75	26.01	12.28	99.78	87.52
R5/510	UNKNOWN	183.28	182.59	170.54	12.05	6.60	99.62	93.05
R6/510	UNKNOWN	95.79	68.90	68.75	0.15	0.21	71.93	71.77
R7/510	UNKNOWN	204.53	204.16	204.13	0.03	0.01	99.82	99.80
R8/510	UNKNOWN	91.40	84.72	84.68	0.04	0.05	92.69	92.65
R9/510	UNKNOWN	236.78	235.79	235.78	0.01	0.00	99.58	99.57
R1/511	UNKNOWN	117.98	101.16	69.31	31.85	31.49	85.75	58.75
R2/511	UNKNOWN	199.78	199.33	179.75	19.59	9.83	99.78	89.97
R4/511	UNKNOWN	212.24	211.81	179.50	32.31	15.26	99.80	84.58
R5/511	UNKNOWN	183.28	183.14	174.37	8.77	4.79	99.92	95.14
R6/511	UNKNOWN	95.79	77.82	77.42	0.40	0.52	81.24	80.82
R7/511	UNKNOWN	204.53	204.17	204.13	0.04	0.02	99.82	99.80
R9/511	UNKNOWN	236.78	235.79	235.77	0.02	0.01	99.58	99.57
R1/512	UNKNOWN	117.98	103.49	75.89	27.60	26.67	87.72	64.32
R2/512	UNKNOWN	199.78	199.42	185.40	14.02	7.03	99.82	92.80
R4/512	UNKNOWN	212.24	211.82	186.45	25.36	11.97	99.80	87.85
R5/512	UNKNOWN	183.28	183.27	182.29	0.98	0.54	100.00	99.46
R6/512	UNKNOWN	95.79	92.38	89.57	2.81	3.04	96.44	93.51
R7/512	UNKNOWN	204.53	204.18	204.18	0.00	0.00	99.83	99.83
R9/512	UNKNOWN	236.78	235.80	235.80	0.00	0.00	99.58	99.58
R1/513	UNKNOWN	117.98	113.07	83.33	29.74	26.30	95.84	70.63
R2/513	UNKNOWN	199.78	199.44	182.34	17.10	8.57	99.83	91.27
R4/513	UNKNOWN	212.24	211.81	184.20	27.61	13.04	99.80	86.79
R5/513	UNKNOWN	183.28	183.27	181.91	1.36	0.74	99.99	99.25
R6/513	UNKNOWN	95.79	92.25	88.05	4.19	4.54	96.30	91.93
R7/513	UNKNOWN	204.53	204.18	204.17	0.00	0.00	99.83	99.83
R9/513	UNKNOWN	236.78	235.78	235.78	0.00	0.00	99.58	99.58
R1/521	UNKNOWN	94.78	85.12	46.04	39.08	45.91	89.81	48.58
R2/521	UNKNOWN	96.53	90.88	90.88	0.00	0.00	94.14	94.14
R1/522	UNKNOWN	94.78	93.17	59.55	33.61	36.08	98.30	62.83
R2/522	UNKNOWN	96.53	94.22	94.22	0.00	0.00	97.61	97.60
R1/523	UNKNOWN	94.78	93.17	66.12	27.05	29.03	98.30	69.76
R2/523	UNKNOWN	96.53	94.32	94.32	0.00	0.00	97.71	97.71
769 HIGH ROAD								
R1/531	UNKNOWN	128.47	125.18	104.21	20.98	16.76	97.44	81.11
R2/531	UNKNOWN	91.14	90.48	64.85	25.63	28.33	99.28	71.15
R1/532	UNKNOWN	128.47	125.28	107.68	17.60	14.05	97.51	83.81
R2/532	UNKNOWN	91.14	90.48	70.28	20.20	22.33	99.28	77.11
771 HIGH ROAD								
R3/531	UNKNOWN	106.99	104.91	82.85	22.07	21.03	98.06	77.44
R4/531	UNKNOWN	81.16	80.70	57.86	22.84	28.30	99.43	71.29
R3/532	UNKNOWN	106.99	105.39	88.24	17.15	16.28	98.51	82.48
R4/532	UNKNOWN	81.16	80.74	62.25	18.49	22.90	99.49	76.71
771a HIGH ROAD								

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R5/531	UNKNOWN	126.64	120.15	96.77	23.38	19.46	94.87	76.41
773 HIGH ROAD								
R4/530	UNKNOWN	289.55	284.90	261.60	23.29	8.18	98.39	90.35
R1/541	UNKNOWN	96.06	95.17	77.76	17.41	18.29	99.08	80.95
R2/541	UNKNOWN	96.84	95.91	78.33	17.58	18.33	99.04	80.89
R1/542	UNKNOWN	96.06	95.15	80.07	15.08	15.85	99.05	83.35
R2/542	UNKNOWN	96.84	95.92	80.92	15.00	15.63	99.05	83.56
775 HIGH ROAD								
R3/541	UNKNOWN	90.69	89.38	78.48	10.90	12.19	98.56	86.54
R4/541	UNKNOWN	102.26	100.83	90.49	10.35	10.26	98.61	88.49
R3/542	UNKNOWN	90.69	90.04	79.89	10.16	11.28	99.29	88.09
R4/542	UNKNOWN	102.26	101.13	92.27	8.86	8.76	98.89	90.23
777-779-781 HIGH ROAD								
R1/551	UNKNOWN	112.23	110.68	95.20	15.48	13.98	98.61	84.82
R2/551	UNKNOWN	102.87	101.65	89.05	12.60	12.40	98.82	86.57
R3/551	UNKNOWN	90.37	89.74	83.82	5.93	6.60	99.30	92.75
R4/551	UNKNOWN	92.54	91.82	88.25	3.58	3.89	99.23	95.36
R1/552	UNKNOWN	112.23	110.68	97.96	12.71	11.49	98.61	87.29
R2/552	UNKNOWN	102.87	101.65	92.11	9.53	9.38	98.82	89.55
R3/552	UNKNOWN	90.37	89.74	86.87	2.87	3.20	99.30	96.13
R4/552	UNKNOWN	92.54	91.82	90.77	1.05	1.14	99.23	98.10
783 HIGH ROAD								
R7/561	UNKNOWN	143.85	142.39	132.58	9.81	6.89	98.99	92.17
R8/561	UNKNOWN	93.61	92.66	87.24	5.42	5.85	98.99	93.20
R7/562	UNKNOWN	143.12	141.68	133.59	8.08	5.71	99.00	93.35
R8/562	UNKNOWN	93.61	92.66	88.88	3.78	4.08	98.99	94.95
R1/563	UNKNOWN	75.83	8.44	8.44	0.00	0.00	11.13	11.13
R1/564	UNKNOWN	75.83	18.95	18.95	0.00	0.00	24.99	24.99
R1/565	UNKNOWN	75.83	74.23	74.23	0.00	0.00	97.90	97.90
785 HIGH ROAD								
R1/561	UNKNOWN	101.19	99.94	97.61	2.32	2.33	98.76	96.47
R2/561	UNKNOWN	99.21	98.01	97.43	0.58	0.59	98.79	98.21
R1/562	UNKNOWN	101.19	99.94	98.67	1.26	1.26	98.76	97.51
R2/562	UNKNOWN	99.21	98.01	97.78	0.23	0.24	98.79	98.55
787 HIGH ROAD								
R3/561	UNKNOWN	108.79	107.28	105.89	1.39	1.29	98.61	97.34
R4/561	UNKNOWN	103.69	102.42	101.73	0.69	0.67	98.77	98.11
R3/562	UNKNOWN	108.79	107.35	106.10	1.25	1.16	98.67	97.53
R4/562	UNKNOWN	103.69	102.48	101.94	0.54	0.53	98.83	98.31
789 HIGH ROAD								
R5/561	UNKNOWN	106.81	105.40	104.84	0.56	0.53	98.68	98.15
R6/561	UNKNOWN	96.82	95.82	95.82	0.00	0.00	98.97	98.97
R5/562	UNKNOWN	106.81	105.42	105.28	0.14	0.14	98.70	98.56
R6/562	UNKNOWN	96.82	95.82	95.82	0.00	0.00	98.97	98.97
791 HIGH ROAD								
R9/561	UNKNOWN	117.70	115.74	115.21	0.54	0.46	98.34	97.88
R10/561	UNKNOWN	156.47	156.47	156.47	0.00	0.00	100.00	100.00
R11/561	UNKNOWN	137.62	132.18	132.18	0.00	0.00	96.05	96.05
R9/562	UNKNOWN	117.70	115.74	115.52	0.22	0.19	98.34	98.15
R10/562	UNKNOWN	156.47	156.47	156.47	0.00	0.00	100.00	100.00
R11/562	UNKNOWN	137.62	132.35	132.35	0.00	0.00	96.17	96.17
793-795 HIGH ROAD (BANK)								
R1/571	UNKNOWN	101.35	99.75	99.03	0.72	0.73	98.43	97.72
R2/571	UNKNOWN	103.07	101.83	101.83	0.00	0.00	98.80	98.80
R3/571	UNKNOWN	195.38	192.32	192.32	0.00	0.00	98.43	98.43
R4/571	UNKNOWN	151.74	151.57	151.57	0.00	0.00	99.89	99.89
R5/571	UNKNOWN	214.14	209.87	207.58	2.29	1.09	98.01	96.94
R1/572	UNKNOWN	101.35	99.76	99.75	0.01	0.01	98.43	98.43

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R2/572	UNKNOWN	103.07	101.83	101.83	0.00	0.00	98.80	98.80
R3/572	UNKNOWN	195.38	192.32	192.32	0.00	0.00	98.43	98.43
R4/572	UNKNOWN	151.74	151.57	151.57	0.00	0.00	99.89	99.89
R5/572	UNKNOWN	214.14	209.87	209.72	0.15	0.07	98.01	97.94
R1/573	UNKNOWN	146.42	135.10	133.98	1.12	0.83	92.27	91.50
R2/573	UNKNOWN	94.44	90.92	90.92	0.00	0.00	96.27	96.27
R3/573	UNKNOWN	203.96	197.47	197.47	0.00	0.00	96.81	96.81
R4/573	UNKNOWN	183.72	141.54	141.48	0.06	0.04	77.04	77.01
797 HIGH ROAD								
R1/581	UNKNOWN	109.68	106.63	106.63	0.00	0.00	97.22	97.22
R2/581	UNKNOWN	97.79	96.23	96.23	0.00	0.00	98.41	98.41
R1/582	UNKNOWN	109.68	106.51	106.51	0.00	0.00	97.11	97.11
R2/582	UNKNOWN	97.79	96.19	96.19	0.00	0.00	98.37	98.37
799 HIGH ROAD								
R1/591	UNKNOWN	100.44	99.01	99.01	0.00	0.00	98.58	98.58
R2/591	UNKNOWN	98.35	97.15	97.15	0.00	0.00	98.78	98.78
R1/592	UNKNOWN	100.44	98.93	98.93	0.00	0.00	98.50	98.50
R2/592	UNKNOWN	98.35	96.99	96.99	0.00	0.00	98.62	98.62
801 HIGH ROAD								
R1/601	UNKNOWN	115.50	113.96	113.96	0.00	0.00	98.66	98.66
R2/601	UNKNOWN	112.31	110.10	110.10	0.00	0.00	98.03	98.03
R1/602	UNKNOWN	115.50	113.96	113.96	0.00	0.00	98.66	98.66
R2/602	UNKNOWN	112.31	110.10	110.10	0.00	0.00	98.03	98.03
803 HIGH ROAD								
R3/601	UNKNOWN	160.43	157.94	157.94	0.00	0.00	98.44	98.44
R4/601	UNKNOWN	151.59	149.40	149.40	0.00	0.00	98.56	98.56
R3/602	UNKNOWN	160.43	157.94	157.94	0.00	0.00	98.44	98.44
R4/602	UNKNOWN	151.59	149.40	149.40	0.00	0.00	98.56	98.56
805 HIGH ROAD								
R5/601	UNKNOWN	234.62	163.77	163.76	0.01	0.00	69.80	69.80
R5/602	UNKNOWN	234.62	163.78	163.77	0.01	0.00	69.81	69.80
809 HIGH ROAD								
R1/621	UNKNOWN	248.15	246.35	246.35	0.00	0.00	99.28	99.28
R2/621	UNKNOWN	160.67	159.39	159.39	0.00	0.00	99.20	99.20
R1/622	Bedroom	146.49	126.83	126.83	0.00	0.00	86.58	86.58
R2/622	Bedroom	131.60	115.32	115.32	0.00	0.00	87.63	87.63
813 HIGH ROAD								
R1/631	UNKNOWN	197.47	195.67	195.67	0.00	0.00	99.09	99.09
R1/632	UNKNOWN	197.47	195.58	195.58	0.00	0.00	99.05	99.04
815 HIGH ROAD								
R2/631	UNKNOWN	213.18	210.14	210.14	0.00	0.00	98.58	98.58
R2/632	UNKNOWN	213.18	210.21	210.20	0.01	0.00	98.61	98.61
817 HIGH ROAD								
R3/631	UNKNOWN	134.26	131.21	131.21	0.00	0.00	97.73	97.72
R3/632	UNKNOWN	134.26	131.24	131.24	0.00	0.00	97.75	97.75
819 HIGH ROAD								
R1/641	UNKNOWN	152.27	151.49	151.49	0.00	0.00	99.49	99.49
R2/641	Bedroom	190.03	187.99	187.99	0.00	0.00	98.92	98.92
R1/642	UNKNOWN	152.27	151.41	151.41	0.00	0.00	99.44	99.44
R2/642	Bedroom	190.03	187.88	187.88	0.00	0.00	98.87	98.87
821 HIGH ROAD								
R3/641	UNKNOWN	160.79	159.58	159.58	0.00	0.00	99.25	99.25
R3/642	UNKNOWN	160.79	159.54	159.54	0.00	0.00	99.22	99.22

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
823 HIGH ROAD								
R4/641	UNKNOWN	148.05	147.58	147.58	0.00	0.00	99.68	99.68
R5/641	UNKNOWN	159.91	159.08	159.08	0.00	0.00	99.48	99.48
R6/641	UNKNOWN	165.86	164.87	164.87	0.00	0.00	99.41	99.41
825 HIGH ROAD								
R1/651	UNKNOWN	252.05	250.80	250.80	0.00	0.00	99.50	99.50
827 HIGH ROAD								
R2/651	UNKNOWN	185.76	183.39	183.39	0.00	0.00	98.73	98.73
820 HIGH ROAD								
R4/11	UNKNOWN	87.45	86.79	86.79	0.00	0.00	99.24	99.24
R4/12	UNKNOWN	87.45	86.79	86.79	0.00	0.00	99.24	99.24
814 HIGH ROAD								
R1/821	UNKNOWN	131.94	126.85	126.85	0.00	0.00	96.14	96.14
R2/821	UNKNOWN	136.29	131.00	131.00	0.00	0.00	96.12	96.12
R1/831	UNKNOWN	110.64	110.33	110.33	0.01	0.01	99.72	99.72
R2/831	UNKNOWN	87.83	84.95	84.95	0.00	0.00	96.72	96.72
R3/831	UNKNOWN	107.99	105.47	105.46	0.01	0.01	97.66	97.65
R4/831	UNKNOWN	89.80	87.81	87.81	0.00	0.00	97.78	97.78
808 HIGH ROAD								
R1/791	UNKNOWN	133.44	130.75	130.75	0.00	0.00	97.98	97.98
R1/792	Unknown	150.70	123.89	123.89	0.00	0.00	82.21	82.21
R1/795	UNKNOWN	95.89	91.16	91.16	0.00	0.00	95.07	95.07
R1/796	UNKNOWN	95.89	93.28	93.28	0.00	0.00	97.28	97.28
R1/797	UNKNOWN	112.70	94.34	94.34	0.00	0.00	83.71	83.71
R2/797	UNKNOWN	154.98	126.77	126.77	0.00	0.00	81.80	81.80
R1/800	UNKNOWN	203.67	196.48	196.48	0.00	0.00	96.47	96.47
R1/801	UNKNOWN	126.56	120.51	120.51	0.00	0.00	95.22	95.22
R1/802	UNKNOWN	126.56	124.27	124.27	0.00	0.00	98.19	98.19
806b HIGH ROAD								
R1/770	UNKNOWN	149.02	142.69	142.69	0.00	0.00	95.75	95.75
R1/771	UNKNOWN	216.79	213.43	209.34	4.09	1.92	98.45	96.57
R2/771	UNKNOWN	208.44	205.91	194.10	11.81	5.74	98.79	93.12
R3/771	UNKNOWN	230.98	228.18	221.90	6.29	2.75	98.79	96.07
806 HIGH ROAD								
R3/781	UNKNOWN	143.86	140.59	140.59	0.00	0.00	97.72	97.72
R4/781	UNKNOWN	114.57	108.62	108.62	0.00	0.00	94.81	94.81
R5/781	UNKNOWN	77.26	71.80	71.80	0.00	0.00	92.94	92.93
R6/781	UNKNOWN	90.96	88.99	88.99	0.00	0.00	97.84	97.84
R3/782	UNKNOWN	143.86	140.66	140.66	0.00	0.00	97.77	97.77
R4/782	UNKNOWN	114.57	107.09	107.09	0.00	0.00	93.47	93.47
R6/782	UNKNOWN	90.96	89.61	89.61	0.00	0.00	98.52	98.52
R1/788	UNKNOWN	90.92	82.33	82.33	0.00	0.00	90.55	90.55
804 HIGH ROAD								
R1/761	UNKNOWN	199.78	199.01	186.05	12.96	6.51	99.61	93.13
R2/761	UNKNOWN	180.74	117.88	117.88	0.00	0.00	65.22	65.22
R1/781	UNKNOWN	105.14	100.62	100.62	0.00	0.00	95.71	95.71
R2/781	UNKNOWN	121.68	118.20	118.20	0.00	0.00	97.14	97.14
R1/782	UNKNOWN	158.02	151.19	151.19	0.00	0.00	95.67	95.67
R2/782	UNKNOWN	121.68	118.79	118.78	0.00	0.00	97.62	97.62
R1/785	UNKNOWN	54.16	46.50	46.50	0.00	0.00	85.85	85.85
R1/786	UNKNOWN	54.80	54.57	54.57	0.00	0.00	99.59	99.59
R1/787	UNKNOWN	72.29	69.65	69.65	0.00	0.00	96.35	96.35
794 HIGH ROAD								

Room / Floor	Room Use	Whole Room	Prev sq ft	New sq ft	Loss sq ft	%Loss	%Prev	%New
R1/674	UNKNOWN	46.58	44.74	44.74	0.00	0.00	96.06	96.06
R1/675	UNKNOWN	49.56	49.19	49.18	0.00	0.01	99.24	99.23
R1/676	UNKNOWN	65.72	59.44	59.37	0.07	0.12	90.45	90.34
R1/680	UNKNOWN	55.35	52.49	50.79	1.70	3.24	94.83	91.76
R1/681	UNKNOWN	83.64	82.86	80.53	2.32	2.80	99.06	96.28
R1/682	UNKNOWN	60.34	59.62	59.62	0.00	0.00	98.82	98.82
R1/689	UNKNOWN	190.39	148.82	122.21	26.61	17.88	78.17	64.19
R1/690	UNKNOWN	207.59	197.92	175.29	22.63	11.43	95.34	84.44
R3/690	UNKNOWN	80.42	63.71	63.71	0.00	0.00	79.22	79.22
R1/691	UNKNOWN	192.78	189.98	154.58	35.39	18.63	98.55	80.19
R1/692	UNKNOWN	179.27	167.24	155.69	11.55	6.91	93.29	86.85
790 HIGH ROAD								
R1/660	UNKNOWN	116.97	114.66	82.09	32.57	28.41	98.03	70.18
R2/660	UNKNOWN	86.58	82.91	47.72	35.19	42.44	95.77	55.12
R3/660	UNKNOWN	107.52	106.14	68.94	37.20	35.05	98.71	64.11
R4/660	UNKNOWN	160.76	121.07	80.75	40.31	33.30	75.31	50.23
R1/661	UNKNOWN	116.97	114.67	82.91	31.76	27.70	98.04	70.88
R2/661	UNKNOWN	86.58	82.50	47.82	34.68	42.04	95.29	55.23
R3/661	UNKNOWN	107.52	106.16	70.34	35.82	33.75	98.73	65.42
R4/661	UNKNOWN	160.76	152.37	113.76	38.61	25.34	94.78	70.77
R1/662	UNKNOWN	116.97	114.67	83.94	30.74	26.81	98.04	71.76
R2/662	UNKNOWN	86.58	82.21	48.91	33.30	40.50	94.96	56.49
R3/662	UNKNOWN	107.52	106.16	71.79	34.37	32.38	98.73	66.76
R4/662	UNKNOWN	160.76	157.00	120.10	36.90	23.50	97.66	74.71
7 WHITE HART LANE								
R1/981	UNKNOWN	120.28	115.07	115.06	0.01	0.01	95.66	95.66
9-39 WHITE HART LANE								
R1/990	UNKNOWN	142.79	134.82	122.17	12.65	9.38	94.42	85.56
R1/991	UNKNOWN	142.79	135.83	126.04	9.80	7.21	95.13	88.27
R1/992	UNKNOWN	142.79	136.25	130.46	5.79	4.25	95.42	91.37
R1/993	UNKNOWN	142.79	137.40	134.65	2.75	2.00	96.22	94.30
8 WILLIAM STREET								
R2/970	UNKNOWN	133.49	123.35	117.86	5.49	4.45	92.40	88.29
R3/970	UNKNOWN	107.79	105.46	100.09	5.37	5.09	97.84	92.86
R4/970	UNKNOWN	139.36	129.11	114.61	14.50	11.23	92.65	82.24
R2/971	UNKNOWN	133.49	129.09	125.37	3.72	2.88	96.70	93.92
R3/971	UNKNOWN	107.79	106.27	102.97	3.30	3.11	98.60	95.53
R4/971	UNKNOWN	139.36	136.95	124.44	12.51	9.13	98.27	89.29
R2/972	UNKNOWN	133.49	130.04	128.30	1.74	1.34	97.42	96.11
R3/972	UNKNOWN	107.79	106.29	104.90	1.39	1.31	98.62	97.33
R4/972	UNKNOWN	139.36	137.37	130.46	6.91	5.03	98.57	93.61
1 MOSELLE STREET								
R1/970	UNKNOWN	163.22	137.38	118.29	19.09	13.90	84.17	72.47
R1/971	UNKNOWN	163.22	146.70	134.95	11.75	8.01	89.88	82.68
R1/972	UNKNOWN	163.22	160.50	145.99	14.51	9.04	98.34	89.45
ERMINE HOUSE								
R1/960	UNKNOWN	159.26	159.17	159.17	0.00	0.00	99.94	99.94
R2/960	UNKNOWN	126.92	126.63	126.46	0.16	0.13	99.77	99.64
R1/961	UNKNOWN	159.26	159.17	159.17	0.00	0.00	99.95	99.95
R2/961	UNKNOWN	126.92	126.63	126.47	0.16	0.13	99.77	99.64
R1/962	UNKNOWN	159.26	159.17	159.17	0.00	0.00	99.95	99.95
R2/962	UNKNOWN	126.92	126.63	126.47	0.16	0.13	99.77	99.64

ANNUAL PROBABLE SUNLIGHT HOURS (APSH)

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
3 NORTHUMBERLAND PARK										
R1/21	W1/21	UNKNOWN	25	81	23	79	2	2	8.00	2.47
R2/21	W2/21	UNKNOWN	25	81	23	79	2	2	8.00	2.47
R1/22	W1/22	UNKNOWN	28	84	28	84	0	0	0.00	0.00
R2/22	W2/22	UNKNOWN	28	84	28	84	0	0	0.00	0.00
5 NORTHUMBERLAND PARK										
R1/31	W1/31	UNKNOWN	25	80	23	78	2	2	8.00	2.50
R2/31	W2/31	UNKNOWN	24	79	22	77	2	2	8.33	2.53
R1/32	W1/32	UNKNOWN	27	83	27	83	0	0	0.00	0.00
R2/32	W2/32	UNKNOWN	28	82	28	82	0	0	0.00	0.00
7 NORTHUMBERLAND PARK										
R1/41	W1/41	UNKNOWN	25	80	23	78	2	2	8.00	2.50
R1/42	W1/42	UNKNOWN	27	82	27	82	0	0	0.00	0.00
9 NORTHUMBERLAND PARK										

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R2/41	W2/41	UNKNOWN	24	80	24	80	0	0	0.00	0.00
R2/42	W2/42	UNKNOWN	26	81	25	80	1	1	3.85	1.23
11 NORTHUMBERLAND PARK										
R3/41	W3/41	UNKNOWN	23	79	23	79	0	0	0.00	0.00
R3/42	W3/42	UNKNOWN	26	82	25	81	1	1	3.85	1.22
13 NORTHUMBERLAND PARK										
R1/51	W1/51	UNKNOWN	23	76	23	76	0	0	0.00	0.00
R2/51	W2/51	UNKNOWN	22	78	22	78	0	0	0.00	0.00
R1/52	W1/52	UNKNOWN	25	81	25	81	0	0	0.00	0.00
R2/52	W2/52	UNKNOWN	25	81	25	81	0	0	0.00	0.00
15 NORTHUMBERLAND PARK										
R3/51	W3/51	UNKNOWN	22	78	22	78	0	0	0.00	0.00
R4/51	W4/51	UNKNOWN	21	77	21	77	0	0	0.00	0.00
R3/52	W3/52	UNKNOWN	26	82	26	82	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R4/52	W4/52	UNKNOWN	25	81	25	81	0	0	0.00	0.00
17 NORTHUMBERLAND PARK										
R5/51	W5/51	UNKNOWN	21	77	21	77	0	0	0.00	0.00
R6/51	W6/51	UNKNOWN	21	77	21	77	0	0	0.00	0.00
R5/52	W5/52	UNKNOWN	25	81	25	81	0	0	0.00	0.00
R6/52	W6/52	UNKNOWN	25	81	25	81	0	0	0.00	0.00
19 NORTHUMBERLAND PARK										
R7/51	W7/51	UNKNOWN	19	74	19	74	0	0	0.00	0.00
R8/51	W8/51	UNKNOWN	19	75	19	75	0	0	0.00	0.00
R7/52	W7/52	UNKNOWN	24	80	24	80	0	0	0.00	0.00
R8/52	W8/52	UNKNOWN	24	80	24	80	0	0	0.00	0.00
21 NORTHUMBERLAND PARK										
R9/51	W9/51	UNKNOWN	20	76	20	76	0	0	0.00	0.00
R9/52	W9/52	UNKNOWN	23	79	23	79	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
23 NORTHUMBERLAND PARK										
R1/60	W1/60	UNKNOWN	11	51	11	51	0	0	0.00	0.00
R2/60	W4/60	UNKNOWN	10	43	10	43	0	0	0.00	0.00
R1/61	W1/61	UNKNOWN	17	57	17	57	0	0	0.00	0.00
R2/61	W2/61	UNKNOWN	17	58	17	58	0	0	0.00	0.00
R1/65	W1/65	UNKNOWN	9	41	9	41	0	0	0.00	0.00
R1/70	W1/70	UNKNOWN	10	41	10	41	0	0	0.00	0.00
R1/71	W1/71	UNKNOWN	13	46	13	46	0	0	0.00	0.00
19 BENNETS CLOSE										
R1/850	W1/850	UNKNOWN	12	69	12	69	0	0	0.00	0.00
R1/851	W1/851	UNKNOWN	26	83	25	82	1	1	3.85	1.20
R1/852	W1/852	UNKNOWN	29	86	29	86	0	0	0.00	0.00
9-13 BENNETS CLOSE										
R1/860	W1/860	UNKNOWN	18	75	18	75	0	0	0.00	0.00
R2/860	W8/860	UNKNOWN	19	76	19	76	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R3/860	W2/860	UNKNOWN	17	63	17	63	0	0	0.00	0.00
R3/860	W3/860	UNKNOWN	19	59	19	59	0	0	0.00	0.00
R4/860	W4/860	UNKNOWN	18	58	18	58	0	0	0.00	0.00
R5/860	W5/860	UNKNOWN	16	56	16	56	0	0	0.00	0.00
R6/860	W6/860	UNKNOWN	18	58	18	58	0	0	0.00	0.00
R6/860	W7/860	UNKNOWN	18	63	18	63	0	0	0.00	0.00
R1/861	W1/861	UNKNOWN	24	81	24	81	0	0	0.00	0.00
R2/861	W8/861	UNKNOWN	24	81	24	81	0	0	0.00	0.00
R3/861	W2/861	UNKNOWN	22	68	22	68	0	0	0.00	0.00
R3/861	W3/861	UNKNOWN	25	65	25	65	0	0	0.00	0.00
R4/861	W4/861	UNKNOWN	24	64	24	64	0	0	0.00	0.00
R5/861	W5/861	UNKNOWN	25	65	25	65	0	0	0.00	0.00
R6/861	W6/861	UNKNOWN	25	65	25	65	0	0	0.00	0.00
R6/861	W7/861	UNKNOWN	24	69	24	69	0	0	0.00	0.00
R1/862	W1/862	UNKNOWN	29	86	29	86	0	0	0.00	0.00
R2/862	W8/862	UNKNOWN	30	87	29	86	1	1	3.33	1.15
R3/862	W2/862	UNKNOWN	27	73	27	73	0	0	0.00	0.00
R3/862	W3/862	UNKNOWN	30	70	29	69	1	1	3.33	1.43

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R4/862	W4/862	UNKNOWN	29	69	28	68	1	1	3.45	1.45
R5/862	W5/862	UNKNOWN	29	69	29	69	0	0	0.00	0.00
R6/862	W6/862	UNKNOWN	29	69	29	69	0	0	0.00	0.00
R6/862	W7/862	UNKNOWN	29	74	28	73	1	1	3.45	1.35
R1/863	W1/863	UNKNOWN	30	87	30	87	0	0	0.00	0.00
R2/863	W8/863	UNKNOWN	30	87	29	86	1	1	3.33	1.15
R3/863	W2/863	UNKNOWN	28	74	28	74	0	0	0.00	0.00
R3/863	W3/863	UNKNOWN	30	70	30	70	0	0	0.00	0.00
R4/863	W4/863	UNKNOWN	30	70	29	69	1	1	3.33	1.43
R5/863	W5/863	UNKNOWN	30	70	30	70	0	0	0.00	0.00
R6/863	W6/863	UNKNOWN	30	70	30	70	0	0	0.00	0.00
R6/863	W7/863	UNKNOWN	30	75	29	74	1	1	3.33	1.33
ST FRANCAIS DE SALES RC PRIMARY SCHOOL										
R1/450	W1/450	UNKNOWN	28	84	28	77	0	7	0.00	8.33
R1/450	W2/450	UNKNOWN	28	84	28	77	0	7	0.00	8.33
R1/451	W1/451	UNKNOWN	29	84	29	78	0	6	0.00	7.14

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R1/451	W2/451	UNKNOWN	30	85	30	79	0	6	0.00	7.06
R1/455	W1/455	UNKNOWN	22	69	20	61	2	8	9.09	11.59
R1/455	W2/455	UNKNOWN	18	59	18	59	0	0	0.00	0.00
729 HIGH ROAD										
R1/460	W4/460	UNKNOWN	26	83	23	66	3	17	11.54	20.48
R1/460	W5/460	UNKNOWN	20	58	17	37	3	21	15.00	36.21
R4/460	W3/460	UNKNOWN	26	83	23	66	3	17	11.54	20.48
R5/460	W1/460	UNKNOWN	25	81	23	66	2	15	8.00	18.52
R5/460	W2/460	UNKNOWN	26	82	23	66	3	16	11.54	19.51
R1/461	W4/461	UNKNOWN	28	81	26	67	2	14	7.14	17.28
R1/461	W5/461	UNKNOWN	20	56	18	35	2	21	10.00	37.50
R2/461	W9/461	UNKNOWN	10	44	9	24	1	20	10.00	45.45
R4/461	W3/461	UNKNOWN	28	81	26	67	2	14	7.14	17.28
R5/461	W1/461	UNKNOWN	28	84	26	70	2	14	7.14	16.67
R5/461	W2/461	UNKNOWN	28	82	26	68	2	14	7.14	17.07
LIBRARY-KATHLEEN FERRIER COURT										

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R1/480	W22/480	Unknown	15	51	12	39	3	12	20.00	23.53
R1/480	W23/480	Unknown	15	53	12	40	3	13	20.00	24.53
R1/480	W24/480	Unknown	15	52	12	38	3	14	20.00	26.92
R1/480	W25/480	Unknown	15	53	12	39	3	14	20.00	26.42
R2/480	W1/480	Unknown	19	19	15	15	4	4	21.05	21.05
R2/480	W2/480	Unknown	18	18	15	15	3	3	16.67	16.67
R2/480	W3/480	Unknown	19	19	15	15	4	4	21.05	21.05
R2/480	W4/480	Unknown	17	27	13	19	4	8	23.53	29.63
R2/480	W5/480	Unknown	19	39	15	23	4	16	21.05	41.03
R2/480	W6/480	Unknown	14	36	10	19	4	17	28.57	47.22
R2/480	W7/480	Unknown	12	34	8	17	4	17	33.33	50.00
R2/480	W8/480	Unknown	8	25	4	9	4	16	50.00	64.00
R2/480	W11/480	Unknown	12	37	8	31	4	6	33.33	16.22
R1/481	W3/481	LIVINGROOM	24	81	20	70	4	11	16.67	13.58
R5/481	W1/481	LIVINGROOM	25	82	21	73	4	9	16.00	10.98
R5/481	W2/481	UNKNOWN	24	81	19	69	5	12	20.83	14.81
R1/482	W1/482	BEDROOM	29	86	25	78	4	8	13.79	9.30
R2/482	W2/482	BEDROOM	29	86	24	76	5	10	17.24	11.63
R3/482	W3/482	BEDROOM	29	86	24	76	5	10	17.24	11.63
R1/483	W3/483	LIVINGROOM	29	85	24	75	5	10	17.24	11.76
R5/483	W1/483	LIVINGROOM	29	86	25	79	4	7	13.79	8.14

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R5/483	W2/483	LIVINGROOM	29	86	24	78	5	8	17.24	9.30
R1/484	W1/484	BEDROOM	30	87	25	79	5	8	16.67	9.20
R2/484	W2/484	BEDROOM	30	86	24	77	6	9	20.00	10.47
R3/484	W3/484	BEDROOM	30	86	24	77	6	9	20.00	10.47
BERGAN-BROOKLYN APPARTMENTS										
R5/510	W10/510	UNKNOWN	15	68	11	53	4	15	26.67	22.06
R5/510	W11/510	UNKNOWN	16	71	11	54	5	17	31.25	23.94
R6/510	W9/510	UNKNOWN	11	37	11	37	0	0	0.00	0.00
R7/510	W7/510	UNKNOWN	18	53	16	42	2	11	11.11	20.75
R7/510	W8/510	UNKNOWN	15	51	13	38	2	13	13.33	25.49
R9/510	W1/510	UNKNOWN	18	62	14	54	4	8	22.22	12.90
R9/510	W2/510	UNKNOWN	17	43	15	40	2	3	11.76	6.98
R5/511	W6/511	UNKNOWN	20	75	16	61	4	14	20.00	18.67
R5/511	W7/511	UNKNOWN	20	76	15	60	5	16	25.00	21.05
R6/511	W5/511	UNKNOWN	15	41	15	41	0	0	0.00	0.00
R7/511	W3/511	UNKNOWN	21	60	17	50	4	10	19.05	16.67

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R7/511	W4/511	UNKNOWN	20	55	17	43	3	12	15.00	21.82
R9/511	W1/511	UNKNOWN	19	60	18	54	1	6	5.26	10.00
R9/511	W2/511	UNKNOWN	20	55	17	48	3	7	15.00	12.73
R5/512	W6/512	UNKNOWN	24	80	18	65	6	15	25.00	18.75
R5/512	W7/512	UNKNOWN	24	80	18	65	6	15	25.00	18.75
R6/512	W5/512	UNKNOWN	20	47	17	44	3	3	15.00	6.38
R7/512	W3/512	UNKNOWN	23	74	17	63	6	11	26.09	14.86
R7/512	W4/512	UNKNOWN	25	78	19	65	6	13	24.00	16.67
R9/512	W1/512	UNKNOWN	20	73	19	67	1	6	5.00	8.22
R9/512	W2/512	UNKNOWN	22	75	20	70	2	5	9.09	6.67
R5/513	W6/513	UNKNOWN	26	82	20	69	6	13	23.08	15.85
R5/513	W7/513	UNKNOWN	26	83	20	69	6	14	23.08	16.87
R6/513	W5/513	UNKNOWN	20	47	17	44	3	3	15.00	6.38
R7/513	W3/513	UNKNOWN	24	75	20	67	4	8	16.67	10.67
R7/513	W4/513	UNKNOWN	25	75	20	66	5	9	20.00	12.00
R9/513	W1/513	UNKNOWN	22	74	20	67	2	7	9.09	9.46
R9/513	W2/513	UNKNOWN	23	74	20	68	3	6	13.04	8.11

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
783 HIGH ROAD										
R1/563	W1/563	UNKNOWN	1	8	1	8	0	0	0.00	0.00
R1/564	W1/564	UNKNOWN	1	12	1	12	0	0	0.00	0.00
R1/565	W1/565	UNKNOWN	28	82	23	75	5	7	17.86	8.54
793-795 HIGH ROAD (BANK)										
R1/571	W3/571	UNKNOWN	25	82	22	79	3	3	12.00	3.66
R2/571	W7/571	UNKNOWN	14	48	11	45	3	3	21.43	6.25
R3/571	W8/571	UNKNOWN	13	47	11	45	2	2	15.38	4.26
R3/571	W9/571	UNKNOWN	14	48	11	45	3	3	21.43	6.25
R4/571	W4/571	UNKNOWN	25	82	23	80	2	2	8.00	2.44
R4/571	W5/571	UNKNOWN	19	63	17	61	2	2	10.53	3.17
R4/571	W6/571	UNKNOWN	14	49	11	46	3	3	21.43	6.12
R5/571	W1/571	UNKNOWN	26	85	23	82	3	3	11.54	3.53
R5/571	W2/571	UNKNOWN	25	84	22	81	3	3	12.00	3.57
R1/572	W3/572	UNKNOWN	29	86	26	83	3	3	10.34	3.49
R2/572	W7/572	UNKNOWN	15	49	11	45	4	4	26.67	8.16

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R3/572	W8/572	UNKNOWN	14	48	11	45	3	3	21.43	6.25
R3/572	W9/572	UNKNOWN	15	49	12	46	3	3	20.00	6.12
R4/572	W4/572	UNKNOWN	30	87	26	83	4	4	13.33	4.60
R4/572	W5/572	UNKNOWN	22	66	19	63	3	3	13.64	4.55
R4/572	W6/572	UNKNOWN	15	48	11	44	4	4	26.67	8.33
R5/572	W1/572	UNKNOWN	30	86	27	83	3	3	10.00	3.49
R5/572	W2/572	UNKNOWN	30	85	27	82	3	3	10.00	3.53
R1/573	W1/573	UNKNOWN	29	84	27	82	2	2	6.90	2.38
R2/573	W2/573	UNKNOWN	30	89	28	87	2	2	6.67	2.25
R3/573	W3/573	UNKNOWN	29	84	27	82	2	2	6.90	2.38
R3/573	W4/573	UNKNOWN	24	70	22	68	2	2	8.33	2.86
R3/573	W5/573	UNKNOWN	15	50	13	48	2	2	13.33	4.00
R4/573	W6/573	UNKNOWN	15	50	13	48	2	2	13.33	4.00
797 HIGH ROAD										
R1/581	W1/581	UNKNOWN	13	47	11	45	2	2	15.38	4.26
R2/581	W2/581	UNKNOWN	13	46	11	44	2	2	15.38	4.35
R1/582	W1/582	UNKNOWN	15	49	12	46	3	3	20.00	6.12
R2/582	W2/582	UNKNOWN	15	50	13	48	2	2	13.33	4.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
799 HIGH ROAD										
R1/591	W1/591	UNKNOWN	12	45	11	44	1	1	8.33	2.22
R2/591	W2/591	UNKNOWN	13	46	12	45	1	1	7.69	2.17
R1/592	W1/592	UNKNOWN	15	49	13	47	2	2	13.33	4.08
R2/592	W2/592	UNKNOWN	15	49	13	47	2	2	13.33	4.08
801 HIGH ROAD										
R1/601	W1/601	UNKNOWN	12	45	11	44	1	1	8.33	2.22
R2/601	W2/601	UNKNOWN	12	45	12	45	0	0	0.00	0.00
R1/602	W1/602	UNKNOWN	14	47	12	45	2	2	14.29	4.26
R2/602	W2/602	UNKNOWN	14	47	12	45	2	2	14.29	4.26
803 HIGH ROAD										
R3/601	W3/601	UNKNOWN	9	39	8	38	1	1	11.11	2.56
R3/601	W4/601	UNKNOWN	12	45	11	44	1	1	8.33	2.22
R4/601	W5/601	UNKNOWN	12	45	12	45	0	0	0.00	0.00
R4/601	W6/601	UNKNOWN	12	45	12	45	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R3/602	W3/602	UNKNOWN	10	40	8	38	2	2	20.00	5.00
R3/602	W4/602	UNKNOWN	12	45	10	43	2	2	16.67	4.44
R4/602	W5/602	UNKNOWN	13	46	12	45	1	1	7.69	2.17
R4/602	W6/602	UNKNOWN	14	47	12	45	2	2	14.29	4.26
805 HIGH ROAD										
R5/601	W7/601	UNKNOWN	12	45	12	45	0	0	0.00	0.00
R5/601	W8/601	UNKNOWN	12	45	12	45	0	0	0.00	0.00
R5/602	W7/602	UNKNOWN	12	45	10	43	2	2	16.67	4.44
R5/602	W8/602	UNKNOWN	14	48	12	46	2	2	14.29	4.17
807 HIGH ROAD										
R1/611	W1/611	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R1/611	W2/611	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R2/611	W3/611	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R3/611	W4/611	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R3/611	W5/611	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R1/612	W1/612	Bedroom	10	44	9	43	1	1	10.00	2.27
R2/612	W2/612	Bedroom	14	48	13	47	1	1	7.14	2.08
809 HIGH ROAD										

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R1/621	W1/621	UNKNOWN	13	46	13	46	0	0	0.00	0.00
R1/621	W2/621	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R1/621	W3/621	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R2/621	W4/621	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R2/621	W5/621	UNKNOWN	12	45	12	45	0	0	0.00	0.00
R1/622	W1/622	Bedroom	8	36	8	36	0	0	0.00	0.00
R2/622	W2/622	Bedroom	8	36	8	36	0	0	0.00	0.00
813 HIGH ROAD										
R1/631	W1/631	UNKNOWN	12	47	12	47	0	0	0.00	0.00
R1/631	W2/631	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R1/632	W1/632	UNKNOWN	12	47	12	47	0	0	0.00	0.00
R1/632	W2/632	UNKNOWN	12	47	12	47	0	0	0.00	0.00
815 HIGH ROAD										
R2/631	W3/631	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R2/631	W4/631	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R2/632	W3/632	UNKNOWN	12	46	12	46	0	0	0.00	0.00
R2/632	W4/632	UNKNOWN	12	46	12	46	0	0	0.00	0.00
817 HIGH ROAD										
R3/631	W5/631	UNKNOWN	12	46	12	46	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R3/632	W5/632	UNKNOWN	12	46	12	46	0	0	0.00	0.00
819 HIGH ROAD										
R1/640	W11/640	UNKNOWN	12	43	12	43	0	0	0.00	0.00
R1/641	W1/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
R1/641	W2/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
R2/641	W3/641	Bedroom	8	39	8	39	0	0	0.00	0.00
R2/641	W4/641	Bedroom	8	39	8	39	0	0	0.00	0.00
R1/642	W1/642	UNKNOWN	13	48	13	48	0	0	0.00	0.00
R1/642	W2/642	UNKNOWN	14	49	14	49	0	0	0.00	0.00
R2/642	W3/642	Bedroom	9	40	9	40	0	0	0.00	0.00
R2/642	W4/642	Bedroom	9	40	9	40	0	0	0.00	0.00
821 HIGH ROAD										
R3/641	W5/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
R3/641	W6/641	UNKNOWN	14	49	14	49	0	0	0.00	0.00
R3/642	W5/642	UNKNOWN	13	48	13	48	0	0	0.00	0.00
R3/642	W6/642	UNKNOWN	13	48	13	48	0	0	0.00	0.00
823 HIGH ROAD										

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R4/641	W7/641	UNKNOWN	14	48	14	48	0	0	0.00	0.00
R4/641	W8/641	UNKNOWN	14	48	14	48	0	0	0.00	0.00
R5/641	W9/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
R5/641	W10/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
R6/641	W11/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
R6/641	W12/641	UNKNOWN	13	47	13	47	0	0	0.00	0.00
825 HIGH ROAD										
R1/651	W1/651	UNKNOWN	13	49	13	49	0	0	0.00	0.00
R1/651	W2/651	UNKNOWN	13	49	13	49	0	0	0.00	0.00
814 HIGH ROAD										
R1/820	W1/820	UNKNOWN	9	28	7	26	2	2	22.22	7.14
R1/821	W1/821	UNKNOWN	12	46	10	44	2	2	16.67	4.35
R1/821	W2/821	UNKNOWN	9	42	7	40	2	2	22.22	4.76
R2/821	W3/821	UNKNOWN	12	47	10	45	2	2	16.67	4.26
R2/821	W4/821	UNKNOWN	12	47	10	45	2	2	16.67	4.26
R1/831	W3/831	UNKNOWN	13	47	11	45	2	2	15.38	4.26
R1/831	W4/831	UNKNOWN	0	10	0	10	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R2/831	W2/831	UNKNOWN	20	74	17	71	3	3	15.00	4.05
R3/831	W1/831	UNKNOWN	20	71	17	68	3	3	15.00	4.23
R4/831	W5/831	UNKNOWN	0	10	0	10	0	0	0.00	0.00
806b HIGH ROAD										
R1/770	W1/770	UNKNOWN	12	60	11	59	1	1	8.33	1.67
R1/771	W5/771	UNKNOWN	19	73	17	71	2	2	10.53	2.74
R1/771	W6/771	UNKNOWN	20	74	19	73	1	1	5.00	1.35
R2/771	W3/771	UNKNOWN	17	71	17	71	0	0	0.00	0.00
R2/771	W4/771	UNKNOWN	18	72	16	70	2	2	11.11	2.78
R3/771	W1/771	UNKNOWN	18	71	15	68	3	3	16.67	4.23
R3/771	W2/771	UNKNOWN	20	74	18	72	2	2	10.00	2.70
804 HIGH ROAD										
R1/761	W1/761	UNKNOWN	15	64	11	60	4	4	26.67	6.25
R1/761	W2/761	UNKNOWN	15	66	12	63	3	3	20.00	4.55
800 HIGH ROAD										
R1/710	W1/710	UNKNOWN	0	5	0	5	0	0	0.00	0.00

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
R1/710	W2/710	UNKNOWN	1	21	0	19	1	2	100.00	9.52
796 HIGH ROAD										
R1/694	W1/694	UNKNOWN	9	40	0	25	9	15	100.00	37.50
R1/694	W2/694	UNKNOWN	15	53	5	33	10	20	66.67	37.74
794 HIGH ROAD										
R1/690	W1/690	UNKNOWN	2	35	0	23	2	12	100.00	34.29
792 HIGH ROAD										
R1/670	W1/670	UNKNOWN	21	66	7	29	14	37	66.67	56.06
R2/670	W2/670	UNKNOWN	23	75	9	36	14	39	60.87	52.00
R2/670	W3/670	UNKNOWN	24	77	10	37	14	40	58.33	51.95
R1/671	W1/671	UNKNOWN	23	75	8	39	15	36	65.22	48.00
R2/671	W3/671	UNKNOWN	27	83	12	44	15	39	55.56	46.99
R2/671	W4/671	UNKNOWN	27	84	12	44	15	40	55.56	47.62
R3/671	W2/671	UNKNOWN	24	78	9	40	15	38	62.50	48.72

Room	Window	Room Use	Existing Winter APSH	Existing Annual APSH	Proposed Winter APSH	Proposed Annual APSH	Winter Loss	Annual Loss	Winter %Loss	Annual %Loss
ERMINE HOUSE										
R1/960	W3/960	UNKNOWN	27	80	24	73	3	7	11.11	8.75
R1/961	W3/961	UNKNOWN	28	82	24	74	4	8	14.29	9.76
R1/962	W3/962	UNKNOWN	30	84	25	76	5	8	16.67	9.52